

WAREHOUSE INTERIOR FINISH NOTES

Rev. 8-31-2015

ALTERNATES OF EQUAL VALUE ARE ACCEPTABLE, EXCEPT FOR THE FOLLOWING ITEMS:
 (1) PAINT.
 (2) FLOOR TILE.
 (3) ACOUSTIC CEILING.
 ALL INTERIOR AND EXTERIOR PAINT SHALL BE FURNISHED BY CONTRACTOR. S.W. = SHERWIN-WILLIAMS PAINTS.
 ALL GYPSUM BOARD WALLS AND CEILINGS TO BE SMOOTH FINISHED TO A LEVEL 4, PRIOR TO PAINTING.
 ALL FLOOR COVERING MATERIALS, AS WELL AS VINYL COVE BASE, SHALL BE FURNISHED BY CONTRACTOR.

PAINT SCHEDULE:
 1. CUSTOMER AREA, RESTROOMS AND OFFICE AREA:
 A. ALL WALLS TO RECEIVE PRIME COAT IF NEEDED, PRO-MAR 400 TO BE USED ON ALL NEW DRYWALL SURFACES PRIOR TO PAINTING.
 B. WALLS, IF DRYWALL, SHALL RECEIVE AS MANY COATS AS NEEDED FOR A GOOD FINISH. MINIMUM TWO COATS OF S.W. #6099, SAND DOLLAR, (EGG-SHELL).
 C. PROVIDE ONE ACCENT WALL IN EACH OFFICE. THIS WALL IS LABELED "ACCENT WALL" ON THE ENLARGED PARTIAL FLOOR PLAN, SHEET A1.2. MINIMUM TWO COATS OF SW #6102 PORTABELLA, (EGG-SHELL).
 D. DOOR FRAMES AND ANY RELATED WINDOW KITS ARE TO RECEIVE AS MANY COATS AS NEEDED FOR A GOOD FINISH. MINIMUM TWO COATS OF S.W. #6041 "OTTIER" (SEMI-GLOSS). DOORS TO BE PRE-FINISHED, LIGHT OAK OR GOLDEN OAK STAINED AND ONE COAT OF POLYURETHANE.
 E. CEILINGS, IF DRY WALL, SHALL RECEIVE A MINIMUM OF 2 FINISH COATS OF S.W. #4000, PURE WHITE, (EGG-SHELL).
 F. ALL WOOD WALL TRIM ON WAREHOUSE PERIMETER WALL TO BE PAINTED S.W. #6099, SAND DOLLAR (SEMI-GLOSS).

ACOUSTIC CEILING SYSTEM:
 1. STANDARD WHITE GRID IN A 2'x4' PATTERN IN ALL ROOMS SHOWN AT 10'-0" AFF.
 2. ACOUSTIC CEILING TILE TO BE ARMSTRONG DUNE SQUARE EDGE #1772.

LAMINATE SURFACES:
 1. ALL COUNTERTOPS - WILSONART #4846-60, MORRO ZEPHYR. FRONT OUTSIDE CORNERS TO BE 2" RADIUS PROVIDE 2" HOLES AND GROMMETS FOR POWER AND DATA WIRES. SEE MILLWORK DETAILS.
 2. PLASTIC LAMINATE CABINETS AND MILLWORK - WILSONART #4624-60, BEIGE NEBULA.

FLOOR FINISH SCHEDULE:
 1. CERAMIC TILE - DAL-TILE, "TRUFFLE FIELD" #5093. USE SAME 18"x18" TILE ON WALLS. AT BASE START WITH 6" PIECE OF CUT TILE, THEN THREE (3) COURSES TO 5'-0" A.F.F. PROVIDE 3"x12" BULLNOSE CAP SO TOP OF TILE WILL BE 5'-3" A.F.F. USE GROUT: MAFI TYPE S, #42 "MOCHA". ALTERNATE CERAMIC TILE IS "INTERCERAMIC", "HIGHLANDS", 18" x18" "SKYE".
 2. VCT (VINYL COMPOSITION TILE) TO BE ARMSTRONG EXCELOX, #5181, "ANTIQUÉ WHITE".
 3. 4" VINYL COVE BASE: JOHNSONITE 47, "BROWN" AT CARPETED, TILED, AND VCT AREAS. DO NOT PROVIDE VINYL BASE IN RESTROOMS WHERE THERE IS A CERAMIC TILE WAINSCOT.
 4. USE S-726 COVE BASE ADHESIVE.
 5. TRANSITION STRIP: PROVIDE WHERE NO THRESHOLD EXISTS AND TILE ENDS.
 6. CARPET TO BE PHILADELPHIA "ON DEMAND OVERDRIVE" #00103.

RESTROOM PARTITIONS:
 PRE-MANUFACTURED METAL PARTITIONS TO BE "HADRIAN" BRAND, STYLE TO BE SUPPORTED FROM THE FLOOR WITH HEAD RAILS. POWDER COATED TOILET PARTITIONS. COLOR: "SAHARA 585"

CHAIR RAIL:
 PROVIDE CHAIR RAIL AT CONFERENCE ROOM AND CUSTOMER WAITING. CENTER AT 33-1/2" A.F.F. IN CUSTOMER WAITING, CENTER AT 28-1/2" A.F.F. IN CONFERENCE ROOM. MANUFACTURE TO BE INPROCOOP. #1400 WALL GUARD WITH END CAPS. COLOR TO BE "ANTIQUÉ WHITE", #0104.

CORNER GUARDS:
 PROVIDE CORNER GUARDS ON ALL INTERIOR OUTSIDE WALL CORNERS. MANUFACTURER TO BE INPROCOOP #160N, BLISSCOE CORNER GUARDS, 48" HEIGHT WITH 2" WINGS. COLOR TO BE "ANTIQUÉ WHITE", #0104.

FIBERGLASS REINFORCED PANELS:
 FIBERGLASS REINFORCED PANELS TO BE LIGHT GRAY IN COLOR AND GO FROM FLOOR TO CEILING IN EMPLOYEE RESTROOM AND FLOOR TO 48" A.F.F. IN BREAK ROOM.

SOLAR WINDOW SHADES:
 PROVIDE SOLAR WINDOW SHADES ON ALL WINDOWS. MANUFACTURER TO BE "DRAPER". FABRIC - SHEARWEAVER BY PHFER - STOCK # SW2100. COLOR - "BONE" SW 2000. GREENGUARD PRODUCT - 90% UV BLOCKAGE. WEIGHT - 14.26 OZ/YD MESH HEIGHT. HEAD CASSETTE TO HAVE MATCHING VALANCE. PROVIDE WITH STAINLESS STEEL PULL CHAIN.

HARDWARE SETS

HARDWARE SET A - (OFFICE DOORS, SUPPLY ROOMS)
 3/0 X 7/0 KD HM FRAME
 3/0 X 7/0 SC WOOD DOOR
 3 EA. HINGES
 1 EA. LOCKSET LEVER HANDLE SET
 1 EA. FLOOR DOME STOP

HARDWARE SET B - (CONFERENCE / TRAINING DOORS)
 3/0 X 7/0 KD HM FRAME FOR 4-7/8" WALLS
 3/0 X 7/0 SC WOOD DOOR WITH 24" X 33" WINDOW KIT
 3 EA. HINGES
 1 EA. LOCKSET LEVER HANDLE SET
 1 EA. FLOOR DOME STOP
 1 EA. 1/2 LITE 24" X 24" WINDOW KIT

HARDWARE SET C - (BREAK ROOM DOORS)
 3/0 X 7/0 KD HM FRAME FOR 4-7/8" WALLS
 3/0 X 7/0 SC WOOD DOOR WITH 24" X 33" WINDOW KIT
 3 EA. HINGES
 1 EA. PUSH-PULL HANDLE SET
 1 EA. CLOSER
 1 EA. 10" X 34" KICK PLATE
 1 EA. FLOOR DOME STOP

HARDWARE SET D - (DATA / PHONE DOORS)
 3/0 X 7/0 KD HM FRAME FOR 4-7/8" WALL
 3/0 X 7/0 SC WOOD DOOR
 3 EA. HINGES
 1 EA. LOCKSET LEVER HANDLE SET
 1 EA. CLOSER
 1 EA. 10" X 34" KICK PLATE
 1 EA. FLOOR DOME STOP
 1 EA. 12" X 24" TWO SIDED GRILL

HARDWARE SET E - (RESTROOM DOORS, MULTIPLE USE)
 3/0 X 7/0 KD HM FRAME
 3/0 X 7/0 SC WOOD DOOR
 3 EA. HINGES
 1 EA. PUSH-PULL HANDLE SET
 1 EA. CLOSER
 1 EA. 10" X 34" KICK PLATE
 1 EA. FLOOR DOME STOP

HARDWARE SET F - (RESTROOM DOORS, SINGLE USE)
 3/0 X 7/0 KD HM FRAME
 3/0 X 7/0 SC WOOD DOOR
 3 EA. HINGES
 1 EA. PRIVACY LEVER HANDLE SET
 1 EA. CLOSER
 1 EA. 10" X 34" KICK PLATE
 1 EA. FLOOR DOME STOP

HARDWARE SET G - (RESTROOM DOORS, MULTIPLE USE)
 3/0 X 7/0 KD HM FRAME FOR 7-1/4" WALLS
 3/0 X 7/0 SC WOOD DOOR WITH 24" X 33" WINDOW KIT
 3 EA. HINGES
 1 EA. PUSH-PULL HANDLE SET
 1 EA. CLOSER
 1 EA. 10" X 34" KICK PLATE
 1 EA. FLOOR DOME STOP

HARDWARE SET H - (RESTROOM DOORS, SINGLE USE)
 3/0 X 7/0 KD HM FRAME FOR 7-1/4" WALLS RATED 45 MINS.
 3/0 X 7/0 SC 45 MIN RATED WOOD DOOR WITH 1/4 LIGHT WINDOW KIT
 3 EA. HINGES
 1 EA. PUSH-PULL HANDLE SET
 1 EA. CLOSER
 1 EA. 10" X 34" KICK PLATE
 1 EA. FLOOR DOME STOP

ROOM FINISH SCHEDULE

MK.	ROOM NAME	FLOOR	BASE	WALL	CEILING	CLG. HT.	MK.	REMARKS
101	CUSTOMER WAITING	18" X 18" CERAMIC TILE W/7/8" GROUT JOINTS	VCT	CERAMIC TILE - POLISHED CONCRETE	EXISTING	10'-0"	101	
102	CUSTOMER RESTROOM	18" X 18" CERAMIC TILE W/7/8" GROUT JOINTS	EXISTING CONCRETE	CERAMIC TILE - POLISHED CONCRETE	EXISTING	10'-0"	102	
103	OPEN OFFICE	18" X 18" CERAMIC TILE W/7/8" GROUT JOINTS	1" X 4" WOOD	CERAMIC TILE - POLISHED CONCRETE	EXISTING	10'-0"	103	
104	OFFICE	18" X 18" CERAMIC TILE W/7/8" GROUT JOINTS	RUBBER	CERAMIC TILE - POLISHED CONCRETE	EXISTING	10'-0"	104	
105	OFFICE	18" X 18" CERAMIC TILE W/7/8" GROUT JOINTS	NONE	CERAMIC TILE - POLISHED CONCRETE	EXISTING	10'-0"	105	
106	SUPPLIES	18" X 18" CERAMIC TILE W/7/8" GROUT JOINTS	1" X 4" WOOD	CERAMIC TILE - POLISHED CONCRETE	EXISTING	10'-0"	106	
107	SPRINKLER ROOM	18" X 18" CERAMIC TILE W/7/8" GROUT JOINTS	RUBBER	CERAMIC TILE - POLISHED CONCRETE	EXISTING	10'-0"	107	
108	PHONE / DATA	18" X 18" CERAMIC TILE W/7/8" GROUT JOINTS	NONE	CERAMIC TILE - POLISHED CONCRETE	EXISTING	10'-0"	108	
109	HALL	18" X 18" CERAMIC TILE W/7/8" GROUT JOINTS	1" X 4" WOOD	CERAMIC TILE - POLISHED CONCRETE	EXISTING	10'-0"	109	
110	BREAK ROOM	18" X 18" CERAMIC TILE W/7/8" GROUT JOINTS	1" X 4" WOOD	CERAMIC TILE - POLISHED CONCRETE	EXISTING	10'-0"	110	
111	WOMEN	18" X 18" CERAMIC TILE W/7/8" GROUT JOINTS	1" X 4" WOOD	CERAMIC TILE - POLISHED CONCRETE	EXISTING	10'-0"	111	
112	JANITOR CLOSET	18" X 18" CERAMIC TILE W/7/8" GROUT JOINTS	1" X 4" WOOD	CERAMIC TILE - POLISHED CONCRETE	EXISTING	10'-0"	112	
113	MEN	18" X 18" CERAMIC TILE W/7/8" GROUT JOINTS	1" X 4" WOOD	CERAMIC TILE - POLISHED CONCRETE	EXISTING	10'-0"	113	
114	HALL	18" X 18" CERAMIC TILE W/7/8" GROUT JOINTS	1" X 4" WOOD	CERAMIC TILE - POLISHED CONCRETE	EXISTING	10'-0"	114	
115	CONFERENCE ROOM	18" X 18" CERAMIC TILE W/7/8" GROUT JOINTS	1" X 4" WOOD	CERAMIC TILE - POLISHED CONCRETE	EXISTING	10'-0"	115	
116	IN-SHOP AREA	18" X 18" CERAMIC TILE W/7/8" GROUT JOINTS	1" X 4" WOOD	CERAMIC TILE - POLISHED CONCRETE	EXISTING	16'-0"-17'-0"	116	
117	WAREHOUSE	18" X 18" CERAMIC TILE W/7/8" GROUT JOINTS	1" X 4" WOOD	CERAMIC TILE - POLISHED CONCRETE	EXISTING	16'-0"-17'-0"	117	
118	RECEIVING	18" X 18" CERAMIC TILE W/7/8" GROUT JOINTS	1" X 4" WOOD	CERAMIC TILE - POLISHED CONCRETE	EXISTING	16'-0"-17'-0"	118	
119	CUSTOMER WAITING	18" X 18" CERAMIC TILE W/7/8" GROUT JOINTS	1" X 4" WOOD	CERAMIC TILE - POLISHED CONCRETE	EXISTING	10'-0"	119	

DOOR & FRAME SCHEDULE

DOOR NO.	ROOM NAME	DOOR						FRAME				HWDR SET	DOOR NO.	REMARKS
		SIZE	TYPE	MAT'L	FINISH SIDE "A"	FINISH SIDE "B"	TYPE	MAT'L	FINISH	WIDTH				
1	EXTERIOR / CUST. WAITING 101	3'x7'-0"	C	AL	EXISTING	EXISTING	2	AL	MATCH EXISTING	MATCH EXISTING	4 7/8"	F	1	PROVIDE ALUMINUM AND FULL GLASS DOOR AND FRAME.
2	CUSTOMER RESTROOM	3'x7'-0"	A	WD	PRE-FIN.	PRE-FIN.	1	HM	PAINT	PAINT	4 7/8"	F	2	
3	CUST. WAITING 101 / OPEN OFFICE	3'x7'-0"	B	WD	PRE-FIN.	PRE-FIN.	1	HM	WHITE	PAINT	4 7/8"	G	3	
4A	VESTIBULE / CUSTOMER WAITING	3'x7'-0"	C	AL	MATCH EXISTING	MATCH EXISTING	2	AL	MATCH EXISTING	MATCH EXISTING	4 7/8"	G	4A	PROVIDE ALUMINUM AND FULL GLASS DOOR AND FRAME W/LOCKSET & CLOSER
4B	OPEN OFFICE 103 / IN-SHOP AREA	3'x7'-0"	B	WD	PRE-FIN.	PRE-FIN.	1	HM	PAINT	PAINT	7 1/4"	A	4B	45 MIN DOOR & FRAME.
5	OFFICE 104 / OPEN OFFICE 103	3'x7'-0"	A	WD	PRE-FIN.	PRE-FIN.	1	HM	PAINT	PAINT	4 7/8"	A	5	
6	OFFICE 105 / OPEN OFFICE 103	3'x7'-0"	A	WD	PRE-FIN.	PRE-FIN.	1	HM	PAINT	PAINT	4 7/8"	A	6	
7	HALL 109 / SUPPLIES 106	3'x7'-0"	A	WD	PRE-FIN.	PRE-FIN.	1	HM	PAINT	PAINT	4 7/8"	A	7	
8	EXTERIOR / SPRINKLER ROOM 107	3'x7'-0"	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	8	
9	SPRINKLER ROOM / HALL 109	3'x7'-0"	A	WD	PRE-FIN.	PRE-FIN.	1	HM	PAINT	PAINT	4 7/8"	D	9	EXISTING OWNER FINISHED/CONTIGUOUS INSTALLER
10	PHONE, DATA 108 / HALL 109	3'x7'-0"	A	WD	PRE-FIN.	PRE-FIN.	1	HM	PAINT	PAINT	4 7/8"	D	10	
11	BREAK ROOM 110 / HALL 109	3'x7'-0"	B	WD	PRE-FIN.	PRE-FIN.	1	HM	PAINT	PAINT	4 7/8"	C	11	
12	WOMEN 111 / HALL 114	3'x7'-0"	A	WD	PRE-FIN.	PRE-FIN.	1	HM	PAINT	PAINT	4 7/8"	E	12	
13	JANITOR CLOSET 112 / HALL 114	3'x7'-0"	A	WD	PRE-FIN.	PRE-FIN.	1	HM	PAINT	PAINT	4 7/8"	A	13	
14	MEN 113 / HALL 114	3'x7'-0"	A	WD	PRE-FIN.	PRE-FIN.	1	HM	PAINT	PAINT	4 7/8"	E	14	
15	CONF., TRAINING 115 / HALL 114	3'x7'-0"	B	WD	PRE-FIN.	PRE-FIN.	1	HM	PAINT	PAINT	4 7/8"	B	15	
16	HALL 114 / WAREHOUSE 117	3'x7'-0"	D	WD	PRE-FIN.	PRE-FIN.	1	HM	PAINT	PAINT	7 1/4"	G	16	45 MIN DOOR & FRAME.
17	EXTERIOR / VESTIBULE	3'x7'-0"	C	AL	MATCH EXISTING	MATCH EXISTING	2	AL	MATCH EXISTING	MATCH EXISTING	4 7/8"	F	17	PROVIDE ALUMINUM AND FULL GLASS DOOR AND FRAME W/LOCKSET & CLOSER
18	EXTERIOR / IN-SHOP AREA	14'x14'-0"	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	18	PROVIDE DOOR OPERATOR
19	EXTERIOR / IN-SHOP AREA	14'x14'-0"	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	19	PROVIDE DOOR OPERATOR
20	EXTERIOR / WAREHOUSE 117	3'x7'-0"	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	20	
21	EXTERIOR / WAREHOUSE 117	3'x7'-0"	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	21	
22	EXTERIOR / WAREHOUSE 117	3'x7'-0"	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	22	
23	EXTERIOR / WAREHOUSE 117	3'x7'-0"	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	23	
24	EXTERIOR / WAREHOUSE 117	14'x14'-0"	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	24	
25	EXTERIOR / WAREHOUSE 117	14'x14'-0"	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	25	
26	EXTERIOR / WAREHOUSE 117	3'x7'-0"	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	26	
27	EXTERIOR / WAREHOUSE 117	3'x7'-0"	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	27	
28	EXTERIOR / WAREHOUSE 117	3'x7'-0"	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	28	
29	EXTERIOR / WAREHOUSE 117	3'x7'-0"	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	29	
30	EXTERIOR / WAREHOUSE 117	14'x14'-0"	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	30	PROVIDE DOOR OPERATOR
31	EXTERIOR / WAREHOUSE 117	14'x14'-0"	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	31	PROVIDE DOOR OPERATOR
32	EXTERIOR / WAREHOUSE 117	3'x7'-0"	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	32	
33	EXTERIOR / WAREHOUSE 117	3'x7'-0"	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	33	
34	EXTERIOR / WAREHOUSE 117	8'x10'-0"	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	34	
35	EXTERIOR / RECEIVING 118	3'x7'-0"	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	35	
36	EXTERIOR / WAREHOUSE 117	3'x7'-0"	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	36	
37	EXTERIOR / WAREHOUSE 117	14'x14'-0"	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	37	
38	EXTERIOR / WAREHOUSE 117	14'x14'-0"	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	38	
39	EXTERIOR / WAREHOUSE 117	3'x7'-0"	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	39	

HARDWARE NOTE:

ALL HARDWARE MUST MEET REQUIREMENTS OF THE LATEST "ADA" GUIDELINES AND ALL LOCAL CODES. THE MOST STRINGENT CODE SHALL PREVAIL.

FINISHES NOTE:

FINISH MATERIALS ON THE WALLS, FLOORS AND CEILINGS, SHALL NOT EXCEED THE FLAME SPREAD CLASSIFICATIONS PER CODE.

RESTROOM ACCESSORIES

TOILET PAPER DISPENSER:
 "BORRICK" B-265 STAINLESS STEEL SURFACE MOUNT. PROVIDE (1) ONE PER UNISEX RESTROOM, (1) ONE PER STALL AT MULTI-USE RESTROOMS. MOUNTING HEIGHT IS 19" A.F.F. TO CENTERLINE. MAX 48" A.F.F.

SANITARY NAPKIN DISPOSAL:
 "BORRICK" B-270 CONTURA SERIES (OR EQUAL) STAINLESS STEEL SURFACE MOUNT. PROVIDE (1) ONE PER UNISEX RESTROOM, (1) ONE PER STALL AT WOMEN'S MULTI-USE RESTROOMS. MOUNTING HEIGHT - 37" A.F.F. TO BOTTOM OF UNIT.

COAT HOOK:
 STAINLESS STEEL SURFACE MOUNT. PROVIDE (1) ONE PER UNISEX RESTROOM DOOR, (1) ONE PER STALL DOOR AT MULTI-USE RESTROOMS. MOUNTING HEIGHT IS 48" A.F.F. (MAX).

HAND DRYER:
 CHROME SURFACE MOUNT. PROVIDE (1) ONE PER RESTROOM. DRYER TO BE CHROME XELATOR MODEL XL-C-1-IN. PROVIDE REQUIRED ELECTRICAL FEED. MOUNT PER MANUFACTURERS RECOMMENDATIONS. MOUNTING HEIGHT 57" A.F.F. TO BOTTOM.