Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 03/03/15

CONCRETE MASONRY LINTEL SCHEDULE

MASONRY OPENING	SIZE	BEARING
4'-10" OR LESS	L4x3 1/2x5/16 (LLV)	8" MIN. ON SGMU
4'-10" TO 7'-0"	L5x3 1/2x5/16 (LLV)	8" MIN. ON SGMU
7'-0" TO 9'-0"	L6x3 1/2x3/8 (LLV)	8" MIN. ON SGMU

NOTES:

1. ONE ANGLE REQUIRED FOR EVERY 4" OF MASONRY.
2. MULTIPLE ANGLES SHALL BE WELDED BACK TO BACK.
3. "SGMU" INDICATES SOLID GROUTED MASONRY UNIT.
4. LINTEL FOR EXTERIOR MASONRY SHALL BE HOT-DIPPED GALVANIZED.

3 PARTIAL SECTION
SCALE: 3/8" = 1'-0"

4 STAIR DETAIL
SCALE: 3/4" = 1'-0"

4 FOUNDATION DETAIL
SCALE: 1 1/2" = 1'-0"

1 BUILDING SECTION
SCALE: 3/8" = 1'-0"

2 WALL SECTION
SCALE: 3/8" = 1'-0"

HARRIMAN
AUBURN PORTLAND MANCHESTER

LEPAGE BAKERIES
COUNTRY KITCHEN
BAKERY OUTLET
DISTRIBUTION
CENTER
276 WARREN AVE.
PORTLAND, MAINE

Harriman Project No.	14558

Key Plan
Proj North

Issues and Revisions

Mark	Date	Description
--	12-31-14	CONTRACTOR REVIEW
--	01-23-15	ISSUED FOR 100% REVIEW
--	01-30-15	ISSUED FOR CONSTRUCTION

LICENSED ARCHITECT
JUDY L. JOHNSENHAUSER
No. 2080
STATE OF MAINE

Drawing Scales	
3/8" = 1'-0"	0 1' 2' 4'
3/4" = 1'-0"	0 6" 1' 2'
1 1/2" = 1'-0"	0 3" 6" 1'
PA / PE: JLJ	© 2015 Harriman Associates
Drawn By: SJD	

BUILDING SECTIONS

A25.1