Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 03/03/15

DOOR AND FRAME SCHEDULE

		DOOR					FRAME						
	ROOM NAME	SIZE	MAT	TYPE	LOUVER		MAT	TYPE	DETAILS			FIRE	REMARKS
		W X H X T			W	H			HEAD	JAMB	SILL	RATING	
	RETAIL SALES	3'-0" X 7'-0" X 1 3/4"	AL/GL	1	-	-	AL	-	-	-	S2	-	SECURE FRAME IN MASONRY OPENING
102	STORAGE	3'-0" X 7'-0" X 1 3/4"	SCW	F	-	-	HM	1	4	1	-	-	
103A	RETAIL SALES T/F EXISTING DISTRIBUTION	3'-0" X 7'-0" X 1 3/4"	SCW	G	-	-	HM	1	4	1	-	-	
103B	EXISTING DISTRIBUTION AREA	4'-0" X 7'-0" X 1 3/4"	HM	EXG	-	-	HM	EXG	EXG	EXG	EXG	-	
103C	EXISTING DISTRIBUTION AREA	4'-0" X 7'-0" X 1 3/4"	HM	EXG	-	-	HM	EXG	EXG	EXG	EXG	-	
103D	EXISTING DISTRIBUTION AREA	4'-0" X 7'-0" X 1 3/4"	HM	EXG	-	-	HM	EXG	EXG	EXG	EXG	-	
103E	EXISTING DISTRIBUTION AREA	4'-0" X 7'-0" X 1 3/4"	HM	EXG	-	-	HM	EXG	EXG	EXG	EXG	-	
104	EXISTING OFFICE T/F DISTRIBUTION AREA	3'-0" X 7'-0" X 1 3/4"	WD	EXG	-	-	WD	EXG	EXG	EXG	EXG	-	
105	WOMEN T/F DISTRIBUTION AREA	3'-0" X 7'-0" X 1 3/4"	SCW	F	-	-	HM	1	4	1	-	-	UNDERCUT DOOR 3/4"
106	MEN T/F DISTRIBUTION AREA	3'-0" X 7'-0" X 1 3/4"	SCW	F	-	-	HM	1	4	1	-	-	UNDERCUT DOOR 3/4"
107A	EXISTING RECEIVING DOCK	6'-0" X 8'-0"	STL	COIL-UP	-	-	STL	EXG	EXG	EXG	EXG	-	
107B	EXISTING RECEIVING DOCK	6'-0" X 8'-0"	STL	COIL-UP	-	-	STL	EXG	EXG	EXG	EXG	-	
109	DISTRIBUTOR CASH-UP T/F STAGING AREA	3'-0" X 7'-0" X 1 3/4"	SCW	G	-	-	HM	1	4	1	-	-	
110	SALES MANAGER OFFICE T/F DIST. CASH-UP	3'-0" X 7'-0" X 1 3/4"	SCW	G	-	-	HM	1	4	1	-	-	
111	SALES MANAGER OFFICE T/F DIST. CASH-UP	3'-0" X 7'-0" X 1 3/4"	SCW	G	-	-	HM	1	4	1	-	-	
112	SALES DIRECTOR OFFICE T/F DIST. CASH-UP	3'-0" X 7'-0" X 1 3/4"	SCW	G	-	-	HM	1	4	1	-	-	
113A	NEW DISTRIBUTION AREA	3'-0" X 7'-0" X 1 3/4"	EXG	F	-	-	EXG	EXG	EXG	EXG	EXG	-	
113B	NEW DISTRIBUTION AREA	4'-0" X 7'-0" X 1 3/4"	HM	F	-	-	HM	2	5	2	-	-	
113C	NEW DISTRIBUTION AREA	4'-0" X 7'-0" X 1 3/4"	HM	F	-	-	HM	2	5	2	-	-	
113D	NEW DISTRIBUTION AREA	4'-0" X 7'-0" X 1 3/4"	HM	F	-	-	HM	2	5	2	-	-	
113E	NEW DISTRIBUTION AREA	4'-0" X 7'-0" X 1 3/4"	HM	F	-	-	HM	2	5	2	-	-	
113F	NEW DISTRIBUTION AREA	4'-0" X 7'-0" X 1 3/4"	HM	F	-	-	HM	2	5	2	-	-	
114	ELECTRIC CLOSET T/F RETAIL SALES	5'-4" X 7'-0" X 1 3/4" (2) 2'-8" X 7'-0" X 1 3/4"	SCW	F	-	-	HM	1	4	1	-	-	PAIR OF DOORS
115	STORAGE	3'-0" X 7'-0" X 1 3/4"	SCW	F	-	-	HM	1	4	1	-	-	

9 DEMOLITION PLAN
SCALE: 1/8" = 1'-0"

8 S2 SILL
SCALE: N.T.S.

6 FRAME & DOOR TYPES
SCALE: 1/4" = 1'-0"

7 S1 SILL
SCALE: N.T.S.

4 INT. HM HEAD
SCALE: 1 1/2" = 1'-0"

5 HM HEAD @ CMU
SCALE: 1 1/2" = 1'-0"

1 INT. HM JAMB
SCALE: 1 1/2" = 1'-0"

2 HM JAMB @ CMU
SCALE: 1 1/2" = 1'-0"

3 FLOOR PLAN
SCALE: 1/8" = 1'-0"

HARRIMAN
AUBURN PORTLAND MANCHESTER

LEPAGE BAKERIES COUNTRY KITCHEN BAKERY OUTLET DISTRIBUTION CENTER
276 WARREN AVE.
PORTLAND, MAINE

Harriman Project No.	14558

Key Plan
Proj North

Issues and Revisions

Mark	Date	Description
--	12-31-14	CONTRACTOR REVIEW
--	01-23-15	ISSUED FOR 100% REVIEW
--	01-30-15	ISSUED FOR CONSTRUCTION

LICENSED ARCHITECT JUDY L. JOHNSBURGER No. 2060 STATE OF MAINE

Drawing Scales
1/8" = 1'-0"
0 4' 8' 12'

PA / PE: JLJ
Drawn By: SJD

© 2015 Harriman Associates

DEMOLITION PLAN AND PROPOSED FLOOR PLAN

A10.1