

DECK INFORMATION REQUIRED WITH YOUR APPLICATION

The following is a guideline of information required for the review of a deck application. It is intended to help you supply proper and complete application packages. Please label all of the following items on your plans. Thank you!

1. A complete plot plan showing all structures & proposed structures with distances to all property lines labeled.
2. Type of foundation system
 - a. Diameter of concrete filled tube ~~12"~~
 - b. depth below grade (minimum 4'-0" below grade)
 - c. anchorage of column to footing ~~insert~~
 - d. spacing of tubesOr
 - e. pre cast concrete pier size 7x11 concrete footing
 - f. depth below grade (minimum 4'-0") 4'
 - g. anchorage of column to footing ~~insert~~ predesigned inserts
 - h. spacing of tubes every 5' (5 total)
3. Columns (members supporting framing of floor system)
 - a. wood size and type 4x4 pressure treated wood
 - b. anchorage of column to footing concrete feet w/ inserts for posts
4. Framing Members
 - a. Ledger size attached to building 2x6, running length of deck patio door side +
 - b. Lag Bolt size and spacing on ledger 2 lag screws between each post house side
 - c. Location of all flashing ~~no flashing planer~~ 2 flashing 1 above ledger
 - d. Girder Size and spans carrying floor system
 - e. Joist size, span, and spacing 2x6, 16" on center 12' long x 10 ft wide
 - f. Joist hangers or ledger 16" on center
 - g. Decking size 12x10
5. Guardrails & Handrail Details
 - a. Guardrail height 36"
 - b. Baluster spacing 2"
 - c. Handrail height 36"
6. Stair Details
 - a. Tread depth (measured nosing to nosing) 10"
 - b. Riser height ~~7"~~ 7"
 - c. Nosing on tread 1"
 - d. Width of stairs 4 feet