



ROOF FINISHES:
 1. CONTRACTOR SHALL PROVIDE ALL WATERPROOF ROOF PENETRATIONS PER ROOF MANUFACTURER'S INSTRUCTIONS.
 2. CONTRACTOR TO COORDINATE ALL ROOF PENETRATIONS WITH MECHANICAL, ELECTRICAL, AND PLUMBING.
 3. NOT ALL ROOF PENETRATING OR ROOF-RELATED EQUIPMENT IS SHOWN ON ROOF PLAN. SEE MECHANICAL, PLUMBING DIVISION COORDINATE WORK OF ALL TRADES.
 4. PROVIDE WALKWAY PAGES @ 2 SIDES OF EA. RTU.

□ = EXTENT OF TAPERED INSULATION