



- DEMOLITION KEYED NOTES**
- (E) WALL GRILL & SECTION OF (E) RETURN DUCT TO BE REMOVED AS INDICATED. DETAIL OF NEW DUCT CONNECTION, SEE SHEET (MH-100) (MH-101)
 - (E) VAV BOX AND ASSOCIATED 14" SUPPLY DIFFUSERS AND DUCTWORK ABANDONED IN PLACE. TO BE REMOVED UNDER ALTERNATE PLAN.
 - (E) VAV RETURN GRILLE TO BE REMOVED AND REPLACED WITH CEILING TILE
 - (E) SUPPLY DUCT TO BE REMOVED FROM EDGE OF CLASSROOM TO (E) DIFFUSER. (E) DIFFUSERS TO BE REMOVED AND STORED FOR RE-INSTALLATION. REFER TO NOTE 3 OF THE R-G-G SCHEDULE, SHEET MH-600.

(E) THRU WALL AC UNIT TO REMAIN
 FOR DETAIL OF NEW WORK IN THIS AREA, SEE SHEET (MH-100) (MH-101)

REMOVE EXISTING (E) ATRIUM ASSOCIATED PIPING IN ROOM READING 30. FOR DETAIL OF NEW WORK SEE SHEET (MH-100) (MH-101)