

PERMIT ISSUED

City of Portland, Maine - Building or Use Permit Application

389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716

Permit No: 03-0616	Issue Date: JUN 05 2003	CBL: 300 D011001
-----------------------	-----------------------------------	---------------------

Location of Construction: 128 Belfort St	Owner Name: Dyer David H	Owner Address: 128 Belfort St	Phone: 878-9992
Business Name:	Contractor Name: Classic Window Systems	Contractor Address: 25 True Street Portland	Phone: 2077731950
Lessee/Buyer's Name	Phone:	Permit Type: Additions - Dwellings	Zone: R3

Past Use: Single Family	Proposed Use: Single Family	Permit Fee: \$51.00	Cost of Work: \$3,500.00	CEO District: 1
----------------------------	--------------------------------	------------------------	-----------------------------	--------------------

FIRE DEPT: <input type="checkbox"/> Approved <input type="checkbox"/> Denied	INSPECTION: Use Group: R3 Type: SB accessory
--	--

Proposed Project Description: Build 8x8 and 10x16 "L" shaped deck	Signature: JMB 6/5/03
--	---------------------------------

PEDESTRIAN ACTIVITIES DISTRICT (P.A.D.)
Action: <input type="checkbox"/> Approved <input type="checkbox"/> Approved w/Conditions <input type="checkbox"/> Denied
Signature: _____ Date: _____

Permit Taken By: jmb	Date Applied For: 06/05/2003	Zoning Approval
-------------------------	---------------------------------	------------------------

<p>1. This permit application does not preclude the Applicant(s) from meeting applicable State and Federal Rules.</p> <p>2. Building permits do not include plumbing, septic or electrical work.</p> <p>3. Building permits are void if work is not started within six (6) months of the date of issuance. False information may invalidate a building permit and stop all work..</p>	Special Zone or Reviews <input type="checkbox"/> Shoreland <input type="checkbox"/> Wetland <i>approved</i> <input type="checkbox"/> Flood Zone <input type="checkbox"/> Subdivision <input type="checkbox"/> Site Plan Maj <input type="checkbox"/> Minor <input type="checkbox"/> MM <input type="checkbox"/> Date: JMB 6/5/03	Zoning Appeal <input type="checkbox"/> Variance <input type="checkbox"/> Miscellaneous <input type="checkbox"/> Conditional Use <input type="checkbox"/> Interpretation <input type="checkbox"/> Approved <input type="checkbox"/> Denied Date: _____	Historic Preservation <input checked="" type="checkbox"/> Not in District or Landmark <input type="checkbox"/> Does Not Require Review <input type="checkbox"/> Requires Review <input type="checkbox"/> Approved <input type="checkbox"/> Approved w/Conditions <input type="checkbox"/> Denied Date: JMB
---	---	---	---

CERTIFICATION

I hereby certify that I am the owner of record of the named property, or that the proposed work is authorized by the owner of record and that I have been authorized by the owner to make this application as his authorized agent and I agree to conform to all applicable laws of this jurisdiction. In addition, if a permit for work described in the application is issued, I certify that the code official's authorized representative shall have the authority to enter all areas covered by such permit at any reasonable hour to enforce the provision of the code(s) applicable to such permit.

SIGNATURE OF APPLICANT ADDRESS DATE PHONE

RESPONSIBLE PERSON IN CHARGE OF WORK, TITLE DATE PHONE

City of Portland, Maine - Building or Use Permit

389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716

Permit No: 03-0616	Date Applied For: 06/05/2003	CBL: 300 D011001
------------------------------	--	----------------------------

Location of Construction: 128 Belfort St	Owner Name: Dyer David H	Owner Address: 128 Belfort St	Phone: () 878-9992
Business Name:	Contractor Name: Classic Window Systems	Contractor Address: 25 True Street Portland	Phone: (207) 773-1950
Lessee/Buyer's Name	Phone:	Permit Type: Additions - Dwellings	

Proposed Use: Single Family	Proposed Project Description: Build 8x8 and 10x16 "L" shaped deck
---------------------------------------	---

Dept: Zoning **Status:** Approved **Reviewer:** Jeanine Bourke **Approval Date:** 06/05/2003
Note: **Ok to Issue:**

Dept: Building **Status:** Approved **Reviewer:** Jeanine Bourke **Approval Date:** 06/05/2003
Note: **Ok to Issue:**

1) Application approval based upon information provided by applicant. Any deviation from approved plans requires separate review and approval prior to work.


All Purpose Building Permit Application

If you or the property owner owes real estate or personal property taxes or user charges on any property within the City, payment arrangements must be made before permits of any kind are accepted.

Location/Address of Construction: 128 BELFORT ST.		
Total Square Footage of Proposed Structure 224 SF DECK	Square Footage of Lot 10,580 + 6,783	
Tax Assessor's Chart, Block & Lot Chart# 300 Block# D Lot# 834 <i>ATTACHED + 300</i>	Owner: DAVID DYER	Telephone: 878-9992
Lessee/Buyer's Name (If Applicable) _____	Applicant name, address & telephone: CLASSIC WINDOW SYSTEMS, INC. 25 TRUE ST. PORTLAND, ME 04103	Cost Of Work: \$ 3500.00 Fee: \$ 51.00
Current use: <u>Single Family</u>		
If the location is currently vacant, what was prior use: _____		
Approximately how long has it been vacant: _____		
Proposed use: <u>Same</u>		
Project description: 10' x 16' x 8' x 8' L Shape		
Contractor's name, address & telephone: CLASSIC WINDOW SYSTEMS, INC. 25 TRUE ST. PORTLAND, ME 04103		
Who should we contact when the permit is ready: JAMES SMITH		
Mailing address: 671-3017		
We will contact you by phone when the permit is ready. You must come in and pick up the permit and review the requirements before starting any work, with a Plan Reviewer. A stop work order will be issued and a \$100.00 fee if any work starts before the permit is picked up. PHONE: 671-3017		

IF THE REQUIRED INFORMATION IS NOT INCLUDED IN THE SUBMISSIONS THE PERMIT WILL BE AUTOMATICALLY DENIED AT THE DISCRETION OF THE BUILDING/PLANNING DEPARTMENT, WE MAY REQUIRE ADDITIONAL INFORMATION IN ORDER TO APPROVE THIS PERMIT.

I hereby certify that I am the Owner of record of the named property, or that the owner of record authorizes the proposed work and that I have been authorized by the owner to make this application as his/her authorized agent. I agree to conform to the applicable laws of this jurisdiction. In addition, if a permit for work described in this application is issued, I certify that the Code Official's authorized representative shall have the authority to enter all areas covered by the permit at any reasonable hour to enforce the provisions of the codes applicable to this permit.



Signature of applicant: <i>[Handwritten Signature]</i>	Date: 6.3.03
--	---------------------

This is NOT a permit, you may not commence ANY work until the permit is issued. If you are in a Historic District you may be subject to additional permitting and fees with the Planning Department on the 4th floor of City Hall

james p smith ll
25 true street
portland,maine,04103
Sun May 04 18:42:26 2003

Construction Specifications

deck 1:

Construction Method = Beam Flush With Joist
Footing Type = In-Ground *SOME TUBES*
Footing Depth = 48"
Live Load = 40
Dead Load = 10
Decking Spacing = 0 1/4"
Joist Spacing = 16"
Beam Spacing = 108"
Post Spacing = 93 1/4"
Decking = 5/4X6 .40 Treated Southern Pine No. 2
Beams = 2X10 .40 Treated Spruce-Pine-Fir No. 2
Joists = 2X6 .40 Treated Spruce-Pine-Fir No. 2
Posts = 4X4 .40 Treated Spruce-Pine-Fir No. 2
Deck Height = 24"
Diagonal Bracing = Yes
Deck Skirt = No
Joist Overhang = 0"
Beam Overhang = 0"
Decking Deflection Factor = 360
Joist Deflection Factor = 360
Beam Deflection Factor = 360

Diag Brace Height 1 = 24" in
Diag Brace Height 2 = 24" in

Railing 3:

Railing Height = 36"
Baluster Spacing = 3 3/4"
Toe Space = 3 3/4"

Stair 3:

Step Width = 36"
Step Height = 24"
Step Rise = 5 19/32"
Step Run = 11"
Stringers = 2X12 .40 Treated Spruce-Pine-Fir No. 2
Risers = 5/4X6 .40 Treated Southern Pine No. 2
Treads = 5/4X6 .40 Treated Southern Pine No. 2

Railing 5:

Railing Height = 36"
Baluster Spacing = 3 3/4"
Toe Space = 3 3/4"

Railing 1:

Railing Height = 36"
Baluster Spacing = 3 3/4"
Toe Space = 3 3/4"

Railing 2:

- Railing Height = 36"
- Baluster Spacing = 3 3/4"
- Toe Space = 3 3/4"

Stair 1:

- Step Width = 36"
- Step Height = 24"
- Step Rise = 5 19/32"
- Step Run = 11"
- Stringers = 2X12 .40 Treated Spruce-Pine-Fir No. 2
- Risers = 5/4X6 .40 Treated Southern Pine No. 2
- Treads = 5/4X6 .40 Treated Southern Pine No. 2

Railing 7:

- Railing Height = 36"
- Baluster Spacing = 3 3/4"
- Toe Space = 3 3/4"

Railing 8:

- Railing Height = 36"
- Baluster Spacing = 3 3/4"
- Toe Space = 3 3/4"

Railing 6:

- Railing Height = 36"
- Baluster Spacing = 3 3/4"
- Toe Space = 3 3/4"

Railing 4:

- Railing Height = 36"
- Baluster Spacing = 3 3/4"
- Toe Space = 3 3/4"

james p smith II
 25 true street
 portland,maine,04103
 5/4/2003

Materials for Deck:

Qty	UOM	Use	Description
34	EA	Baluster	2x2x8 .40 Treated Southern Pine; No.2
1	EA	Beam	2x10x8 .40 Treated Spruce-Pine-Fir; No.2
3	EA	Beam	2x10x16 .40 Treated Spruce-Pine-Fir; No.2
17	EA	Decking	5/4x6x8 .40 Treated Southern Pine; No.2
21	EA	Decking	5/4x6x16 .40 Treated Southern Pine; No.2
5	EA	H Bottom Rail	2x4x4 .40 Treated Southern Pine; No.2
2	EA	H Bottom Rail	2x4x6 .40 Treated Southern Pine; No.2
3	EA	H Bottom Rail	2x4x8 .40 Treated Southern Pine; No.2
5	EA	H Top Rail	2x4x4 .40 Treated Southern Pine; No.2
2	EA	H Top Rail	2x4x6 .40 Treated Southern Pine; No.2
3	EA	H Top Rail	2x4x8 .40 Treated Southern Pine; No.2
1	EA	Joist	2x6x7 .40 Treated Spruce-Pine-Fir; No.2
1	EA	Joist	2x6x8 .40 Treated Spruce-Pine-Fir; No.2
18	EA	Joist	2x6x10 .40 Treated Spruce-Pine-Fir; No.2
1	EA	Joist	2x6x16 .40 Treated Spruce-Pine-Fir; No.2
1	EA	Joist	2x6x18 .40 Treated Spruce-Pine-Fir; No.2
1	EA	Ledger	2x6x8 .40 Treated Spruce-Pine-Fir; No.2
2	EA	Post	4x4x10 .40 Treated Spruce-Pine-Fir; No.2
3	EA	Post	4x4x12 .40 Treated Spruce-Pine-Fir; No.2
15	EA	Railing Post	4x4x6 .40 Treated Southern Pine; No.2
4	EA	Riser	5/4x6x10 .40 Treated Southern Pine; No.2
2	EA	Stair Stringer	2x12x12 .40 Treated Spruce-Pine-Fir; No.2
4	EA	Tread	5/4x6x10 .40 Treated Southern Pine; No.2

Standard Deck Materials

5	BOX	Baluster Screws	2-1/2 Wood Screw 5lb
16	EA	Beam Bolts	5/8x8 Galvanized Hex Bolt
16	EA	Beam Nuts	5/8 Galvanized Hex Nut
32	EA	Beam Washer	5/8 Galvanized Washer
12	EA	ConcreteInGnd	80# Concrete Mix
57	EA	Hurricane Tie	Hurricane Tie
2	BOX	Hurricane Tie Nails	8d 1-1/2 Joist Hanger Nails 165pcs
50	EA	Joist Hanger 2x6	Joist Hanger Single 2x6 - 2x8
4	BOX	Jst Hngr Nails 2x6	10d 1-1/2 Joist Hanger Nails 150pcs
1	ROLL	Poly Weed Blocking	8x100 - 4 Mil Poly
36	EA	Rail Post Bott	3/8x6 Galvanized Lag Screw
36	EA	Rail Post Washer	2-1/2" Galvanized Decking Screws
1	BOX	Step Screws	8x2 1/2" Galvanized Deck Screws 5lb
6	EA	Stringer Hanger	Sloped Stringer Hanger
1	BOX	Stringer Hngr Nails	10d 1-1/2 Joist Hanger Nails 150pcs
5	EA	Wood Sealer	1 Gallon Clear Wood Sealer

Parameters from UBC.cod parameter file.

Parameters used for Deck 1: 40 psf live load, 48 inch footing depth.

CONSUMER INFORMATION SHEET

USE SITE PRECAUTION FOR CCA PRESSURE-TREATED WOOD

- * Wood pressure-treated with CCA preservatives may be used inside residences as long as all sawdust and construction debris are cleaned up and disposed of after construction.
- * Do not use treated wood under circumstances where the preservative may become a component of food or animal feed. Examples of such sites would be structures or containers for storing silage or food.
- * Do not use treated wood for cutting-boards or countertops.
- * Only treated wood that is visibly clean and free of surface residue should be used for patios, decks and walkways.
- * Do not use treated wood for construction of those portions of beehives which may come into contact with the honey.
- * Treated wood should not be used where it may come into direct or indirect contact with public drinking water, except for uses involving incidental contact such as docks and bridges.

HANDLING PRECAUTIONS FOR CCA PRESSURE-TREATED WOOD

- * Dispose of treated wood by ordinary trash collection or burial. Treated wood should not be burned in open fires or in stoves, fireplaces or residential boilers because toxic chemicals may be produced as part of the smoke and ashes. Treated wood from commercial or industrial use (e.g., construction sites) may be burned only in commercial incinerators or boilers in accordance with state and Federal regulations.
- * Avoid frequent or prolonged inhalation of sawdust from treated wood. When sawing and machining treated wood, wear a dust mask. Whenever possible, these operations should be performed outdoors to avoid indoor accumulations of airborne sawdust from treated wood.
- * When power-sawing and machining, wear goggles to protect eyes from flying particles.
- * After working with the wood, and before eating, drinking, and the use of tobacco products, wash exposed areas well.
- * If preservatives or sawdust accumulates on clothes, launder before reuse. Wash work clothes separately from other household clothing.
- * Treated wood should be dry before handling.

BUILDING QUALIFICATIONS:

The attached plans are intended to be used by individuals knowledgeable in and familiar with generally accepted methods, techniques and standards of construction, as well as the safe operation of all required tools. Individuals without these qualifications should not attempt the construction of this project.


PLAN MODIFICATIONS:

The suggested printed plans attempt to comply with generally accepted construction methods in North America and to be applicable with most local building codes to the extent possible. There is no guarantee that the plans conform to all the building conditions and requirements in your area. A professional contractor or local building inspector should be consulted for codes and restrictions which may apply to your specific building site. In order to comply with local codes, regulations, and local standards of safe and proper building practices pertinent to your existing local site conditions, changes and modifications to these plans may be required. Local lot restrictions and building attachments may also require changes to these plans. The final plans or modifications to plans and the associated materials is the responsibility of the builder.

PLAN ACCURACY:


jar p smith ll
 25 ... ie street
 portland, maine, 04103
 Sun May 04 18:41:37 2003

Deck Dimensions for Deck 1



This view is a general outline of the dimensions and/or substructure layout of your design. If a deck is to be attached to your house, make sure a solid connection can be made. Your design should be checked by a qualified professional or inspector. Consult your local building department for your correct building code and fastener requirements. Some local building codes require different beam to post connections than what is shown. Portions Copyright © 1989-2002 Cad Quest, Inc. Big Hammer DeckBot, Version 5.2.0, Copyright © 2002 Big Hammer, LLC.

&PostLayout View for Deck 1



This view is a general outline of the dimensions and/or substructure layout of your design. If a deck is to be attached to your house, make sure a solid connection can be made. Your design should be checked by a qualified professional or inspector. Consult your local building department for your correct building code and fastener requirements. Some local building codes require different beam to post connections than what is shown. Portions Copyright © 1989-2002 Cad Quest, Inc. Big Hammer DeckBot, Version 5.2.0, Copyright © 2002 Big Hammer, LLC.


smith ll
treet
,maine,04103

May 04 18:43:54 2003

Deck Layout




Will provide Graspable
handrail



House

This view is a general outline of the dimensions and/or substructure layout of your design. If a deck is to be attached to your house, make sure a solid connection can be made. Your design should be checked by a qualified professional or inspector. Consult your local building department for your correct building code and fastener requirements. Some local building codes require different beam to post connections than what is shown. Portions Copyright © 1989-2002 Cad Quest, Inc. Big Hammer DeckBot, Version 5.2.0, Copyright © 2002 Big Hammer, LLC.





Descriptor/Area

A: 1Fr/B
792 sqft

B: 1Fr
208 sqft

> 1000 SF
160
64
New
1224

Lot 6,783
X .25% OK

1,695.75

This page contains a detailed description of the Parcel ID you selected. Press the **New Search** button at the bottom of the screen to submit a new query.

Current Owner Information

Card Number	1 of 1
Parcel ID	300 D011001
Location	128 BELFORT ST
Land Use	SINGLE FAMILY
 Owner Address	 DYER DAVID H 128 BELFORT ST PORTLAND ME 04103
 Book/Page	 9415/175
Legal	300-D-11-12-52 + 300-D-34-37 BELFORT ST 128 6783 SF

Valuation Information

Land	Building	Total
\$31,920	\$45,780	\$77,700

Property Information

Year Built 1958	Style Ranch	Story Height 1	Sq. Ft. 1000	Total Acres 0.156	
Bedrooms 2	Full Baths 1	Half Baths	Total Rooms 5	Attic None	Basement Full

Outbuildings

Type	Quantity	Year Built	Size	Grade	Condition
-------------	-----------------	-------------------	-------------	--------------	------------------

Sales Information

Date	Type	Price	Book/Page
-------------	-------------	--------------	------------------

Picture and Sketch

<u>Picture</u>	<u>Sketch</u>
--------------------------------	-------------------------------

[Click here to view Tax Roll Information.](#)

Any information concerning tax payments should be directed to the Treasury office at 874-8490 or e-
[mailed.](#)

New Search

CHART	LETTER	BLOCK	LOT	UNIT NO.	CARD NUMBER	NUMBER	STREET NAME	CLASS	101
300	-	D	034	001	0101			111	101
								112	101
								113	101
								114	101
								115	101

SALES DATA	VALID	SOURCE	AMOUNT	TYPE	NO	YR	TYPE

OWNER & MAILING ADDRESS	114	DEED BOOK	DEED PAGE	DEED DATE
ROBINSON HARLEY S DEVS				

LEGAL DESCRIPTION	200	201	202
389 CONGRESS ST PORTLAND ME 04101			

LIVING UNITS	104	105	106	107	108	109	110
0	03	102					

ACTUAL	EFFECTIVE	EFFECTIVE	EFFECTIVE	DEPT	EFFECTIVE	ACTUAL	DEPT	EFFECTIVE	INFLUENCE	LAND VALUE

ACTUAL	EFFECTIVE	EFFECTIVE	EFFECTIVE	DEPT	EFFECTIVE	ACTUAL	DEPT	EFFECTIVE	INFLUENCE	LAND VALUE

ACTUAL	EFFECTIVE	EFFECTIVE	EFFECTIVE	DEPT	EFFECTIVE	ACTUAL	DEPT	EFFECTIVE	INFLUENCE	LAND VALUE

ACTUAL	EFFECTIVE	EFFECTIVE	EFFECTIVE	DEPT	EFFECTIVE	ACTUAL	DEPT	EFFECTIVE	INFLUENCE	LAND VALUE

ACTUAL	EFFECTIVE	EFFECTIVE	EFFECTIVE	DEPT	EFFECTIVE	ACTUAL	DEPT	EFFECTIVE	INFLUENCE	LAND VALUE

ACTUAL	EFFECTIVE	EFFECTIVE	EFFECTIVE	DEPT	EFFECTIVE	ACTUAL	DEPT	EFFECTIVE	INFLUENCE	LAND VALUE

ACTUAL	EFFECTIVE	EFFECTIVE	EFFECTIVE	DEPT	EFFECTIVE	ACTUAL	DEPT	EFFECTIVE	INFLUENCE	LAND VALUE

ACTUAL	EFFECTIVE	EFFECTIVE	EFFECTIVE	DEPT	EFFECTIVE	ACTUAL	DEPT	EFFECTIVE	INFLUENCE	LAND VALUE

ACTUAL	EFFECTIVE	EFFECTIVE	EFFECTIVE	DEPT	EFFECTIVE	ACTUAL	DEPT	EFFECTIVE	INFLUENCE	LAND VALUE

ACTUAL	EFFECTIVE	EFFECTIVE	EFFECTIVE	DEPT	EFFECTIVE	ACTUAL	DEPT	EFFECTIVE	INFLUENCE	LAND VALUE

ACTUAL	EFFECTIVE	EFFECTIVE	EFFECTIVE	DEPT	EFFECTIVE	ACTUAL	DEPT	EFFECTIVE	INFLUENCE	LAND VALUE

ACTUAL	EFFECTIVE	EFFECTIVE	EFFECTIVE	DEPT	EFFECTIVE	ACTUAL	DEPT	EFFECTIVE	INFLUENCE	LAND VALUE

ACTUAL	EFFECTIVE	EFFECTIVE	EFFECTIVE	DEPT	EFFECTIVE	ACTUAL	DEPT	EFFECTIVE	INFLUENCE	LAND VALUE

ACTUAL	EFFECTIVE	EFFECTIVE	EFFECTIVE	DEPT	EFFECTIVE	ACTUAL	DEPT	EFFECTIVE	INFLUENCE	LAND VALUE

ACTUAL	EFFECTIVE	EFFECTIVE	EFFECTIVE	DEPT	EFFECTIVE	ACTUAL	DEPT	EFFECTIVE	INFLUENCE	LAND VALUE

ACTUAL	EFFECTIVE	EFFECTIVE	EFFECTIVE	DEPT	EFFECTIVE	ACTUAL	DEPT	EFFECTIVE	INFLUENCE	LAND VALUE

ACTUAL	EFFECTIVE	EFFECTIVE	EFFECTIVE	DEPT	EFFECTIVE	ACTUAL	DEPT	EFFECTIVE	INFLUENCE	LAND VALUE

ACTUAL	EFFECTIVE	EFFECTIVE	EFFECTIVE	DEPT	EFFECTIVE	ACTUAL	DEPT	EFFECTIVE	INFLUENCE	LAND VALUE

ACTUAL	EFFECTIVE	EFFECTIVE	EFFECTIVE	DEPT	EFFECTIVE	ACTUAL	DEPT	EFFECTIVE	INFLUENCE	LAND VALUE

ACTUAL	EFFECTIVE	EFFECTIVE	EFFECTIVE	DEPT	EFFECTIVE	ACTUAL	DEPT	EFFECTIVE	INFLUENCE	LAND VALUE

ACTUAL	EFFECTIVE	EFFECTIVE	EFFECTIVE	DEPT	EFFECTIVE	ACTUAL	DEPT	EFFECTIVE	INFLUENCE	LAND VALUE

ACTUAL	EFFECTIVE	EFFECTIVE	EFFECTIVE	DEPT	EFFECTIVE	ACTUAL	DEPT	EFFECTIVE	INFLUENCE	LAND VALUE

ACTUAL	EFFECTIVE	EFFECTIVE	EFFECTIVE	DEPT	EFFECTIVE	ACTUAL	DEPT	EFFECTIVE	INFLUENCE	LAND VALUE

ACTUAL	EFFECTIVE	EFFECTIVE	EFFECTIVE	DEPT	EFFECTIVE	ACTUAL	DEPT	EFFECTIVE	INFLUENCE	LAND VALUE

ACTUAL	EFFECTIVE	EFFECTIVE	EFFECTIVE	DEPT	EFFECTIVE	ACTUAL	DEPT	EFFECTIVE	INFLUENCE	LAND VALUE

ACTUAL	EFFECTIVE	EFFECTIVE	EFFECTIVE	DEPT	EFFECTIVE	ACTUAL	DEPT	EFFECTIVE	INFLUENCE	LAND VALUE

300-D-34 10 37
SARFIELD ST
10580SF

ROBINSON HARLEY S DEVS
Dyer, Davis
389 CONGRESS ST
PORTLAND ME
04101

DELETED 300 330

LAND DATA & COMPUTATIONS

LOT 1
1 Regular Lot
2 Apartment Site

SQUARE FEET
1 Primary Site
2 Secondary Site
3 Undeveloped
4 Residual
5 Waterfront

ACREAGE
1 Primary Site
2 Secondary Site
3 Undeveloped
4 Marshland
5 Waterfront

0 TOTAL

GROSS
3 Residual
4 Homestead
9 Minus R.O.W.
2 Site Value

PROPERTY FACTORS
421 UTILITIES
421 STREET/ROAD
441 TRAFFIC

VALUE SUMMARY
PREVIOUS ASSESSMENT

EL
1 ALL PUBLIC
2 PUBLIC WATER
3 PUBLIC SEWER
4 GAS
5 WELL
6 SEPTIC
7 NONE
8

WEST REET
2 SEMI-IMPROVED
3 UNPAVED
4 PROPOSED
5 CURB & GUTTER
6 SIDEWALK
7 ALLEY
8 NONE

LAND
1 LIGHT
2 MEDIUM
3 HEAVY
4 NONE

BUILDING
1
2
3

TOTAL
1140

EXEMPT
1140

EXEMPT VALUE
1140

REASON
DATE

MARKET REVIEW TOTAL VALUE
R MONTH/DAY/YEAR REVIEWER

LAND VALUE
1140

REASON
DATE
REVIEWER
SM

DATE INSPECTED
12/11/87

COLLECTOR
JEF

SIGNATURE:
ON PAGE 5 ST

SIGNATURE BY OWNER OR AGENT BELOW INDICATES
DATA ON THIS FORM WAS COLLECTED IN YOUR
PRESENCE. IT DOES NOT MEAN THAT YOU HAVE
VERIFIED THE INFORMATION HEREON.

0 Entrance and Signature Gained
1 Entrance Gained
2 Not Applicable, Unimproved Parcel
3 Entrance and Information Refused
4 Entrance Refused, Information at Door
5 Currently Unoccupied
6 Estimated for Miscellaneous Reasons (See Memorandum)
7 Occupant Not at Home
8 Other

ENTRANCE CODES
106

INFO CODES
1 Owner
2 Tenant
3 Other

1 Land
2 Land and Buildings
3 Building

SOURCE
A. Relative Sale
B. Intra Corporation
C. Included Excessive
Personal Property
K. To or From Non-Profit
Organization
L. Reorganization/Sale of
Foreclosed Property
M. Zoning Change
N. Other

1 Buyer
2 Seller
3 Agent
4 Other

ENTRANCE CODES
106

VALIDITY CODES
202
201
200

NO YR TYPE

AMOUNT
SOURCE
VALID

DEED DATE
DEED PAGE
DEED BOOK
114

OWNER & MAILING ADDRESS

STREET NO.
112
1531

STREET CODE
111
1531

STREET NO.
102
0000


LAND USE
113
40

ROUTE
39

PORTLAND, MAINE

PRC-360

499	DELETE 505-533	VACANT	DWELLING	OTHER	STORY HEIGHT	1.5	2.0	2.5	3.0
505					EXTERIOR WALLS	13 MANSION	7 CONDO	14 GAMBREL	15 GARRISON
506					RAISED RANCH	13 MANSION	7 CONDO	8 CONTEMP	14 GAMBREL
507					LIVING ACCOMMODATIONS	NO. KITCHEN	1 - YES	NO. BATH	1 - YES
508					AGE	REMODELED	NO	REMODELED	NO
509					ERECTED	EST	REMODELED	19	
510					TOTAL	FAMILY	ROOMS	ADJUTL	TOTAL
511					ROOMS	FAMILY	ROOMS	ADJUTL	TOTAL
512					BATHS	1	BATHS	1	ADJUTL
513					NO. KITCHEN	1	NO. BATH	1	ADJUTL
514					REMODELED	NO	REMODELED	NO	
515					INTERIOR CONDITION	BETTER	SAME	POORER	
516					PHYSICAL CONDITION	1	2	3	4
517					LEVEL	CONDO	1 - INTERIOR	2 - CORNER	



800	1 SEE DETAILED CARD	2 SEE DETAILED REPORT	TOTAL GROSS VALUE	
801				
802				
803				
804				
805				
806				
807				
808				
809				
810				
811				
812				
813				
814				
815				
816				
817				
818				
819				
820				
821				
822				
823				
824				
825				
826				
827				
828				
829				
830				
831				
832				
833				
834				

471										
472										
473										
474										
475										
476										
477										
478										
479										
480										
481										
482										
483										
484										
485										
486										
487										
488										
489										
490										
491										
492										
493										
494										
495										
496										
497										
498										
499										
500										
501										
502										
503										
504										
505										
506										
507										
508										
509										
510										
511										
512										
513										
514										
515										
516										
517										
518										
519										
520										
521										
522										
523										
524										
525										
526										
527										
528										
529										
530										
531										
532										
533										
534										

NOTES

BUILDING PERMIT INSPECTION PROCEDURES

Please call 874-8703 or ~~874-8693~~ to schedule your inspections as agreed upon

Permits expire in 6 months, if the project is not started or ceases for 6 months.

The Owner or their designee is required to notify the inspections office for the following inspections and provide adequate notice. Notice must be called in 48-72 hours in advance in order to schedule an inspection:

By initializing at each inspection time, you are agreeing that you understand the inspection procedure and additional fees from a "Stop Work Order" and "Stop Work Order Release" will be incurred if the procedure is not followed as stated below.

~~JB~~ ~~Pre-construction Meeting:~~ Must be scheduled with your inspection team upon receipt of this permit. Jay Reynolds, Development Review Coordinator at ~~874-8692~~ must also be contacted at this time, before any site work begins on any project other than single family additions or alterations.

- ~~Footing/Building Location Inspection:~~ Prior to pouring concrete
- ~~NA~~ ~~Re-Bar Schedule Inspection:~~ Prior to pouring concrete
- ~~NA~~ ~~Foundation Inspection:~~ Prior to placing ANY backfill
- ~~NA~~ ~~Framing/Rough Plumbing/Electrical:~~ Prior to any insulating or drywalling
- ~~Final/Certificate of Occupancy:~~ Prior to any occupancy of the structure or use. NOTE: There is a \$75.00 fee per inspection at this point.

Certificate of Occupancy is not required for certain projects. Your inspector can advise you if your project requires a Certificate of Occupancy. All projects DO require a final inspection

If any of the inspections do not occur, the project cannot go on to the next phase, REGARDLESS OF THE NOTICE OR CIRCUMSTANCES.

~~NA~~ **CERTIFICATE OF OCCUPANCIES MUST BE ISSUED AND PAID FOR, BEFORE THE SPACE MAY BE OCCUPIED**

James P. Smith 3.6.16
Signature of applicant/designee Date
Annunzio _____
Signature of Inspections Official Date

CBL: 300-D-11 Building Permit #: 037616

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK

CITY OF PORTLAND

BUILDING DEPARTMENT

PERMIT

PERMIT ISSUED

Permit Number: 030616

JUN 05 2003

Please Read Application And Notes, if Any, Attached

This is to certify that Dyer David H/Classic Window Systems
has permission to Build 8x8 and 10x16 "L" shade deck
AT 128 Belfort St 300 D011001

CITY OF PORTLAND

provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statutes of Maine and of the ordinances of the City of Portland regulating the construction, maintenance and use of buildings and structures, and of the application on file in this department.

Apply to Public Works for street line and grade if nature of work requires such information.

Notification of inspection must be given and written permission procured before this building or part thereof is laid or occupied. CLOSED-IN. HOURS NOTICE IS REQUIRED.

A certificate of occupancy must be procured by owner before this building or part thereof is occupied.

OTHER REQUIRED APPROVALS

Fire Dept. _____
Health Dept. _____
Appeal Board _____
Other _____
Department Name

Jeanie Bourke 6/5/03
Director - Building & Inspection Services

PENALTY FOR REMOVING THIS CARD