



- KEYED NOTES - GENERAL**
(THESE NOTES ARE SPECIFIC TO THIS SHEET ONLY)
- 1 LOCATION OF L-SHAPED MODULAR WORK STATION PROVIDED AND SET IN PLACE BY SAFELITE. SEE DETAIL 2/A-5 FOR PLAN VIEW DIMENSIONS.
 - 2 PROVIDE AND INSTALL A TUB SINK IN IN-SHOP AREA WHERE SHOWN.
 - 3 PROVIDE NEW PREMANUFACTURED BOLT-DOWN BOLLARDS WHERE SHOWN. SEE DETAIL 8/A1.3.
 - 4 PROVIDE NEW STEEL CONCRETE FILLED BOLLARDS WHERE SHOWN. SEE DETAIL 8/A1.3.
 - 23 PROVIDE NEW PREMANUFACTURED BOLT-DOWN BOLLARDS WHERE SHOWN. SEE DETAIL 8/A1.3. VERIFY IN THE FIELD, EXACT LOCATIONS AND QUANTITIES BASED ON INSTALLATION OF ELECTRICAL PANELS AND SPRINKLER RISER.
 - 24 PROVIDE NEW 8' TALL CHAIN-LINK FENCE WITH A 3'-0" WIDE WALK GATE AND LATCH WHERE SHOWN.
 - 25 PROVIDE A STEEL ROOF ACCESS LADDER WITH WALK THRU HANDRAILS AND MOUNTABLE SECURITY LADDER GUARD.
 - 26 CONTRACTOR TO PROVIDE FIRE EXTINGUISHERS INSPECTED AND TAGGED PER NFPA 10 AND THE 2006 IFG SECTION 906. VERIFY FINAL QUANTITY AND LOCATION OF FIRE EXTINGUISHERS WITH THE GOVERNING FIRE MARSHALL.
 - 27 NO SPRINKLER HEADS TO BE PROVIDED IN THE ELECTRIC/PHONE ROOM.
 - 28 PROVIDE A ONE-HOUR SHUTTER WITH FUSIBLE LINK WHERE SHOWN TO COVER BOTH DOOR AND WINDOW.

1 FLOOR PLAN
SCALE - 3/32"=1'-0"

Floor Plan Key	
	EXISTING WALLS TO REMAIN
	NEW FRAMED PARTITION WALLS
	NEW FRAMED PARTITION WALLS FLOOR TO DECK
	EXISTING DOORS TO REMAIN
	NEW DOORS TO PROVIDE AND INSTALL

Sheet Name: **FLOOR PLAN**

Safelite AutoGlass
421 Warren Avenue
Portland, Maine 04103

No.	Revisions		Issue Date: 01-15-2016	Sheet No. A-1
	Description	Date		
1	NOT FOR REGULATORY APPROVAL PERMITTING OR CONSTRUCTION		File PORTLAND-A1.dwg	
			Scale AS NOTED	
			Drawn By: KRM	
			Checked By: ...	
			Checked By: ...	