SITE LIGHTING PHOTOMETRICS
1" = 10'-0"

LUMINAIRE SCHEDULE

Symbol	Label	Qty	Catalog Number	Description	Lamp	File	Lumens	LLF	Watts
	SA2	1	STLM-III-175MH CLEAR FLAT TEMPERED GLASS LENS, SEGMENTED SPECULAR TYPE-III REFLECTOR HORIZONTAL LAMP TOTAL WATTS = 210	MOUNTED AT 20'-0" OVERALL	175 WATT CLEAR ED17 METAL HALIDE	STLM-3-17M.ies	14000	0.75	420
	SA	4	STLM-III-175MH CLEAR FLAT TEMPERED GLASS LENS, SEGMENTED SPECULAR TYPE-III REFLECTOR HORIZONTAL LAMP TOTAL WATTS = 210	MOUNTED AT 20'-0" OVERALL	175 WATT CLEAR ED17 METAL HALIDE	STLM-3-17M.ies	14000	0.75	210
	SB	1	STLM-IV-175MH CLEAR FLAT TEMPERED GLASS LENS, SEGMENTED SPECULAR TYPE-IV REFLECTOR HORIZONTAL LAMP TOTAL WATTS = 210	MOUNTED AT 20'-0" OVERALL	175 WATT CLEAR ED17 METAL HALIDE	STLM-4-17M.ies	14000	0.75	210

STATISTICS

Description	Symbol	Avg	Max	Min	Max/Min	Avg/Min
Calc Zone #1	+	2.6 fc	8.7 fc	0.3 fc	29.0:1	8.8:1

vocon DESIGN INC.
2450 Prospect Avenue
Cleveland, Ohio 44115
216 623-6800 p.
216 623-0410 f.
vocon@vocon.com

WORKLEY ARCHITECTS, inc.
2450 Prospect Ave. 1st floor
Cleveland, Ohio 44115-2604
216/ 623-6800 216/ 623-0410 fax

Consulting Engineers
3030 West Streetsboro Road (330) 659-6688 Ph.
Richfield, Ohio 44286 (330) 659-6675 Fax

SEAL:

KeyBank
2025 Ontario Ave, 4th Floor
Cleveland, Ohio 44115
Phone: 216-689-8274
FAX: 216-689-3163

PROPOSED REMOTE ATM
424 WARREN AVE
PORTLAND, ME 04103

Submittals:

No.	Date	Description
	APR. 21, 2005	Resubmittal for Review
	JUNE 1, 2005	Submittal for Permit

Revisions:

No.	Date	Description

Drawn by: TBA
Checked by: JDM
Job Number: 4072-000

Dwg. Phase: CONSTRUCTION DOCUMENTS

Sheet Title:
SITE LIGHTING PHOTOMETRICS

Sheet Number:
E2.0