

City of Portland, Maine - Building or Use Permit Application

389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716

| | | |
|-----------------------|-----------------------------------|---------------------|
| Permit No: 04-0015 | Issue Date: MAR 26 2004 | CBL: 306 B001001 |
|-----------------------|-----------------------------------|---------------------|

| | | | |
|---|--|---|---------------------------|
| Location of Construction: 563 Riverside St | Owner Name: Six G's Coed Llc | Owner Address: 557 Riverside St | Phone: RECEIVED |
| Business Name: n/a | Contractor Name: Patco Construction | Contractor Address: 1293 Main St Sanford | Phone: 2073245574 |
| Lessee/Buyer's Name: n/a | Phone: n/a | Permit Type: Additions - Commercial | Zone: TM |

| | | | | |
|----------------------------------|--|---|--|--------------------|
| Past Use: Commercial / Vacant | Proposed Use: Commercial / Build new 2,000 sq.ft commercial Rental Units. | Permit Fee: \$3,684.00 | Cost of Work: \$407,000.00 | CEO District: 5 |
| | | FIRE DEPT: <input checked="" type="checkbox"/> Approved <input type="checkbox"/> Denied | INSPECTION: Use Group: B/E2 Type: 2C 52 3/26/04 | |

| | | |
|--|----------------------------------|----------------------------------|
| Proposed Project Description: Commercial / Build new 2,000 sq. Ft. Commercial rental units. 14,000, 52 Ft BUILDING! | Signature: <i>[Signature]</i> | Signature: <i>[Signature]</i> |
| PEDESTRIAN ACTIVITIES DISTRICT (P.A.D.) | | |
| Action: <input type="checkbox"/> Approved <input type="checkbox"/> Approved w/Conditions <input type="checkbox"/> Denied | | |
| Signature: | | Date: |

| | | |
|------------------------|---------------------------------|------------------------|
| Permit Taken By: gg | Date Applied For: 01/06/2004 | Zoning Approval |
|------------------------|---------------------------------|------------------------|

| | | | |
|---|---|--|--|
| <p>1. This permit application does not preclude the Applicant(s) from meeting applicable State and Federal Rules.</p> <p>2. Building permits do not include plumbing, septic or electrical work.</p> <p>3. Building permits are void if work is not started within six (6) months of the date of issuance. False information may invalidate a building permit and stop all work..</p> | <p>Special Zone or Reviews</p> <p><input type="checkbox"/> Shoreland N/A</p> <p><input type="checkbox"/> Wetland</p> <p><input type="checkbox"/> Flood Zone panel 1 zone C</p> <p><input type="checkbox"/> Subdivision</p> <p><input checked="" type="checkbox"/> Site Plan 2003-0210</p> <p>Maj <input type="checkbox"/> Minor <input checked="" type="checkbox"/> MM <input type="checkbox"/></p> <p><i>ok with conditions</i></p> <p>Date: 03/17/04</p> | <p>Zoning Appeal</p> <p><input type="checkbox"/> Variance</p> <p><input type="checkbox"/> Miscellaneous</p> <p><input type="checkbox"/> Conditional Use</p> <p><input type="checkbox"/> Interpretation</p> <p><input type="checkbox"/> Approved</p> <p><input type="checkbox"/> Denied</p> <p>Date:</p> | <p>Historic Preservation</p> <p><input checked="" type="checkbox"/> Not in District or Landmark</p> <p><input type="checkbox"/> Does Not Require Review</p> <p><input type="checkbox"/> Requires Review</p> <p><input type="checkbox"/> Approved</p> <p><input type="checkbox"/> Approved w/Conditions</p> <p><input type="checkbox"/> Denied</p> <p>Date: S</p> |
|---|---|--|--|

CERTIFICATION

I hereby certify that I am the owner of record of the named property, or that the proposed work is authorized by the owner of record and that I have been authorized by the owner to make this application as his authorized agent and I agree to conform to all applicable laws of this jurisdiction. In addition, if a permit for work described in the application is issued, I certify that the code official's authorized representative shall have the authority to enter all areas covered by such permit at any reasonable hour to enforce the provision of the code(s) applicable to such permit.

SIGNATURE OF APPLICANT _____ ADDRESS _____ DATE _____ PHONE _____

RESPONSIBLE PERSON IN CHARGE OF WORK, TITLE _____ DATE _____ PHONE _____

**CITY OF PORTLAND, MAINE
DEVELOPMENT REVIEW APPLICATION
PLANNING DEPARTMENT PROCESSING FORM
Zoning Copy**

2003-0210
Application I. D. Number
10/8/03
Application Date
Office/Industrial Building
Project Name/Description

Six Gs Coed, LLC
Applicant
557 Riverside Street, Portland, ME 04103
Applicant's Mailing Address

Consultant/Agent
Applicant Ph: (207) 797-5830 Agent Fax:
Applicant or Agent Daytime Telephone, Fax

567 - 567 Riverside St, Portland, Maine
Address of Proposed Site
312 B003 306-B-1:07
Assessor's Reference: Chart-Block-Lot

Proposed Development (check all that apply):
 New Building Building Addition Change Of Use Residential Office Retail
 Manufacturing Warehouse/Distribution Parking Lot Other (specify) _____

14,000 s.f.
Proposed Building square Feet or # of Units Acreage of Site IM
Zoning

Check Review Required:

- | | | | |
|--|---|--|--|
| <input checked="" type="checkbox"/> Site Plan (major/minor) | <input type="checkbox"/> Subdivision # of lots _____ | <input type="checkbox"/> PAD Review | <input type="checkbox"/> 14-403 Streets Review |
| <input type="checkbox"/> Flood Hazard | <input type="checkbox"/> Shoreland | <input type="checkbox"/> Historic Preservation | <input type="checkbox"/> DEP Local Certification |
| <input type="checkbox"/> Zoning Conditional Use (ZBA/PB) | <input type="checkbox"/> Zoning Variance | <input type="checkbox"/> Other _____ | |

Fees Paid: Site Plan \$400.00 Subdivision _____ Engineer Review _____ Date: 10/14/03

Zoning Approval Status:

Approved Approved w/Conditions
See Attached Denied

Approval Date _____ Approval Expiration _____ Extension to _____ Additional Sheets
Attached

Condition Compliance _____ _____
signature date

Performance Guarantee Required* Not Required

* No building permit may be issued until a performance guarantee has been submitted as indicated below

| | | | |
|---|----------------|--|-----------------|
| <input type="checkbox"/> Performance Guarantee Accepted | _____ | _____ | _____ |
| | date | amount | expiration date |
| <input type="checkbox"/> Inspection Fee Paid | _____ | _____ | |
| | date | amount | |
| <input type="checkbox"/> Building Permit Issued | _____ | | |
| | date | | |
| <input type="checkbox"/> Performance Guarantee Reduced | _____ | _____ | _____ |
| | date | remaining balance | signature |
| <input type="checkbox"/> Temporary Certificate of Occupancy | _____ | <input type="checkbox"/> Conditions (See Attached) | _____ |
| | date | | expiration date |
| <input type="checkbox"/> Final Inspection | _____ | _____ | |
| | date | signature | |
| <input type="checkbox"/> Certificate Of Occupancy | _____ | | |
| | date | | |
| <input type="checkbox"/> Performance Guarantee Released | _____ | _____ | |
| | date | signature | |
| <input type="checkbox"/> Defect Guarantee Submitted | _____ | _____ | _____ |
| | submitted date | amount | expiration date |

SRG ENGINEERING, INC.
P.O. Box 925
GRAY, ME 04039



PATCO
CONSTRUCTION, INC.

Fax Transmittal

Phoenix Welding



To: _____

Date: _____ Fax: _____

From: _____ No. of pages: _____

(including cover sheet)

Message:





PATCO
CONSTRUCTION, INC.

January 5, 2004

Mr. Michael Nugent
City of Portland
City Hall Room 315
389 Congress Street
Portland, ME 04101

Re: Six G's Coed L.L.C./Phoenix Welding

Dear Michael:

Attached please find our building permit application for the above project on Riverside Street. We have included the following:

- Cover letter
- Permit Application
- Designer's certification form
- Building code certificate
- Accessibility certificate

- Varco-Pruden letter of certification (metal building)
- Architectural plans: A-1, A-2, 11 x 17 and 24 x 36
- Foundation plans: S-1, S-2, 11 x 17 and 24 x 36
- Structural Steel plans: 1-31, 11 x 17 and 18 x 24
- Site plans : 1- 4, (for information)

The proposed building consists of seven (7) 2,000 sq. ft. speculative rental spaces for a total of 14,000 sq. ft. Each unit has it's own on grade overhead door, small office, H.C. bathroom, two means of egress, individual utilities, heat and electrical. The building also has a complete automatic sprinkler system and fire alarm.

I hope that this is sufficient information for your review. If you have any questions, call me at 651-0798 or 324-5574.

Sincerely,

Dennis M. Waters

DMW/jg
Enclosure

From: Marge Schmuckal
To: Sarah Hopkins
Date: Mon, Jan 12, 2004 11:12 AM
Subject: 563 Riverside St. - Six G's Coed LLC

Knud's job

Sarah,
I don't know what planner has this site plan for the 14,000 sq. ft. building. Why isn't there a place on the site plan form for that? Anyway, there is one zoning problem - First of all it is a IM zone not an I-H zone - Second, the pavement setbacks requirement of 10' is not being met. Only about 3' is shown along the entry way and not quite 10' by the parking. Third, the plans say that there is City sewer available, but they want to put in a private subsurface instead. However, I don't see that on the plans.

Thanks,
Marge

*1/20/04
received NEW
plans - pavement
setback ok*

All Purpose Building Permit Application

If you or the property owner owes real estate or personal property taxes or user charges on any property within the City, payment arrangements must be made before permits of any kind are accepted.

306

563-573

Location/Address of Construction: 557 Riverside Street (Phoenix Welding)

Total Square Footage of Proposed Structure: 12,000 sq. ft. Square Footage of Lot: 373,888 sq. ft.

Tax Assessor's Chart, Block & Lot
 Chart# 312 Block# 306 Lot# 6
 Maps 312 & 306 3, 11

Owner: Six G's COED, L.L.C. Telephone: 797-5832

Lessee/Buyer's Name (if Applicable): N/A Applicant name, address & telephone: Dennis Waters Patco Construction, Inc. 1293 Main St. Sanford 324-5574 Cost Of Work: \$ 407,000.- Fee: \$ 3,684.-

Current use: Empty lot owe 75.00 copy

If the location is currently vacant, what was prior use: N/A

Approximately how long has it been vacant: N/A minor

Proposed use: 2,000 sq. ft. commercial rental units Site Plan waiting for approval

Project description:

Contractor's name, address & telephone: Patco Construction, 1293 Main St. Sanford, ME. 04073 - 324-5574

Who should we contact when the permit is ready: Dennis Waters 651-0798 300-72004

Mailing address: SAME

We will contact you by phone when the permit is ready. You must come in and pick up the permit and review the requirements before starting any work, with a Plan Reviewer. A stop work order will be issued and a \$100.00 fee if any work starts before the permit is picked up. PHONE: SAME

RECEIVED

IF THE REQUIRED INFORMATION IS NOT INCLUDED IN THE SUBMISSIONS THE PERMIT WILL BE AUTOMATICALLY DENIED AT THE DISCRETION OF THE BUILDING/PLANNING DEPARTMENT, WE MAY REQUIRE ADDITIONAL INFORMATION IN ORDER TO APPROVE THIS PERMIT.

I hereby certify that I am the Owner of record of the named property, or that the owner of record authorizes the proposed work and that I have been authorized by the owner to make this application as his/her authorized agent. I agree to conform to all applicable laws of this jurisdiction. In addition, if a permit for work described in this application is issued, I certify that the Code Official's authorized representative shall have the authority to enter all areas covered by this permit at any reasonable hour to enforce the provisions of the codes applicable to this permit.


Signature of applicant: Dennis Waters Date: 1/6/04

This is NOT a permit, you may not commence ANY work until the permit is issued. If you are in a Historic District you may be subject to additional permitting and fees with the Planning Department on the 4th floor of City Hall



PATCO
CONSTRUCTION, INC.

Mr. Michael Nugent
City of Portland
City Hall room 315
389 Congress Street
Portland, ME 04101



RE: 557 Riverside/Six G's Coed LLC/ Phoenix Welding *MN*

Dear Michael:

Attached please find the following items to complete our building permit application per your request.

- Geotechnical report by S.W. Cole Engineering, Inc. *Rec'd*
- Statement of special inspection by Steven R. Grant, P.E.
- 8 ½ x 11" detail for masonry veneer wall by Steven R. Grant, P.E.
- Site plans approval letter from the City of Portland dated January 5, 2004 *M*
- Copy of original building permit application cover letter.

If you have any questions or need additional information, call me at 651-0798 or 324-5574.

Sincerely,

Dennis Waters
Vice President

DMW/klf

S E A M

Structural Engineering Association of Maine

STATEMENT OF SPECIAL INSPECTIONS

PROJECT: Six G's COED L.L.C. / PHOENIX WELDING
 LOCATION: PORTLAND, MAINE
 PERMIT APPLICANT: PATCO CONSTRUCTION, INC
 APPLICANT'S ADDRESS: 1293 MAIN ST.
SANFORD, ME 04073
 STRUCTURAL ENGINEER OF RECORD: STEVEN R. GRANT, P.E. SRG ENGINEERING, INC
Name Firm
 ARCHITECT OF RECORD: JOHN EINSIEDLER (SAME)
Name Firm


This Statement of Special Inspections is submitted in accordance with Section 1705.0 of the 1993 BOCA National Building Code. It includes a listing of special inspections applicable to this project as well as the name of the Special Inspector, and the names of other agencies intended to be retained for conducting these inspections.

The Special Inspector shall keep records of all inspections listed herein, and shall furnish inspection reports to the Code Official and to the Registered Design Professional of Record. All discrepancies shall be brought to the immediate attention of the Contractor for correction. If the discrepancies are not corrected, the discrepancies shall be brought to the attention of the Code Official and to the Registered Design Professional of Record. Interim reports shall be submitted to the Code Official and to the Registered Design Professional of Record monthly, unless more frequent submissions are requested by the Code Official.

Job site safety is solely the responsibility of the Contractor. Materials and activities to be inspected are not to include the Contractor's equipment and methods used to erect or install the materials listed.

Prepared By:

STEVEN R. GRANT, P.E.
NAME
[Signature] 1-22-04
SIGNATURE DATE



Applicant's Authorization:

Building Code Official:

SIGNATURE DATE

SIGNATURE DATE

S E A M

Structural Engineering Association of Maine

LIST OF AGENTS

PROJECT: Six G's COED L.L.C / PHOENIX WELDING
STRUCTURAL ENGINEER OF RECORD: STEVEN R. GRANT SRG ENGINEERING, INC.
Name Firm
PO Box 925 Gray, ME 04039
Address
ARCHITECT OF RECORD: JOHN EINSTEADLER (SAME)
Name Firm
148 SEA ROAD, KENNEBUNK, ME 04043
Address

Following is the List of Agents selected for performance of Special Inspections for this project.

- | | Name | Firm |
|-----------------------|-----------------------------|------------------------------|
| 1. Special Inspector | <u>STEVEN R. GRANT</u> | <u>SRG ENGINEERING, INC.</u> |
| 2. Testing Laboratory | <u>J. W. COLE ENG. INC.</u> | <u>(SAME)</u> |
| 3. Testing Laboratory | _____ | _____ |
| 4. | _____ | _____ |
| 5. | _____ | _____ |
| 6. | _____ | _____ |
| 7. | _____ | _____ |
| 8. | _____ | _____ |
| 9. | _____ | _____ |
| 10. | _____ | _____ |

SCHEDULE OF SPECIAL INSPECTION SERVICES

PROJECT:

PAGE ___ OF ___

| MATERIAL / ACTIVITY | ITEM | SERVICE | APPLICABLE TO THIS PROJECT | | | | | | |
|--|------------------------------------|---|----------------------------|--|----------|---------------|----------------|--------|--|
| | | | Y/N | EXTENT (All, Sample, Other, None) | COMMENTS | AGENT # | DATE COMPLETED | REV. # | |
| 1705.3 STEEL CONSTRUCTION | 1.00 | | | | | | | | |
| Steel Fabrication <i>V.P IS A CERTIFIED PLANT, THIS IS NOT READ BY SAG.</i> | | In-plant review Part A - Fabrication procedures | | | | NR (NOT READ) | | | |
| | | Part B - Procedures implementation Review conformance to Part A | | SER to determine extent after completion of Part A | | NR | | | |
| | | Review material certificates of compliance (Bolts, nuts, washers, structural steel, & weld filler material) | | | | | | | |
| | | Review connections | | | | NR | | | |
| | | Review welding of seismic-resisting system in Cat. "C" buildings | | | | NR | | | |
| Steel Erection | | Review welder certification | | | | NR | | | |
| | X | Review materials certificates of compliance (Bolts, nuts, washers, & weld filler material) | | | | | | | |
| | X | Review primary steel connections | | | | | | | |
| | X | Moment connections | | | | | | | |
| | X | Shear connections | | | | | | | |
| | X | Bracing connections | | | | | | | |
| | | Review welded Cat. "C" seismic connections | | | | NR | | | |
| | | Review welded column splices | | | | NR | | | |
| | | Review base metal testing for "t" > 1 1/2" | | | | NR | | | |
| | X | Review secondary steel connections | | | | | | | |
| | X | Girts | | | | | | | |
| | X | Steel deck | | | | | | | |
| | | Lintels | | | | NR | | | |
| | Review installation of shear studs | | | | NR | | | | |
| X | Review Details / Steel Frame | | | | | | | | |

All Steel Construction Special Inspections have been completed in accordance with BOCA Section 1705.3

Special Inspector _____ Date _____

SCHEDULE OF SPECIAL INSPECTION SERVICES

PROJECT:

PAGE ___ OF ___

| MATERIAL / ACTIVITY | ITEM | SERVICE | APPLICABLE TO THIS PROJECT | | | | | | |
|------------------------------|------|--|----------------------------|-----------------------------------|----------|---------|----------------|--------|--|
| | | | Y/N | EXTENT (All, Sample, Other, None) | COMMENTS | AGENT # | DATE COMPLETED | REV. # | |
| 1705.4 CONCRETE CONSTRUCTION | 2.00 | | | | | | | | |
| Concrete Materials | X | Review materials (ACI Chapter 3) | | | | | | | |
| | X | Review mix design (ACI Chapter 4) | | | | | | | |
| | X | Review reinforcing certification & weldability (ASTM A706) if required | | | | | | | |
| Placing Reinforcement | X | Review condition & placement of reinforcing and prestressing steel (ACI 318 7.4-7.7) | | | | | | | |
| | | Review welding of reinforcing in Cat "C" seismic-resisting systems | | | | N.R. | | | |
| Formwork | | Review formwork (ACI 318 6.1) | | | | NR | | | |
| | | Review form removal & reshoring (ACI 318 6.2) | | | | NR | | | |
| Concrete Operations | X | Review concrete strength tests (ACI 318 5.6) | | | | | | | |
| | X | Review mix proportions and technique (ACI 318 5.2, 5.3, 5.4, & 5.8) | | | | | | | |
| | X | Review concrete placement (ACI 318 5.9 & 5.10) | | | | JW COLE | | | |
| | | Review curing technique & temperature (ACI 318 5.11, 5.12, & 5.13) | | | | | | | |
| Prestressing Operations | | Review application of prestressing force (ACI 318 18.18) | | | | | | | |
| | | Review grouting of bonded prestressing tendons in Cat. "C" seismic-resisting systems | | | | | | | |
| Precast Manufacturing | | In-plant review Part A - Fabrication procedures | | | | | | | |
| | | Part B - Procedures implementation Review conformance to Part A | | | | | | | |
| Erection of Precast Concrete | | Review erection of precast units | | | | | | | |
| | | Review key reinforcement | | | | | | | |
| | | Review key grouting | | | | | | | |
| | | Review concrete topping | | | | | | | |
| | | Review connections | | | | | | | |

All Concrete Construction Special Inspections have been completed in accordance with BOCA Section 1705.4

Special Inspector _____ Date _____

SCHEDULE OF SPECIAL INSPECTION SERVICES

PROJECT:

PAGE ___ OF ___

| MATERIAL / ACTIVITY | ITEM | SERVICE | APPLICABLE TO THIS PROJECT | | | | | | |
|--|------|--|----------------------------|-----------------------------------|----------|---------|----------------|--------|--|
| | | | Y/N | EXTENT (All, Sample, Other, None) | COMMENTS | AGENT # | DATE COMPLETED | REV. # | |
| 1705.5 MASONRY CONSTRUCTION | 3.00 | | | | | | | | |
| Materials NA | | Review materials certification Masonry units Reinforcing steel | | | | | | | |
| | | Review grout materials & mix design | | | | | | | |
| | | Review mortar materials & mix design | | | | | | | |
| | | Review strength determination Unit strength method. Review unit strengths & grout, mortar mixes | | | | | | | |
| | | Prism strength method. Review pre-construction test results. Field tests during construction. | | | | | | | |
| | | Grout testing Determine compressive strength | | | | | | | |
| | | Mortar testing Field test compressive strength ASTM C780 (Reqd. only if property reqs of ASTM C270 are used) | | | | | | | |
| General Masonry Work NA | | Review mortar mix proportions & mixing (ACI 530.1: 2.3.2.5) | | | | | | | |
| | | Review grout mix proportions & mixing (ACI 530.1: 4.2.2) | | | | | | | |
| | | Review general installation of mortar, grout, masonry units. (ACI 530.1: 2.3.3.3, 4.3.3) | | | | | | | |
| | | Review installation of horiz., vert., & joint reinforcing (incl. location, sizes, splices, & positioning devices) (ACI 530, Ch. 8) | | | | | | | |
| | | Review hot/cold weather procedures (ACI 530.1: 2.3.2.2, 2.3.2.3) | | | | | | | |
| | | Review installation of anchorage devices (ACI 530: 4.2, 5.14) | | | | | | | |
| | | Review installation of lintels | | | | | | | |
| | | Review welding of reinf., grouting, consolidation and reconsolidation for seismic Cat. "C" buildings | | | | | | | |

All Masonry Construction Special Inspections have been completed in accordance with BOCA Section 1705.5

Special Inspector _____ Date _____

SRG ENGINEERING, INC.

P.O. Box 925
GRAY, ME 04039

SCHEDULE OF SPECIAL INSPECTION SERVICES

PROJECT:

PAGE ___ OF ___

| MATERIAL / ACTIVITY | ITEM | SERVICE | APPLICABLE TO THIS PROJECT | | | | | | |
|--|------|---|----------------------------|-----------------------------------|----------|---------|----------------|--------|--|
| | | | Y/N | EXTENT (All, Sample, Other, None) | COMMENTS | AGENT # | DATE COMPLETED | REV. # | |
| 1705.6 WOOD CONSTRUCTION | 4.00 | | | | | | | | |
| Wood Truss Fabrication NA | | In-plant review Part A- Fabrication procedures | | | | | | | |
| | | Part B- Procedures implementation Review conformance to Part A | | | | | | | |
| | | Review member arrangement | | | | | | | |
| | | Check for TPI Stamp | | | | | | | |
| Wood Truss Materials NA | | Review lumber Wood species Grade stamps Moisture content | | | | | | | |
| | | Review connector plates Size Gage Orientation Location Fit | | | | | | | |
| Wood Truss Erection NA | | Review storage at site | | | | | | | |
| | | Review permanent bracing | | | | | | | |
| | | Review field connections | | | | | | | |
| Glulam Fabrication NA | | In-plant review Part A- Fabrication procedures | | | | | | | |
| | | Part B- Procedures implementation Review conformance to Part A | | | | | | | |
| Glulam Materials NA | | Review wood species and grade | | | | | | | |
| Glulam and Solid Timber Erection NA | | Review connections | | | | | | | |
| | | Bolted connections | | | | | | | |
| | | Connection fittings | | | | | | | |
| Seismic-Resisting System (Seis. Perf. Cat. "C") NA | | Review seismic connections Nailed connections Bolted connections Structural glued connections Other seismic fasteners | | | | | | | |

All Wood Construction Special Inspections have been completed in accordance with BOCA Section 1705.6

Special Inspector _____ Date _____

| PROJECT: | | SCHEDULE OF SPECIAL INSPECTION SERVICES | | | | | | PAGE ___ OF ___ | |
|--------------------------------|------|--|----------------------------|-----------------------------------|-----------------|---------|----------------|-----------------|--|
| MATERIAL / ACTIVITY | ITEM | SERVICE | APPLICABLE TO THIS PROJECT | | | | | | |
| | | | Y/N | EXTENT (All, Sample, Other, None) | COMMENTS | AGENT # | DATE COMPLETED | REV. # | |
| 1705.7 PREPARED FILL | 5.00 | | | | | | | | |
| Site Preparation | X | Review site preparation prior to prepared fill placement | | | S.W. COLE (SWC) | | | | |
| During Fill Placement | X | Review compliance to soils report Material | | | SWC | | | | |
| | X | Lift thickness | | | SWC | | | | |
| Evaluation of in-Place Density | X | Review in-place dry density for compliance with soils report | | | SWC | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |

All Prepared Fill Special Inspections have been completed in accordance with BOCA Section 1705.7 Special Inspector _____ Date _____

SCHEDULE OF SPECIAL INSPECTION SERVICES

PROJECT:

PAGE ___ OF ___

| MATERIAL / ACTIVITY | ITEM | SERVICE | APPLICABLE TO THIS PROJECT | | | | | | |
|----------------------------|------|---|----------------------------|-----------------------------------|----------|---------|----------------|--------|--|
| | | | Y/N | EXTENT (All, Sample, Other, None) | COMMENTS | AGENT # | DATE COMPLETED | REV. # | |
| 1705.8 PILE FOUNDATIONS | 6.00 | | | | | | | | |
| Pile Fabrication NA | | In-plant review Part A- Fabrication procedures | | | | | | | |
| | | Part B- Procedures implementation Review conformance to Part A | | | | | | | |
| Pile Driving NA | | Review pile driving records | | | | | | | |
| | | Review load test results | | | | | | | |
| | | Review pile driving equipment & procedure | | | | | | | |
| Pile Materials NA | | Review accessories | | | | | | | |
| | | Pile tip assembly | | | | | | | |
| | | Pile splice assembly | | | | | | | |
| | | Rock anchors | | | | | | | |
| | | Tendons | | | | | | | |
| | | Review steel piles | | | | | | | |
| | | Material identification markings | | | | | | | |
| | | Inspection of corrosion protection | | | | | | | |
| | | Review timber piles | | | | | | | |
| | | Wood species | | | | | | | |
| | | Butt or tip diameter | | | | | | | |
| | | Grade stamps/markings/treatment | | | | | | | |
| | | Review other pile systems | | | | | | | |
| Prestressed Concrete Piles | | See "Precast Concrete" | | | | | | | |

All Pile Foundation Special Inspections have been completed in accordance with BOCA Section 1705.8

Special Inspector _____ Date _____

SRG ENGINEERING, INC.
 P.O. Box 925
 GRAY, ME 04039

| PROJECT: | | SCHEDULE OF SPECIAL INSPECTION SERVICES | | | | PAGE | OF | |
|-----------------------|------|---|-----|-----------------------------------|--|---------|----------------|--------|
| MATERIAL / ACTIVITY | ITEM | SERVICE | Y/N | EXTENT (All, Sample, Other, None) | APPLICABLE TO THIS PROJECT COMMENTS | AGENT # | DATE COMPLETED | REV. # |
| 1705.12 SPECIAL CASES | 7.00 | | | | | | | |
| N.A. | | | | | | | | |

All Special Case Special Inspections have been completed in accordance with BOCA Section 1705.12 Special Inspector _____ Date _____

**BEARING CAPACITY ASSESSMENT
PROPOSED PHOENIX WELDING BUILDING
RIVERSIDE STREET
PORTLAND, MAINE**

04-0067 February 12, 2004

Prepared for:

PATCO Construction
Attn: Dennis Waters
1293 Maine Street
Sandford, ME 04073

Prepared by:

S.W.COLE ENGINEERING, INC
Timothy J. Boyce, P.E.
286 Portland Road
Gray, Maine 04039



S.W. COLE
ENGINEERING, INC.

• Geotechnical Engineering • Field & Lab Testing • Scientific & Environmental Consulting

04-0067

February 12, 2004

PATCO Construction
Attn: Dennis Waters
1293 Maine Street
Sandford, ME 04073

Subject: Bearing Capacity Assessment
Proposed Phoenix Welding Building
Riverside Street
Portland, Maine

Dear Mr. Waters:

In accordance with our Agreement dated January 29, 2004, we have observed test pit explorations and made a bearing capacity assessment of the subsurface soils for foundation support of the proposed building at the above referenced site. This report summarizes our findings and recommendations and its contents are subject to the limitations set forth in Attachment A.

PROPOSED CONSTRUCTION

Based on information provided by PATCO Construction (PATCO), we understand the building will be a single-story, on-grade, pre-engineered metal building occupying a plan area of about 14,000 square-feet. According to the site plans prepared by Sebago Technics, we understand the building will have a finished floor elevation of 101.0 feet (project datum) and require tapered fills approaching 3 to 4 feet in thickness.

EXPLORATION WORK

Eight test pit explorations were made at the site on February 3, 2004 by Storey Brothers of Cumberland, Maine working under contract to PATCO. The test pit locations were selected by S.W. COLE ENGINEERING, INC. based on a site plan prepared by Sebago Technics (project civil engineer). The test pits were established in the field based on taped measurements from staked building corners established by PATCO. The approximate test pit locations are shown on the "Exploration Location Plan" attached as



04-0067
February 12, 2004

Sheet 1. Logs of the test pits are attached as Sheets 2 through 5. A key to the notes and symbols used on the logs is attached as Sheet 6.

SUBSURFACE CONDITIONS

The test pits generally encountered a soil profile consisting of 2 to 5.5 feet of clayey sand with silt (fill) and gravelly silty sand (fill) overlying a ½ to 1-foot thick relic topsoil layer with roots overlying up to 2 feet of orange-brown silty sand overlying very stiff brown silty clay. The fill and relic topsoil layers were not encountered in test pits TP-3 and TP-4. The exposed topsoil layer at TP-3 and TP-4 was observed to be 1 to 3 feet thick. The test pits were terminated at depths of 4.5 and 8.0 feet below the ground surface.

Slight groundwater seepage was observed in the test pits to depths of about 6 feet below the ground surface. The surface soils were frozen to a depth of 1 to 3.5 feet and the very stiff brown clays appeared wet of the optimum moisture content needed for compaction. Groundwater should be expected to fluctuate seasonally and during periods of heavy precipitation or snow melt.

Refer to the attached logs for more detailed descriptions of the subsurface findings at the test pit locations.

EVALUATION AND RECOMMENDATIONS

Based on the subsurface findings, the proposed construction appears feasible from a geotechnical standpoint. However, the fill and relic topsoil layers underlying the proposed foundations must be overexcavated to expose stable native non-organic soils (orange-brown silty sand or very stiff brown clay) and backfilled with compacted granular borrow. The width of overexcavation must extend one foot outward from the edge of footings for each foot of overexcavation depth. Based on the subsurface findings, it should be anticipated that it will be necessary to overexcavate below perimeter footings along the front wall, the two end walls and the westerly half of the back wall of the proposed building and interior footings within this general area. The overexcavated area should be backfilled with granular fill compacted in 1-foot lifts to at least 95 percent of its maximum dry density as determined by ASTM D-1557. The



04-0067
February 12, 2004

existing fill soils may be suitable for reuse as compacted fill provided they are at a moisture conditions that is suitable for the required compaction.

We recommend that excavation to subgrade be completed with a smooth-edged bucket to preclude disturbance of the olive-brown clays and orange brown silty sands anticipated at footing grade and at the base of overexcavated footing areas. We recommend that a S.W.COLE ENGINEERING, INC. observe overexcavated areas prior to backfilling and footing subgrades prior to the placement of foundation concrete.

For spread footings founded on properly prepared subgrades, we recommend an allowable soils bearing pressure of 2.0 ksf with a base friction factor of 0.35 for foundation design. Foundations exposed to freezing temperatures must be placed at least 4.5 feet below exterior finish grades in order to provide frost protection. We recommend that a perimeter underdrain be installed at footing grade. The underdrain must have a gravity outlet.


As discussed, S.W.COLE ENGINEERING, INC. is available to provide geotechnical observations and testing of soil, concrete, asphalt and structural steel construction materials during construction if necessary.


CLOSURE

If you have any questions or require additional assistance, please do not hesitate to contact us.

Sincerely,

S.W.COLE ENGINEERING, INC.


Timothy J. Boyce, P.E.
Senior Geotechnical Engineer



Attachment A
Limitations


This report has been prepared for the exclusive use of PATCO Construction for specific application to the Proposed Phoenix Welding Building on Riverside Street in Portland, Maine as described herein. Our services were limited by PATCO Construction to an assessment of soil bearing capacity only and a deeper soils investigation to evaluate settlement and other geotechnical considerations was specifically excluded by PATCO Construction. PATCO Construction has agreed to protect and hold harmless S.W.COLE ENGINEERING, INC. from any and all claims, including third-party claims, for damages or consequential damages due to underlying soil conditions including but not limited to post-construction settlement. S.W.COLE ENGINEERING, INC. has endeavored to conduct the work in accordance with generally accepted soil and foundation engineering practices. No other warranty, expressed or implied, is made.

The soil profiles described in the report are intended to convey general trends in subsurface conditions. The boundaries between strata are approximate and are based upon interpretation of exploration data and samples. Observations have been made during exploration work to assess site groundwater levels. Fluctuations in water levels will occur due to variations in rainfall, temperature, and other factors.

The analyses performed during this investigation and recommendations presented in this report are based in part upon the data obtained from subsurface explorations made at the site. Variations in subsurface conditions may occur between explorations and may not become evident until construction. If variations in subsurface conditions become evident after submission of this report, it will be necessary to evaluate their nature and to review the recommendations of this report.

S.W.COLE ENGINEERING, INC.'s scope of work has not included the investigation, detection, or prevention of any Biological Pollutants at the project site or in any existing or proposed structure at the site. The term "Biological Pollutants" includes, but is not limited to, molds, fungi, spores, bacteria, and viruses, and the byproducts of any such biological organisms.

Recommendations contained in this report are based substantially upon information provided by others regarding the proposed project. In the event that any changes are made in the design, nature, or location of the proposed project, S.W.COLE ENGINEERING, INC. should review such changes as they relate to analyses associated with this report. Recommendations contained in this report shall not be considered valid unless the changes are reviewed by S.W.COLE ENGINEERING, INC.



PATCO CONSTRUCTION
EXPLORATION LOCATION PLAN
 PROPOSED PHOENIX WELDING BUILDING
 RIVERSIDE STREET
 PORTLAND, MAINE

PROJECT NO. 04-0087
 SCALE: As shown
 SHEET: 1

DATE: February 11, 2004

LEGEND

Approximate Test Pit Location

NOTES

1. Base plan prepared by Sebago Technics
2. Exploration locations determined in the field by taped measurements from staked building corners.



S.W. COLE ENGINEERING, INC.

TEST PIT LOGS

PROJECT/CLIENT: PROPOSED PHOENIX WELDING BUILDING / PATCO CONSTRUCTION

LOCATION: PORTLAND, MAINE

PROJECT NO. 04-0067

| TEST PIT <u>TP-1</u> | | | |
|-------------------------------|------------|--|--------------|
| DATE: <u>2/3/04</u> | | SURFACE ELEVATION: <u>99' +/-</u> | |
| SAMPLE NO. | DEPTH (FT) | STRATUM DESCRIPTION | TEST RESULTS |
| | 3.2' | BROWN CLAYEY SAND SOME GRAVEL SOME ORGANICS (FILL) | w = 36.2 % |
| | 4.0' | BROWN SAND SOME SILT (FILL) | |
| S-1 | 4.5' | -VERY STIFF- BROWN SILTY CLAY $c_u = 6 - 8 \text{ KSF}$ | |
| | | BOTTOM OF EXPLORATION AT 4.5' | |
| COMPLETION DEPTH: <u>4.5'</u> | | NOTES: 2.5' FROST MILD SEEPAGE TO 4.4' NO CAVING | |

| TEST PIT <u>TP-2</u> | | | |
|-------------------------------|------------|--|------------------------------|
| DATE: <u>2/3/04</u> | | SURFACE ELEVATION: <u>99' +/-</u> | |
| SAMPLE NO. | DEPTH (FT) | STRATUM DESCRIPTION | TEST RESULTS |
| | 2.0' | BROWN CLAYEY SAND SOME GRAVEL SOME ORGANICS (FILL) | w = 19.9 % w = 30.4 % |
| | 2.8' | RELIC TOPSOIL HORIZON | |
| S-1 | 4.5' | ORANGISH BROWN SILT AND SAND | |
| S-2 | 6.5' | BROWN SILTY CLAY DESICCATED -VERY STIFF- $c_u = 5 - 7 \text{ KSF}$ | |
| | | BOTTOM OF EXPLORATION AT 6.5' | |
| COMPLETION DEPTH: <u>6.5'</u> | | NOTES: 2.5' FROST MILD SEEPAGE TO 6.0' NO CAVING | |



S.W. COLE ENGINEERING, INC.

TEST PIT LOGS

PROJECT/CLIENT: PROPOSED PHOENIX WELDING BUILDING / PATCO CONSTRUCTION

LOCATION: PORTLAND, MAINE

PROJECT NO. 04-0067

| TEST PIT <u>TP-3</u> | | | |
|-------------------------------|------------|--|--------------|
| DATE: <u>2/3/04</u> | | SURFACE ELEVATION: <u>99' +/-</u> | |
| SAMPLE NO. | DEPTH (FT) | STRATUM DESCRIPTION | TEST RESULTS |
| | 1.1' | LIGHT BROWN SANDY TOPSOIL | w = 31.0% |
| | | ORANGISH BROWN SILTY SAND | |
| | 3.5' | BROWN SILTY CLAY | |
| S-1 | 4.5-5' | $c_p = 6 - 8 \text{ KSF}$ | |
| | 6.0' | BOTTOM OF EXPLORATION AT 6.0' | " |
| COMPLETION DEPTH: <u>6.0'</u> | | NOTES: 1.5' FROST MILD SEEPAGE TO 5.2' NO CAVING | |

| TEST PIT <u>TP-4</u> | | | |
|-------------------------------|------------|--|--------------|
| DATE: <u>2/3/04</u> | | SURFACE ELEVATION: <u>98' +/-</u> | |
| SAMPLE NO. | DEPTH (FT) | STRATUM DESCRIPTION | TEST RESULTS |
| | | ORGANIC MATTER (ROOTS) WITH SILTY SAND (FILL) | |
| | 3.0' | BROWN SILTY CLAY | |
| | 5.5' | $c_p = 5 - 7 \text{ KSF}$ -VERY STIFF- | |
| | | BOTTOM OF EXPLORATION AT 5.5' | |
| COMPLETION DEPTH: <u>5.5'</u> | | NOTES: 2.0' FROST MILD SEEPAGE TO 4.8' NO CAVING | |



S.W. COLE ENGINEERING, INC.

TEST PIT LOGS

PROJECT/CLIENT: PROPOSED PHOENIX WELDING BUILDING; PATCO CONSTRUCTION

LOCATION: PORTLAND, MAINE

PROJECT NO. 04-0067

| TEST PIT TP-5 | | | |
|------------------------|------------|----------------------------------|--|
| DATE: 2/3/04 | | SURFACE ELEVATION: 100' +/- | |
| SAMPLE NO | DEPTH (FT) | STRATUM DESCRIPTION | TEST RESULTS |
| | | BROWN GRAVELLY SILTY SAND (FILL) | |
| | 3.5' | | |
| | 4.3' | RELIC TOPSOIL HORIZON WITH ROOTS | |
| | 5.0' | BROWN SILTY SAND SOME CLAY | |
| | 6.5' | BROWN SILTY CLAY -VERY STIFF- | q _p = 5 - 8 KSF |
| | | BOTTOM OF EXPLORATION AT 6.5' | |
| COMPLETION DEPTH: 6.5' | | | NOTES: 4.0' FROST NO SEEPAGE NO CAVING |

| TEST PIT TP-6 | | | |
|------------------------|------------|--------------------------------------|---|
| DATE: 2/3/04 | | SURFACE ELEVATION: 99' +/- | |
| SAMPLE NO | DEPTH (FT) | STRATUM DESCRIPTION | TEST RESULTS |
| | | BROWN CLAYEY SAND SOME GRAVEL (FILL) | |
| | 4.0' | | |
| | 5.0' | RELIC TOPSOIL HORIZON | |
| | 6.0' | BROWN SILTY CLAY -VERY STIFF- | c _u = 5.5 - 6.5 KSF |
| | | BOTTOM OF EXPLORATION AT 6.0' | |
| COMPLETION DEPTH: 6.0' | | | NOTES: 2.5' FROST MINOR SEEPAGE NO CAVING |



S.W. COLE ENGINEERING, INC.

TEST PIT LOGS

PROJECT/CLIENT: PROPOSED PHOENIX WELDING BUILDING / PATCO CONSTRUCTION

LOCATION: PORTLAND, MAINE

PROJECT NO. 04-0087

| TEST PIT <u>TP-7</u> | | | |
|-------------------------------|------------|---|--------------|
| DATE: <u>2/3/04</u> | | SURFACE ELEVATION: <u>100' +/-</u> | |
| SAMPLE NO. | DEPTH (FT) | STRATUM DESCRIPTION | TEST RESULTS |
| | 1.0' | BROWN GRAVELLY SAND (FILL) | |
| | | BROWN CLAYEY SAND SOME GRAVEL (FILL) | |
| | 5.0' | RELIC TOPSOIL HORIZON | |
| | 6.0' | BROWN SILTY CLAY -VERY STIFF- $c_u = 7 - 8$ KSF | |
| | 8.0' | BOTTOM OF EXPLORATION AT 8.0' | |
| COMPLETION DEPTH: <u>8.0'</u> | | NOTES: 1.0' FROST MINOR SEEPAGE NO CAVING | |

| TEST PIT <u>TP-8</u> | | | |
|-------------------------------|------------|---|--------------|
| DATE: <u>2/3/04</u> | | SURFACE ELEVATION: <u>100' +/-</u> | |
| SAMPLE NO. | DEPTH (FT) | STRATUM DESCRIPTION | TEST RESULTS |
| S-1 | 0.2' | BROWN GRAVELLY SILTY SAND SOME CLAY (FILL) | |
| | 5.5' | RELIC TOPSOIL HORIZON | |
| | 6.0' | BROWN SILTY CLAY -VERY STIFF- | |
| | 6.5' | BOTTOM OF EXPLORATION AT 6.5' | |
| COMPLETION DEPTH: <u>6.5'</u> | | NOTES: 3.5' FROST MINOR SEEPAGE NO CAVING | |



KEY TO THE NOTES & SYMBOLS

Test Boring and Test Pit Explorations

All stratification lines represent the approximate boundary between soil types and the transition may be gradual.

Key to Symbols Used:

| | | |
|----------------|---|--|
| w | - | water content, percent (dry weight basis) |
| q _u | - | unconfined compressive strength, kips/sq. ft. - based on laboratory unconfined compressive test |
| S _v | - | field vane shear strength, kips/sq. ft. |
| L _v | - | lab vane shear strength, kips/sq. ft. |
| q _p | - | unconfined compressive strength, kips/sq. ft. based on pocket penetrometer test |
| O | - | organic content, percent (dry weight basis) |
| W _L | - | liquid limit - Atterberg test |
| W _P | - | plastic limit - Atterberg test |
| WOH | - | advance by weight of hammer |
| WOM | - | advance by weight of man |
| WOR | - | advance by weight of rods |
| HYD | - | advance by force of hydraulic piston on drill |
| RQD | - | Rock Quality Designator - an index of the quality of a rock mass. RQD is computed from recovered core samples. |
| γ _T | - | total soil weight |
| γ _B | - | buoyant soil weight |
| HSA | - | Hollow Stem Auger |
| HW | - | 4" Casing |
| NW | - | 3" Casing |
| SS | - | split-spoon sampler |

Description of Proportions:

0 to 5% TRACE

5 to 12% SOME

12 to 35% "Y"

35+% AND

REFUSAL: Test Boring Explorations - Refusal depth indicates that depth at which, in the drill foreman's opinion, sufficient resistance to the advance of the casing, auger, probe rod or sampler was encountered to render further advance impossible or impracticable by the procedures and equipment being used.

REFUSAL: Test Pit Explorations - Refusal depth indicates that depth at which sufficient resistance to the advance of the backhoe bucket was encountered to render further advance impossible or impracticable by the procedures and equipment being used.

Although refusal may indicate the encountering of the bedrock surface, it may indicate the striking of large cobbles, boulders, very dense or cemented soil, or other buried natural or man-made objects or it may indicate the encountering of a harder zone after penetrating a considerable depth through a weathered or disintegrated zone of the bedrock.

Mar. 3. 2004 3:47PM VP BUILDINGS CS 6088822370

No. 2783 P. 1

Varco Pruden Buildings, Inc.
WISCONSIN SERVICE CENTER
 ENGINEERING GROUP

Date: 03/03/2004

To: Bill Rudman of PATCO

Copy:

Fax: 207-324-1643

number of pages 1

Copy fax:

From: Carl W. Walker, PE
 WI Service Center


ph: 608-882-5001 ext. 415
 fax: 608-882-2370
 e-mail: cwalker@vp.com

SUBJECT: WI0301217-01
 Response to Code Compliance

Bill, below should address the following items required by the inspector:

- Unbalanced and Drift snow load – none required for the design of this project.
- Deflection Limits –L/150 vertical, L/120 horizontal for metal roof and walls.
- Load Combinations – the load combinations used are based upon the requirements of BOCA 99. See the report supplied by VP Buildings labeled “reactions package” to show all load combinations used.
- Flat snow roof snow load = 49.00 psf as shown on letter of certification
- Seismic soil profile type is S1 as defined to VP Buildings
- Fire Classification of roof covering – Class B – metal roof panel.

If you have any further questions, please let us know.



651-2809
TODAY
MONDAY

Form # P 04

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK

CITY OF PORTLAND

BUILDING INSPECTION

PERMIT

DEPT. OF BUILDING INSPECTION
CITY OF PORTLAND, ME
MAR 26 2004
RECEIVE

Permit Number: 040015

Please Read Application And Notes, If Any, Attached

This is to certify that Six G's Coed Llc /Patco Construction
has permission to Commercial / Build new 2,000 sq. Ft. Commercial Rental unit 1400 Soft Building
AT 563 Riverside St Portland, ME 04101 306 B001001

provided that the person or persons who apply for or accept this permit shall comply with all of the provisions of the Statutes of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of buildings and structures, and of the application on file in this department.

Apply to Public Works for street line and grade if nature of work requires such information.

Notification of inspection must be given and when permission procedure is complete this building or part thereof shall be inspected or otherwise closed-in within 24 HOURS NO OTHER INSPECTION REQUIRED.

A certificate of occupancy must be procured by owner before this building or part thereof is occupied.

OTHER REQUIRED APPROVALS
Fire Dept. [Signature]
Health Dept. _____
Appeal Board _____
Other _____
Department Name _____

[Signature] 3/26/04
Director - Building & Inspection Services

PENALTY FOR REMOVING THIS CARD

306-B-1-7

CITY OF PORTLAND, MAINE
DEVELOPMENT REVIEW APPLICATION
PLANNING DEPARTMENT PROCESSING FORM
Planning Copy

2003-0210
Application I. D. Number
10/08/2003
Application Date
Office/Industrial Building
Project Name/Description

Six Gs Coed, LLC
Applicant
557 Riverside Street, Portland, ME 04103
Applicant's Mailing Address

567 - 567 Riverside St, Portland, Maine
Address of Proposed Site
312 B003
Assessor's Reference: Chart-Block-Lot

Consultant/Agent
Applicant Ph: (207) 797-5830 Agent Fax:
Applicant or Agent Daytime Telephone, Fax

Proposed Development (check all that apply): New Building Building Addition Change Of Use Residential Office Retail
 Manufacturing Warehouse/Distribution Parking Lot Other (specify)

14,000 s.f. Proposed Building square Feet or # of Units
Acreage of Site
IH Zoning

Check Review Required:

- Site Plan (major/minor)
- Flood Hazard
- Zoning Conditional Use (ZBA/PB)
- Subdivision # of lots
- Shoreland
- Zoning Variance
- PAD Review
- Historic Preservation
- 14-403 Streets Review
- DEP Local Certification
- Other

Fees Paid: Site Plan \$400.00 Subdivision Engineer Review \$1,184.00 Date 03/15/2004

Approval Status:

Reviewer Kandi Talbot MAR 25 2004

- Approved
- Approved w/Conditions See Attached
- Denied

Approval Date 01/05/2004 Approval Expiration 01/05/2005 Extension to Additional Sheets Attached

OK signature date 03/24/2004

Performance Guarantee Required* Not Required

* No building permit may be issued until a performance guarantee has been submitted as indicated below

| | | | |
|--|--------------------|--|-------------------------------|
| <input checked="" type="checkbox"/> Performance Guarantee Accepted | 03/24/2004 date | \$76,300.00 amount | 04/17/2005 expiration date |
| <input checked="" type="checkbox"/> Inspection Fee Paid | 03/23/2004 date | \$1,526.00 amount | |
| <input type="checkbox"/> Building Permit Issue | date | | |
| <input type="checkbox"/> Performance Guarantee Reduced | date | remaining balance | signature |
| <input type="checkbox"/> Temporary Certificate of Occupancy | date | <input type="checkbox"/> Conditions (See Attached) | expiration date |
| <input type="checkbox"/> Final Inspection | date | signature | |
| <input type="checkbox"/> Certificate Of Occupancy | date | | |
| <input type="checkbox"/> Performance Guarantee Released | date | signature | |
| <input type="checkbox"/> Defect Guarantee Submitted | submitted date | amount | expiration date |
| <input type="checkbox"/> Defect Guarantee Released | date | signature | |

BUILDING PERMIT INSPECTION PROCEDURES

Please call 874-8703 or 874-8693 to schedule your inspections as agreed upon

Permits expire in 6 months, if the project is not started or ceases for 6 months.

The Owner or their designee is required to notify the inspections office for the following inspections and provide adequate notice. Notice must be called in 48-72 hours in advance in order to schedule an inspection:

By initializing at each inspection time, you are agreeing that you understand the inspection procedure and additional fees from a "Stop Work Order" and "Stop Work Order Release" will be incurred if the procedure is not followed as stated below.

Pre-construction Meeting: Must be scheduled with your inspection team upon receipt of this permit. Jay Reynolds, Development Review Coordinator at 874-8632 must also be contacted at this time, before any site work begins on any project other than single family additions or alterations.

Footing/Building Location Inspection: Prior to pouring concrete

Re-Bar Schedule Inspection: Prior to pouring concrete

Foundation Inspection: Prior to placing ANY backfill


Framing/Rough Plumbing/Electrical: Prior to any insulating or drywalling

Final/Certificate of Occupancy: Prior to any occupancy of the structure or use. NOTE: There is a \$75.00 fee per inspection at this point.

Certificate of Occupancy is not required for certain projects. Your inspector can advise you if your project requires a Certificate of Occupancy. All projects DO require a final inspection

If any of the inspections do not occur, the project cannot go on to the next phase, REGARDLESS OF THE NOTICE OR CIRCUMSTANCES.


CERIFICATE OF OCCUPANICES MUST BE ISSUED AND PAID FOR, BEFORE THE SPACE MAY BE OCCUPIED



Signature of Applicant/Designee

3/26/04

Date



Signature of Inspections Official

03/26/04

Date

CBL: 306-B 001

Building Permit #: 040015

facsimile transmittal

To: Dennis Waters **From:** Mike Nugent
Fax: 324-1643 **Date:** March 2, 2004
Phone: 324-5574 **Pages:** 1
Re: 563 Riverside St. (306 B001)

Urgent For Review Please Comment Please Reply Please Recycle

Omitted Structural/Code Compliance information:

- 1) Unbalanced and Drift snow load (Sections 1608.5 and 1608.6) ✓
- 2) Deflection limits (Section 1608.5) ✓
- 3) Load Combinations (Section 1613.1) ✓
- 4) Flat roof snow load (Section 1608.3) ✓
- 5) Seismic soil profile type (Section 1610.3.1) ✓
- 6) Fire Classification of roof covering (Section 1506.0) ✓

This is basically it for my review, After I get this info and Planning authorizes the issuance (after the performance guarantees are reviewed and approved etc.) The permit can be issued.

HOODING FOR
PLANNING
APPROVAL
[Signature]

3/26 - K.C. DID FOOTINGS

3/29 MJN DID THE FOUNDATION
WALLS ON THE "RIGHT" SIDE.
REBAR PLACED "STACKED" INSTEAD OF
SIDE BY SIDE SEE FIG 51 ON J2
CALLED STEVE GRANT ENGINEER
PATCO ADVISED HE APPROVED

3/30 rebar for Pour of kicker wall OK JB

3/31 rebar for final Footing (Front wall) OK JB

4/1/04 - Footing + wall - front - OK JM

4-6-04 Plumbing Drp underground