

Casement

SKU: NC6300-CASE

At Paradigm Windows, it all hinges on fitting your specific needs. Like a casement window that swings out. The casement styles provide a clean contemporary look. For a beautiful, open view from your home, Paradigm's Casement windows offer a unique blend of charm and elegance. Three continuous seals of weather-stripping around the window's perimeter provides a barrier to help eliminate drafts and delivers the ultimate in comfort. Custom design enhancements offer the style and versatility you desire. There is also the security and comfort of multi-point locks and ease of cleaning. Casement windows feature our patented multi-chambered, fusion welded sashes and frames, insuring a lifetime of rugged durability.



Attachments

[Brochure](#)

pdf | 5.34 MB

[Warranty](#)

pdf | 1.72 MB

[Features](#) [Options](#) [Colors](#) [Performance](#) [Specifications](#) [Warranty](#) [Installation](#)

- Extruded PVC components produced from commercial quality virgin PVC (unplasticised polyvinyl chloride), conforms to AAMA 303 from sections in one piece, straight, true and smooth. Provide multi-chambered PVC extruded frames and sash in accordance with the manufacturers standard practice. Fusion welded frame joints strong enough to develop full strength of members.
- Locking Device: Locking device shall be Roto X-Drive locking system manufactured by Roto-Frank, Chester, CT. Materials are high pressure zinc die-cast handle, case and sliders (liquid or powder coated painted finish).
- Glass and Glazing: Glass shall conform to DD-G-451 and not less than "B" quality. Factory glazed 3/4" insulating glass conforming to ASTM-E-774, with warm edge seal spacer. Glazing shall be integral glazing type system with architectural back bedded glazing tape and designed to maintain a watertight seal between glass and sash frame. Non-standard glass options will have metal box-type spacer with dual seal system.

