

Installation Scope of Work

Date Prepared: 05/29/2014

Customer Name: Northern New England District
Council of Assembly of God

Contract Number:
Task Order:
Project Destination:
Facility Code:

Contact: Edwin Shearer
Contact Phone:
Street Address: 501 Riverside St

City: Portland
State: ME
Zip Code: 04103

New Construction:
Existing Equipment:

Legend
All items should be checked off
W = Device wired
I = Device installed
T = Device tested

FURNISH AND INSTALL

PART NO	REV #	CLIN	QTY	W	I	I	Group	Sub-Group	EQUIPMENT DESCRIPTION	LOCATION	INDICATE EQUIPMENT/LOCATION CHANGES	NOTE
Profile Codes			1						Profile Codes			
Sensor Devices			1						Sensor Devices			
Transmission Type			1						Transmission Type			
10			1						Account Management - None			
10			1						Guard Response and Training - None			
Guard Response Services			1						Guard Response Services			
20			1						Fire Alarm (Other) Monitoring PROVIDED			
Monitoring Service			1						Monitoring Service PROVIDED			
Primary Monitoring Service			1						Primary Monitoring Service PROVIDED			
40			1						Transmission - Digital Two Line			
55			1						Maintenance Quality Service Plan NOT PROVIDED			
Allowance (Preventative Maintenance)			1						1 Fire Alarm Inspections PROVIDED Allowance for abnormal conditions/ remote locations/ horns&strobes			

9 1 4 0 U E 0 0

Estimate #: 1-WY7VL1

Revision #: 1

Estimate Name: NNEDAssemblyofGodFA

Sales Rep: Sandra Sherry

Sales Rep Phone: 2073965741 207-867-7321

Estimated Install Date:

Town #: 0082-PORTLAND, ME

Customer #: 108202585

Job #: 3



Integrated Security

Installation Scope of Work

<u>PART NO</u>	<u>REV #</u>	<u>CLIN</u>	<u>QTY</u>	<u>W</u>	<u>I</u>	<u>I</u>	<u>Group</u>	<u>Sub-Group</u>	<u>EQUIPMENT DESCRIPTION</u>	<u>LOCATION</u>	<u>INDICATE EQUIPMENT/LOCATION CHANGES</u>	<u>NOTE</u>
Basic Fee			1						Basic Fee			
Fire			1						Inspections Fire Questionnaire			
Smokes, Heats, Pulls			1						Smokes, Heats, Pulls (Normally 1 Test/yr)			
Other			1						Other			
(Preventative Maintenance)												
Regular Labor 411			4						Regular Labor ASSY, FNL, 411			
MCBL-7			1						Accessory, Fire, DACT to Telephone Conn. Cord, 7' Long (2 req.)			
			2						Labor Adjustments			
Labor Adjustments			1									

Notes:

The scope of work is a description of the project and services to be provided. It is a short narrative to include design brief, deliverables both products and services, and project objectives; i.e., "what are we trying to accomplish for the customer?"

SCOPE OF WORK

Contact Information:

Edwin Shearer 207-878-2777

System Operation:

Simplex FA Panel 4001 add dialer and test with Central Station

Programming Info:

Tyco Technician to add dialer and test devices to Central Service

Site Conditions:

Existing Building with Optex/Simplex 4001 Combo to be split due to panel discontinuance for dialer bring Pro-411 hand held programmer

Existing Equipment:

Adding to legacy system; no dismantling required

Customer Expectations:

Operational system approved by Authorities having Jurisdiction

Training Expectations:

Standard

General Comments:

Portland FA Code allows panel replacement or split as long as no new devices are installed; Final sign off and approval comes from AHJ; will submit list and NFPA document as required

Customer Responsibilities / Tyco Exclusions:

Provide Access to Technicians between 8am and 4pm M-F

Documentation Needs:

Standard

Enhanced Job Details:

System Type: FA

Product Family: Other

Construction Complexity: Exist.Bldg-Add On

Network Integration: No network integration



Installation Scope of Work

Square Footage: <15,000 sqft

SCOPE OF WORK CERTIFICATION - TO BE SIGNED BY THE TYCO INSTALLATION MANAGER OR SUPERVISOR UPON COMPLETION OF THE PROJECT FOR CLOSEOUT AND BILLING.

I hereby certify that this document reflects the "ACTUAL" equipment installed along with the true equipment placement location.

Signature

Date

Print Name & Title