

CITY OF PORTLAND
 FIRE PREVENTION BUREAU
 380 Congress Street, Portland, Maine 04101
 fireprevention@portlandmaine.gov
 (207) 874-8400

NOTICE OF VIOLATION AND ORDER TO CORRECT

Francis Jackson
 139 Hartley St
 Portland ME 04103

March 16, 2018

Location 543 RIVERSIDE ST	CBL 312 B010001	Inspection Date 2/15/2018
Inspector John Brennan	Inspection Type FP Routine Inspection	Status Failed

The City of Portland Fire Department inspected this property, and found the fire and life safety code violations listed below, which you are hereby ordered to correct. You must propose a date of completion to remedy each violation, a final date of completion, and a date of re-inspection.

You must send this form to the Fire Prevention Bureau no later than 4/15/2018.

Your failure to submit a plan of action by the date provided, or to correct any violation within the applicable time frame, may result in legal action against you, the imposition of civil penalties, and the pursuit of other legal remedies.

Violation	Proposed Date of Completion
NFPA 101- 31.3.1.1.1 VERTICAL OPENINGS NOT FIRE RATED; Vertical openings shall be enclosed or protected in accordance with Section 8.6. Patch the holes in the ceiling near Apt 2 entry door in front stairwell and the hole in between the rear entry for Apt 3 and the basement door.	3/15/2018
NFPA 1 EXCESSIVE/DISORDERLY STORAGE; Reference NFPA 1 for excessive fuel-load. Remove all storage from the front stairwell.	3/15/2018
NFPA 101- 31.3.2.1.1 BOILER PROTECTION REQUIRED; The areas described in Table 31.3.2.1.1 shall be protected as indicated: Boiler and fuel-fired heater rooms serving more than a single dwelling unit (minimum separation/protection is 1 hour or sprinklers) A domestic head is required over the gas dryer in the rear entry area or create a 60 minute barrier with a fire door that meets the same standards as the fire door violations listed for the apt doors.	4/1/2018
NFPA 101- 8.3.4.2 60 MINUTE FIRE DOOR REQUIRED; Refer to NFPA 101- Table 8.3.4.2 that states fire door assemblies for vertical shafts (including stairways, exits, and refuse chutes) are rated and required for 1 hour. A self closing 60 minute fire door is required in the following locations: Apt 1, Apt 2, both front and rear doors for Apt 3, Stairwell door for Apt 4, and the basement door.	9/1/2018
FINAL DATE OF COMPLETED VIOLATION(S)	___/___/___
FIRE PREVENTION BUREAU RE-INSPECTION OF COMPLETED VIOLATION(S)	___/___/___

The Bureau reserves the right to reject or modify any proposed plan of action, and may require evidence of sufficient financial and technical capacity to complete the proposed plan. Please contact the Bureau with any questions.

VIOLATOR CERTIFICATION

I agree to remedy the violations listed within the timeframes provided. If I require additional time to comply, I understand that I must contact the Fire Prevention Bureau prior to the deadline to request an extension, which is entirely within the Bureau's discretion to grant or deny.

I further understand that it is my responsibility to schedule a reinspection of my property once the violations have been remedied to do so. My failure to schedule a reinspection shall be deemed an admission that the violations have not been remedied.

If I fail to comply with this agreement, I understand that I am liable for penalties pursuant to the City of Portland Code of Ordinances §§ 1-15 and 10-25, and 30-A M.R.S. § 4452 and may be subject to further legal action.

Date Responsible Party

Date Responsible Party

SEEN AND AGREED

Date Fire Prevention Bureau