

**STRUCTURAL GENERAL NOTES**

**Riverside Self Storage Containers**  
Portland, ME

SI Job #: 16-0264

**DESIGN LOADS:** International Building Code; IBC 2009 Edition, except as noted  
Occupancy Category, Table 1604.5

	II	Standard
Roofs:		
Ground Snow, P <sub>g</sub>		60 psf (used for drifting calculations)
Sloped Roof Snow, P <sub>s</sub>		70 psf
Snow Exposure Factor, C <sub>e</sub>	Table 1608.3.1	1.0
Snow importance Factor, I <sub>s</sub>	Table 1604.5	1.0
Snow Thermal Factor, C <sub>t</sub>	Table 1608.3.2	1.0
Floors:		
Storage		125 psf

**FOUNDATION DESIGN:**

Foundations are designed without an engineer's soil investigation. Foundation design criteria was assumed for purpose of foundation design and shall be confirmed by a soils engineer, at owner's expense, prior to construction. (This procedure may require revisions to foundation design, at additional expense to the owner, if soils engineer determines that such design criteria are inappropriate for this building site.)

**REINFORCED CONCRETE:**

We encourage the use of blast furnace slag  
Design is based on "Building Code Requirements for Reinforced Concrete"(ACI 318). Concrete work shall conform to "Standard Specifications for Structural Concrete" (ACI 3019).  
Structural concrete shall have the following properties:

Intended Use	f'c, psi 28day	Max W/C Ratio	Maximum Aggregate	Slump inches	Entrained Air Percent ±1.5%	Cement Type	Admixtures, Comments
footings	4,500	.45	¾" Stone	4	---	I/II	Fibermesh

Detailing, fabrication, and placement of reinforcing steel shall be in accordance with the Manual of Standard Practice for Detailing Reinforced Concrete Structures (ACI 315).  
Welded wire fabric shall conform to ASTM A185.  
Reinforcing bars shall conform to ASTM A615.

Grade 60,  
except ties or bars shown to be field-bent, which shall be Grade 40.

Epoxy coated reinforcing bars shall conform to ASTM 775.

Zinc coated (galvanized) reinforcing bars shall conform to ASTM 767.

Bars to be welded shall conform to ASTM 706.

At splices, lap bars 50 diameters unless noted otherwise.

At corners and intersections, make horizontal bars continuous or provide matching corner bars.

Around openings in walls and slabs, provide 2-#5, extending 2'-0" beyond edge of opening.

In continuous members, splice top bars at mid-span and splice bottom bars over supports.

Provide intermittent shear keys at all construction joints and elsewhere as shown on the drawings.

Except as noted on the drawings, concrete protection for reinforcement in cast-in-place concrete shall be as follows:

- Cast against and permanently exposed to earth 3"
- Exposed to earth or weather:
  - #6 through #18 bars 2"
  - #5 bar, W31 or D31 wire, and smaller 1-1/2"
- Not exposed to weather or in contact with ground:
  - Slabs, walls, joists: #11 bar and smaller 3/4"
  - Beams, columns:
    - Primary reinforcement 1-1/2"
    - Stirrups, ties, spirals 1-1/2"

Fibermesh admixture shall be 100% virgin polypropylene, fibrillated fibers as manufactured by Fibermesh Co. per ASTM C-1116 type 111 4.1.3 and ASTM C-1116 performance level one, 1.5 lbs per cubic yard of concrete.

Anchor bolts and rods for beam and column-bearing plates shall be placed with setting templates.

Permanent corrugated steel forms for concrete floor slabs shall be manufactured and erected according to the "Specifications and Code of Standard Practice" of the Steel Deck Institute.

All concrete work is subject to inspection by a qualified special inspector employed by the owner in accordance with IBC Section 1704.4.

**STRUCTURAL STEEL:**

Structural steel shall be detailed, fabricated, and erected in accordance with latest AISC Specifications, and Code of Standard Practice. Structural steel wide flange beams shall conform to ASTM A992.

Except as noted, framed beam connections shall be bearing-type with 3/4" diameter, snug tight, A325-N bolts, detailed in conformance with Part 4, Tables II and III, for 0.6 times the allowable uniform loads tabulated in Part 2 of the AISC Manual, 9th Edition. Install bolts in accordance with AISC "Specification for Structural Joints Using ASTM A325 or A490 Bolts".

All beams shall have full depth web stiffeners each side of webs above and below columns

Anchor rods shall conform to ASTM F1554, Grade 55, with weldability supplement S1.

Headed anchor studs (HAS) shall be attached to structural steel with equipment approved by the stud manufacturer according to the stud manufacturer's recommendations.

Welding shall be done by a certified welder in accordance with AISC and AWS specifications and recommendations using E70-electrodes. Where not specifically noted, minimum weld shall be 3/16" fillet by length of contact edge.

All post-installed anchors shall have current ICC Evaluation Report, and shall be installed in accordance with the manufacturer's requirements.

Expansion anchors shall be approved "wedge" type unless specifically noted to be "sleeve" type.  
Chemical anchors shall be approved epoxy or similar adhesive type and shall have current ICC Evaluation Report.  
Where base material is not solid, approved screen tubes shall be used.  
Grout beneath column base and beam-bearing plates shall be minimum 28-day compressive strength of 7,500 psi, approved pre-bagged, non-metallic, non-gaseous, bleed free, non-shrink, when tested in accordance with ASTM C1107  
Grade B or C at a flow cone fluid consistency of 20 to 30 seconds


**SHOP DRAWINGS:**

Construction Documents are copyrighted and shall not be copied for use as erection plans or shop details.  
Use of SI Inc.'s electronic files as base for shop drawings requires prior approval by SI Inc., signed release of liability by subcontractor,  
payment of an administration fee of \$100 per drawing sheet to SI Inc, and deletion of SI Inc's name and Logo from all sheets so used.  
The General Contractor and his subcontractors shall submit in writing any requests to modify the plans or specifications.  
All shop and erection drawings shall be checked and stamped by the General Contractor prior to submission for Engineer's review.  
Unchecked submittals will be returned without review.  
Furnish one (1) reproducible and two (2) prints of shop and erection drawings to the Structural Engineer for review prior to fabrication for, reinforcing steel, structural steel, decking, P.E.M.B. anchor bolt plan, P.E.M.B. shop drawings, and P.E.M.B. reactions  
Submit in a timely manner to permit ten (10) working days for review.  
Shop drawings submitted for review do not constitute "in writing" unless specific suggested changes are clearly marked.  
In any event, such changes by means of the shop drawing submittal process become the responsibility of the one initiating such change.



ABBREVIATIONS KEY			
AB	Anchor Rod (Bolt)	EF	Each Face
ADDL	Additional	EJ	Expansion Joint
ADJ	Adjustable	ELEV	Elevation
AF	Above Finished Floor	ELEC	Electric (Electrical)
ALT	Alternate	ENGR	Engineer
AMT	Amount	EQ	Equal
ANCH	Anchor, Anchorage	EQUIP	Equipment
APPROX	Approximate	EQUIV	Equivalent
ARCH	Architect, -ural	ES	Each Side
ATR	All Thread Rod	EST	Estimate
AVG	Average	E-W	East to West
BC	Bottom of Concrete	EXC	Excavate
BL	Brick Ledge	EXP	Expansion
BLK	Block	EXT	Exterior
BLKG	Blocking	FND	Foundation
BM	Beam	FF	Far Face, Finished Floor
BOT	Bottom	F-F	Face to Face
BRG	Bearing	FIG	Figure
BW	Bottom of Wall	FL	Flush
CB	Counterbores	FLG	Flange
CF	Cubic Foot	FLR	Floor
CG	Center of Gravity	FO	Face of
CIP	Cast in Place	FP	Full Penetration
CJ	Construction Joint	FS	Far Side
CLG	Ceiling	FTG	Footing
CLR	Clear	GA	Gage (Gauge)
CM	Construction Manager (Management)	GALV	Galvanized
CMU	Concrete Masonry Unit	GC	General Contractor
COL	Column	GEN	General
COM	Common	GL	Glue laminated (Glulam)
COMB	Combination	GND	Ground
CONC	Concrete	GR	Grade
CONN	Connection	GT	Girder Truss
CONT	Continue (Continuous)	GYP BD	Gypsum Board
COORD	Coordinate, -tion	HAS	Headed Anchor Stud
CS	Countersink	HORIZ	Horizontal
CTR	Center	HFT	Height
CY	Cubic Yard	ID	Inside Diameter
DAB	Deformed Anchor Bar	IF	Inside Face
DET	Detail	INT	Interior (Intermediate)
DEV	Develop	JB	Joist Bearing
DIAG	Diagonal	JST	Joist
DIM	Dimension	JT	Joint
DL	Dead Load	K	Kip (1,000 lbs.)
DN	Down	LD	Load
DP	Drilled Pier	LL	Live Load
DT	Double Tee	LLH	Long Leg Horizontal
DWG	Drawing	LLV	Long Leg Vertical
DWL	Dowel	LOC	Location
EA	Each	LSL	Laminated Strand Lumber (generic term)
ECC	Eccentric	LTV	Light
E-E	End to End	LVL	Laminated Veneer Lumber (generic term)
MACH	Machine	MFR	Manufacture, -er, -ed
MASY	Masonry	ML	Microlam (Truss-joist brand LVL)
MATL	Material	MO	Masonry Opening
MAX	Maximum	MTL	Metal
MB	Machine bolt	NF	Near Face
MECH	Mechanical	NIC	Not In Contract
MEZZ	Mezzanine	NS	Near Side
MIN	Minimum	N-S	North to South
ML	Microlam	NTS	Not to Scale
MO	Masonry Opening	OCJ	OSHA Column Joist
MTL	Metal	OD	Outside Diameter
NF	Near Face	OF	Outside Face
NIC	Not In Contract	OH	Opposite Hand
NS	Near Side	OPNG	Opening
N-S	North to South	OPP	Opposite
NTS	Not to Scale	OSB	Oriented Strand Board
OCJ	OSHA Column Joist	PAF	Powder Actuated Fastener
OD	Outside Diameter	PC	Precast
OF	Outside Face	PCF	Pounds Per Cubic Foot
OH	Opposite Hand	PEN	Penetration
OPNG	Opening	PERP	Perpendicular
OPP	Opposite	PL	Property Line
OSB	Oriented Strand Board	PLF	Pounds per Linear Foot
PAF	Powder Actuated Fastener	PNL	Panel
PC	Precast	PP	Panel Point
PCF	Pounds Per Cubic Foot	PS	Prestressed
PEN	Penetration	PSF	Pounds per Square Foot
PERP	Perpendicular	PSI	Pounds per Square Inch
PL	Property Line	PSL	Parallel Strand Lumber (generic term)
PLF	Pounds per Linear Foot	PT (1)	Post Tensioned
PNL	Panel	PT (2)	Pressure Treated
PP	Panel Point	PTN	Partition
PS	Prestressed	PWD	Plywood
PSF	Pounds per Square Foot	QTY	Quantity
PSI	Pounds per Square Inch	R	Radius
PSL	Parallel Strand Lumber (generic term)	RD	Roof Drain
PT (1)	Post Tensioned	RE	Reference (refer to)
PT (2)	Pressure Treated	RECT	Rectangle
PTN	Partition	REINF	Reinforce, -ed, -ing
PWD	Plywood	REQ	Required
QTY	Quantity	REQMT	Requirement
R	Radius	RET	Retaining
RD	Roof Drain	RM	Room
RE	Reference (refer to)	RMO	Rough Masonry Opening
RECT	Rectangle		
REINF	Reinforce, -ed, -ing		
REQ	Required		
REQMT	Requirement		
RET	Retaining		
RM	Room		
RMO	Rough Masonry Opening		
RO	Rough Opening		
SC	Slip Critical		
SCH	Schedule		
SDST	Self Drilling Self Tapping		
SECT	Section		
SF	Square Feet		
SFT	Sheet		
SFTG	Sheathing		
SIM	Similar		
SLH	Short Leg Horizontal		
SLV	Short Leg Vertical		
SOG	Slab on Grade		
SP	Spaces		
SPEC	Specifications		
SQ	Square		
ST	Snug Tight		
STD	Standard		
STIFF	Stiffener		
STL	Steel		
STRUCT	Structure, -al		
SUPP	Support		
SY	Square Yard		
SYM	Symmetrical		
T&B	Top and Bottom		
T&G	Tongue and Groove		
TB	Top of Beam		
TJC	Top of Concrete		
TJD	Top of Deck		
THD	Thread		
THK	Thick, -ness		
TJ	Top of Joist		
TL	Total Load		
TPG	Topping		
TRANS	Transverse		
TW	Top of Wall		
TYP	Typical		
ULT	Unless Noted Otherwise		
UNO	Unless Otherwise		
VERT	Vertical		
VIF	Verify in Field		
WA	Wedge Anchor		
WP	Work Point		
WT	Weight		
WWF	Welded Wire Fabric		
XS	Extra Strong		
XSECT	Cross-section		
XXS	Double Extra Strong		
	(E)	Existing	
	(N)	New	
	(R)	Remove	

**Structural Drawing Index**

S1.0	General Notes, Etc.
S1.1	Foundation Plan
S1.2	Details / Sections



**TYPICAL CONCRETE WALL INTERSECTIONS**  
NO SCALE



RIVERSIDE SELF STORAGE CONTAINERS  
Portland, Maine

Document Title:  
Shipping Container  
Storage Foundation  
Drawings

Sheet Title:  
**GENERAL  
NOTES**

Scale: AS NOTED

Date: 6/6/2017

Revisions

Sheet

**S1.0**