


GENERAL NOTES

- 1. DRAWING NOTES:**
CONTRACTOR TO FURNISH AND INSTALL ALL NOTED LABOR AND MATERIALS UNLESS OTHERWISE NOTED.
- 2. CODE COMPLIANCE:**
ALL WORK SHALL CONFORM TO THE LATEST EDITION OF STATE, LOCAL AND OTHER CODES WHICH APPLY TO THIS PROJECT OR HAVE JURISDICTION.
- 3. COORDINATION:**
IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO COORDINATE ALL DISCIPLINES AND TRADES SO THAT ALL BUILDING SYSTEMS AND COMPONENTS CAN BE ASSEMBLED WITHOUT CONFLICTS. IN THE EVENT THAT THE CONSTRUCTION DOCUMENTS DEFINE CONDITIONS WHICH PROHIBIT, OR MAY PROHIBIT, SUCH ASSEMBLY, THE CONTRACTOR SHALL BRING TO THE ARCHITECTS ATTENTION, IN WRITING AND IN A TIMELY FASHION, SUCH CONDITION. THE CONTRACTOR SHALL NOT PROCEED WITH RELATED WORK WITHOUT A WRITTEN RESOLUTION CLARIFICATION FROM THE ARCHITECT. THE CONTRACTOR AND HIS/HER SUBCONTRACTORS SHALL BE RESPONSIBLE FOR PROVIDING MATERIALS AND SYSTEMS SHOWN IN THE CONSTRUCTION DOCUMENTS REGARDLESS OF WHERE THE INFORMATION IS LOCATED. WHERE COMPONENTS OF A SYSTEM ARE INDICATED THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ALL LABOR AND MATERIALS NECESSARY TO COMPLETE THE SYSTEM.
- 4. DISCREPANCIES & CLARIFICATIONS:**
EXISTING DIMENSIONS SHOWN ON THE DRAWINGS ARE BELIEVED TO BE ACCURATE, BUT CANNOT BE GUARANTEED. MEASURE AND VERIFY DIMENSIONS IN FIELD PRIOR TO FABRICATION AND CONSTRUCTION. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO BRING TO THE ARCHITECTS ATTENTION, IN WRITING, ANY DISCREPANCIES OR AMBIGUITIES IN THE DRAWINGS AND/OR SPECIFICATIONS. THE CONTRACTOR SHALL NOT PROCEED WITH RELATED WORK WITHOUT A WRITTEN RESOLUTION OR CLARIFICATION FROM THE ARCHITECT.
- 5. LAYOUT:**
UNLESS INDICATED OTHERWISE, CENTER WALL FRAMING AND PARTITION FRAMING ON COLUMN LINES. FLOOR PLAN DIMENSIONS ARE TO CENTER OF FRAMING, FACE OF CONCRETE, FACE OF WALL, OR FROM COLUMN CENTERLINES, UNLESS INDICATED OTHERWISE. DOORS AND WINDOWS ARE DIMENSIONED TO CENTERLINES UNLESS INDICATED OTHERWISE.
- 6. CENTERING:**
UNLESS INDICATED OTHERWISE, CENTER BUILDING ELEMENTS WITHIN OR BETWEEN OTHER BUILDING ELEMENTS WHEN CONDITIONS OR THE DRAWINGS INDICATE OR IMPLY THAT SUCH IS THE INTENT, WHETHER OR NOT DIMENSIONS ARE INCLUDED.
- 7. SYMMETRY:**
WHERE CONDITIONS OR THE DRAWINGS INDICATE OR IMPLY THAT SYMMETRY IS INTENDED, INFORMATION PROVIDED AT ONE SIDE APPLIES EQUALLY TO BOTH SIDES, UNLESS CONDITIONS CLEARLY PRECLUDE SUCH APPLICATION.
- 8. ACCESSIBILITY:**
ALL HANDICAPPED ACCESSIBLE BATHROOMS, GRAB BARS, AND DOOR OPENINGS SHALL MEET THE REQUIREMENTS OF TITLE 94-348, CHAPTER 5 OF THE MAINE HUMAN RIGHTS COMMISSION TITLE LATEST EDITION & THE DEPARTMENT OF JUSTICE ADA STANDARDS FOR ACCESSIBLE DESIGN.
- 9. DRAWING SCALES:**
WORK FROM THE GIVEN DIMENSIONS ONLY. SCALE IS INDICATED ON THE DRAWINGS FOR CONVENIENCE ONLY. IT IS NOT INTENDED THAT INFORMATION BE DETERMINED BY SCALING THE DRAWINGS SINCE SOME ITEMS MAY NOT BE TO SCALE.
- 10. WATER-RESISTANT GWB:**
INSTALL WATER-RESISTANT GYPSUM WALL BOARD IN ALL REST ROOMS & TOILET ROOMS OR AT ANY WALL WITH PLUMBING FIXTURES.
- 10A. HIGH IMPACT GWB:**
INSTALL HIGH IMPACT GYPSUM WALL BOARD IN ALL STAIRWELLS
- 11. INTERIOR ELEVATIONS:**
INTERIOR ELEVATIONS MAY BE REVERSED FROM AND/OR SIMILAR TO ACTUAL CONDITIONS. SEE FLOOR PLANS FOR WINDOW AND DOOR QUANTITIES AND LOCATIONS, FOR CASEWORK LAYOUTS, AND FOR MONITOR LOCATIONS.
- 12. BUILDING INSULATION:**
PROVIDE AS INDICATED IN WALL SECTIONS AND IN ACCORDANCE WITH PARTITION TYPES, WHETHER OR NOT SHOWN IN DETAILS AND OTHER DRAWINGS. FOR CLARITY, INSULATION MAY NOT BE SHOWN IN SOME CASES, EVEN IF IT IS TO BE PROVIDED.
- 13. BLOCKING:**
INSTALL BLOCKING BEHIND ALL SURFACE-APPLIED FIXTURES TRIM, CASEWORK, SHELVES, BRACKETS, TOOL ACCESSORIES, CHAIR RAILS, PICTURE RAILS, GRAB BARS, BASE MOLDINGS, AND AS OTHERWISE REQUIRED, WHEN SUCH ITEMS ARE APPLIED ON STUD WALLS.
- 14. PENETRATIONS AT STRUCTURAL MEMBERS:**
BEFORE PENETRATING JOISTS, BEAMS OR OTHER STRUCTURAL MEMBERS, CONSULT WITH THE ARCHITECT.
- 15. DAMAGED WORK:**
BUILDING OR SITE COMPONENTS WHICH ARE AFFECTED BY NEW WORK, DEMOLITION, OR WHICH MAY BE DAMAGED BY THE GENERAL CONTRACTOR OR ANY SUB-CONTRACTOR SHALL BE REPLACED OR RESTORED TO ORIGINAL CONDITION AND COLOR TO MEET THE APPROVAL OF THE ARCHITECT.
- 16. UTILITIES:**
VERIFY THE SIZE AND LOCATION OF ALL UNDERGROUND UTILITIES AND REPORT ANY DISCREPANCIES TO THE ARCHITECT IN WRITING. DO NOT PROCEED WITH WORK UNTIL THE DISCREPANCY HAS BEEN RESOLVED TO THE SATISFACTION OF THE ARCHITECT.
- 17. RATED CONSTRUCTION:**
PROVIDE RATED CONSTRUCTION AS REQUIRED BY CODE, AS SPECIFIED, AND AS INDICATED ON DRAWINGS. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO PROVIDE AND INSTALL ALL COMPONENTS REQUIRED TO CREATE SUCH RATED CONSTRUCTION, REGARDLESS OF WHETHER OR NOT SUCH COMPONENTS ARE INDICATED. PROVIDE CONTINUITY OF SUCH RATED CONSTRUCTION AROUND AND BETWEEN SPACES, INCLUDING AT CHASES AND AT FLOORS, TO MAINTAIN COMPLETE SEPARATIONS, EVEN IF NOT SPECIFICALLY INDICATED.
- 18. SHOP DRAWINGS:**
SUBMIT SHOP DRAWINGS TO THE ARCHITECT FOR REVIEW PRIOR TO FABRICATIONS. SUBMITTALS REQUIRED INCLUDE, BUT ARE NOT LIMITED TO, SHOP DRAWINGS FOR ALL PREFABRICATED CONCRETE, STEEL, MILLWORK & SIGNAGE, SAMPLES OF ALL PROPOSED PAINTS, METALS, WALL COVERINGS, LAMINATES, SOLID SURFACE MATERIALS, CERAMIC TILE, AND HARDWARE. SUBMIT MANUFACTURERS' DATA FOR ALL LIGHTING SYSTEMS, AND HARDWARE.
- 19. PERMITS:**
THE GENERAL CONTRACTOR SHALL OBTAIN AND PAY FOR ANY BUILDING PERMITS REQUIRED AND CARRY ANY INSURANCE COVERAGES REQUIRED.
- 20. INTERIOR FINISHES:**
ALL INTERIOR FINISHES AND FURNISHINGS ARE TO BE CLASS 'A' FIRE-RATED AND ARE TO COMPLY WITH IBC CHAPTER-8 (INTERIOR FLAME SPREAD).
- 21. ELECTRICAL DESIGN:**
REFER TO ELECTRICAL DRAWINGS AND SPECIFICATIONS
- 22. WASTE REMOVAL:**
THE GENERAL CONTRACTOR SHALL DISPOSE OF ALL WASTE AND DEBRIS OFF THE PREMISES.
- 23. LANDLORD COORDINATION:**
THE GENERAL CONTRACTOR MUST COORDINATE WITH THE BUILDING OWNER ALL ACTIVITIES INCLUDING BUT NOT LIMITED TO WORK WHICH WILL GENERATE EXCESSIVE NOISE AND MODIFICATION TO UTILITIES. WORK MUST NOT INTERFERE WITH EXISTING SMOKE DETECTORS, ALARMS OR BUILDING SYSTEM MANAGEMENT.
- 24. TEMPORARY FACILITIES:**
PROVIDE ALL TEMPORARY FACILITIES AND SERVICES, CONSTRUCTION AND SUPPORT FACILITIES, AND SECURITY AND PROTECTION AS NEEDED TO PROTECT NEW AND EXISTING CONSTRUCTION FOR THE DURATION OF A COMPLETE INSTALLATION.
- 25. FINAL CLEANING:**
EMPLOY EXPERIENCED WORKERS FOR FINAL CLEANING. CLEAN EACH SURFACE TO THE CONDITION EXPECTED IN A COMMERCIAL BUILDING CLEANING PROGRAM.
- 26. MANUFACTURERS INSTRUCTIONS:**
ALL MATERIALS & EQUIPMENT SHALL BE INSTALLED ACCORDING TO MANUFACTURER'S SPECIFICATIONS.
- 27. GUARANTEE:**
GUARANTEE: ALL MATERIALS AND WORKMANSHIP SHALL BE GUARANTEED FOR A PERIOD OF ONE YEAR FROM THE DATE OF FINAL ACCEPTANCE UNLESS OTHERWISE SPECIFIED FOR A LONGER PERIOD OF TIME ON A CERTAIN ITEM.
- 28. ASBESTOS:**
ALL MATERIAL USED FOR THE CONSTRUCTION OF THIS PROJECT, WHETHER BUILDING MATERIALS OR APPURTENANCES, SHALL BE NON-ASBESTOS CONTAINING MATERIAL.
- 29. HAZARDOUS FUMES:**
THE GENERAL CONTRACTOR SHALL CONFIRM THAT ALL MATERIAL AND FINISHES SPECIFIED AND THEIR FABRICATION OR INSTALLATION WILL NOT RELEASE FUMES OR AROMAS DURING CONSTRUCTION WHICH MAY BE A HAZARD OR NUISANCE TO PERSONNEL.
- 30. PEST CONTROL:**
SEAL AND CAULK AROUND ALL PENETRATIONS, CRACKS AND CREVICES AND ANY OPENINGS CAPABLE OF HARBORING INSECTS/RODENTS.
- 31. EXPOSED UTILITIES:**
ALL EXPOSED UTILITY WIRES AND PIPES (ELECTRICAL, PLUMBING, ETC.) SHALL BE INSTALLED IN A WAY THAT DOES NOT OBSTRUCT OR PREVENT THE CLEANING OF FLOORS, WALLS, AND CEILING AREAS. THEY SHALL BE INSTALLED A MINIMUM OF 6" OFF FLOORS AND 1" OFF WALLS, CEILING AND ADJACENT PIPES.
- 32. OWNER SUPPLIED EQUIPMENT:**
EQUIPMENT SUPPLIED BY THE OWNER AND INSTALLED BY THE GENERAL CONTRACTOR. EQUIPMENT INFORMATION AND SPECIFICATIONS ARE TO BE THE MOST CURRENT AVAILABLE AT THE TIME OF DOCUMENTATION PREPARATION. THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING WITH THE OWNER THE EXACT DIMENSIONS AND EQUIPMENT CONNECTION REQUIREMENTS (INCLUDING ELECTRICAL CIRCUIT REQUIREMENTS) OF EQUIPMENT TO BE SUPPLIED. THE GENERAL CONTRACTOR SHALL MAKE ALL FINAL CONNECTIONS AS NOTED ON THE DRAWINGS, INSTALL THE SET UP IN WORKING ORDER, CHECK WARRANTIES, TEST AND NOT VOID WARRANTIES. THE GENERAL CONTRACTOR SHALL COORDINATE WITH THE OWNER DELIVERY, STORAGE AND INSTALLATION OF ALL OWNER SUPPLIED EQUIPMENT. THE GENERAL CONTRACTOR SHALL STORE EQUIPMENT IF REQUESTED BY THE OWNER UNTIL INSTALLATION. SEE DRAWINGS FOR OTHER OWNER SUPPLIED/GENERAL CONTRACTOR INSTALLED ITEMS.
- 33. FIRE PROTECTION NOTE:**
EXISTING SPRINKLERHEADS, ALARM SYSTEM AND DETECTORS ARE TO BE MODIFIED TO CONFORM WITH THE PROPOSED PLAN. COORDINATE WITH THE ARCHITECT, ANY MODIFICATION OR LOCATIONS WHERE EXISTING SYSTEMS ARE AFFECTED BY THE NEW DESIGN.
- 34. SOILS AT FOOTINGS:**
REPORT THE LOCATION OF ALL UNSUITABLE SOILS AND MATERIALS BELOW ANTICIPATED LEVEL OF FOOTING TO THE ARCHITECT PRIOR TO THE SETTING OF FORMS.
- 35. ACCESS PANELS:**
CONTRACTOR IS RESPONSIBLE FOR COORDINATING QUANTITY AND LOCATION OF ALL REQUIRED ACCESS PANELS FOR ALL MEP CONTROLS, CLEANOUTS, DAMPERS, PULL BOXES, ETC.
- 36. EXISTING HAZARDOUS MATERIALS:**
ALL HAZARDOUS MATERIALS INCLUDING BUT NOT LIMITED TO ASBESTOS AND LEAD PAINT ARE TO BE HANDLED, ENCAPSULATED, ABATED AND DISPOSED OF IN ACCORDANCE WITH ANY AND ALL FEDERAL, STATE AND LOCAL REQUIREMENTS AND REGULATIONS.
- 37. INDUSTRY STANDARDS:**
ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH INDUSTRY STANDARDS. STANDARDS INCLUDE BUT ARE NOT LIMITED TO THE FOLLOWING:
AAMA AMERICAN ARCHITECTURAL MANUFACTURERS ASSOCIATION
ACI AMERICAN CONCRETE INSTITUTE
ANSI AMERICAN NATIONAL STANDARDS INSTITUTE
ASTM AMERICAN SOCIETY FOR TESTS AND MATERIALS
AWI ARCHITECTURAL WOODWORK INSTITUTE
"CUSTOM GRADE"
AWS AMERICAN WELDING SOCIETY
IGMA INSULATING GLASS MANUFACTURERS ALLIANCE
NAAMM NATIONAL ASSOCIATION OF ARCHITECTURAL METAL MANUFACTURERS
NRCA NATIONAL ROOFING CONTRACTORS ASSOCIATION
NTCA NATIONAL TILE CONTRACTORS ASSOCIATION
SMACNA SHEET METAL AND AIR CONDITIONING NATIONAL ASSOCIATION
WDMA WINDOW AND DOOR MANUFACTURERS ASSOCIATION


ABBREVIATIONS

A AC ACT AD ADAAG	AIR CONDITIONING ACOUSTICAL CEILING TILE AREA DRAIN AMERICANS WITH DISABILITIES ACT ACCESSIBILITY'S GUIDELINES	L LAB LAM LB LH LCC	LABORATORY LAMINATED LEAD LEFT-HAND LEAD COATED COPPER
ADD AFF AHU AL ARCH AWP	ADDENDUM ABOVE FINISHED FLOOR AIR-HANDLING UNIT ALUMINUM ARCHITECT/ARCHITECTURAL ACOUSTIC WALL PANEL	M MACH MAS MATL MAX MDO MECH MEMB MEZZ MET MFR MIN MISC MO MTD MTL MB	MACHINE MASONRY MATERIAL MAXIMUM MEDIUM-DENSITY OVERLAY MECHANICAL MEMBRANE METAL MEZZANINE MANUFACTURER MINIMUM MISCELLANEOUS MASONRY OPENING MOUNTED METAL MARKER BOARD
B B TO BLS B.B.G.C. BL BLDG BLKS BSMT BTWN BO	BACK-TO-BACK ANGLES BASE BUILDING GENERAL CONTRACTOR BUILDING LINE BUILDING BLOCKING BLOCKING BLOCKING BETWEEN BY OTHERS	N N # NIC NOM NTS	NORTH NUMBER NOT IN CONTACT NOMINAL DIMENSION NOT TO SCALE
C C CER CG FH CJ CLG CMU CO COL CONC COND CONN CONSTR CONST CORR CUH	COURSE (MASONRY) CERAMIC CORNER GUARD COAT HOOK CONTROL JOINT CENTER LINE CEILING CONCRETE MASONRY UNIT CLEAN OUT COLUMN CONCRETE CONSTRUCTION CONNECT/CONNECTION CONCRETE CONTINUOUS CORRIDOR CERAMIC TILE CABINET UNIT HEATER	O ON OC OD OFF OPNG OP OPP H OSB OS	ON/OVER ON CENTER OUTSIDE DIAMETER/OUTSIDE DIMENSION OFFICE OPENING OPPOSITE OPPOSITE HAND ORIENTED STRAND BOARD
D DBL DF DIA DIFF DIM DN DR DSP DWG	DOUBLE DRINKING FOUNTAIN DIAMETER DIFFUSER DIMENSION DOWN DOOR DRY STAND PIPE DRAWING	P PBO/BC PC PCAST PL FLAM PR PRE FAB PRIV PRIM PSF PSI PTD PTN PVC PLYWOOD PT PERF	PURCHASED BY OWNER INSTALLED BY CONTRACTOR PRECAST PLATE PLASTIC LAMINATE PAIR PREFABRICATE PRIVACY PRIMED POUNDS PER SQUARE FOOT POUNDS PER SQUARE INCH PAINTED PARTITION POLYVINYL CHLORIDE PLYWOOD PRESSURE TREATED PERFORATED
E E EA ELC COND ENTR EQ EQUIP EXP XPB EXPJ EXT EPDM EWC	EAST EACH ELEVATION ELECTRICAL ELEVATOR ENTRANCE EQUIP EXPANSION EXPANSION BOLT EXPANSION JOINT EXTERIOR ETHYLENE PROPYLENE DIENE MONOMER ELECTRIC WATER COOLER	Q QT R RAD RB RCP RD REBAR REFR REIN REQ RES REV RM RO ROW	QUARRY TILE QUARTER RISER/RADIUS RADIUS RUBBER BASE REFLECTED CEILING PLAN ROOF DRAIN REINFORCING BAR REFRIGERATOR REINFORCED REQUIRED RESILIENT REVERSE ROOM ROUGH OPENING RIGHT OF WAY
F FB FC FD FE FEC FTWD FIN FL FOB FOC FOF FOS FOW FSS FT FTG FRG FTR FH	FAHRENHEIT FLAT BAR FIRE EXTINGUISHER AND CABINET FLOOR DRAIN FIRE EXTINGUISHER FIRE EXTINGUISHER CABINET FIRE TREATED WOOD FINISH FLOOR FACE OF BRICK FACE OF CONCRETE FACE OF FINISH FACE OF STUDS FACE OF WALL FIRE SUPPRESSION SYSTEM FOOT FOOTING FIBER REINFORCED GYPSUM FIN TUBE RADIATION FUME HOOD	S S SCHED SQ SIM SPEC SQU SST STD STL STOR STRUC SUSP	SCHEDULE SQUARE FEET SIMILAR SPECIFICATION SQUARE STAINLESS STEEL SOUND TRANSMISSION CLASS STANDARD STEEL STORAGE STRUCTURE/STRUCTURAL SUSPENSION
G GA GALV GB GC GFI GL GLAM GND GWB	GAUGE GALVANIZED GRAB BAR GENERAL CONTRACTOR GROUND-FAULT INTERRUPTER GLASS/GLAZING/GLAZED GLUE-LAMINATED WOOD GROUND GYPSUM WALL BOARD	T T&G TEL THK TOD TOS TYP TV TACK BOARD TOP OF CONCRETE	TONGUE/GROOVE TELEPHONE THICK TOP OF DECK TOP OF STEEL TYPICAL TELEVISION TACK BOARD TOP OF CONCRETE
H HB HC HM HORIZ HR HW HVAC	HOSE BIB HANDICAP HOLLOW METAL HORIZONTAL HORSE POWER/HIGH POINT/HEAT PUMP HOUR HOT WATER HEATING VENTILATION AIR CONDITIONING	U UL UV V VCT VERT VIF VOL	UNDERWRITERS LABORATORIES, INC. UNIT VENTILATOR VINYL COMPOSITION TILE VERTICAL VERIFY IN FIELD VOLUME
I ID IN INFO INSUL	INSIDE DIMENSION/INSIDE DIAMETER INCHES INFORMATION INSULATION	W W W/O W/ W/ WD WC WP WT	WEST WITHOUT JOINT WOOD WIDE FLANGE WORK POINT WEIGHT
J JST JT	JOIST JOINT	K KIP	KILN-DRIED 1000 POUNDS

DRAWING LEGEND



FIRESTOPPING DETAILS



SPECIFICATIONS

WRAP STRIP: 1/4" THICK x 1 1/2" MINIMUM WIDTH INTUMESCENT MATERIAL WITH PLASTIC FILM FACING BOTH SIDES. TEMPORARILY SECURE WITH MAKING TAPE. SPECIFIED TECHNOLOGIES INC. (STI) *SpecSeal RED Wrap Strip* OR *SpecSeal BLU Wrap Strip* OR EQUAL.

STEEL COLLAR: WRAP STRIP MANUFACTURER'S STEEL COLLAR, FABRICATED FROM .016 INCH THICK GALVANIZED SHEET STEEL. WIDTH TO MATCH WRAP STRIP (1 1/2" MINIMUM), WITH 1 INCH x 2 INCH ANCHOR TABS AND RETAINER TABS. ANCHOR TABS TO BE SYMMETRICALLY OPPOSED AROUND COLLAR; PROVIDE 4 TABS FOR 2 1/2" AND 3" PIPE; PROVIDE 4 TABS FOR 4" PIPE.

INTUMESCENT SEALANT: ONE-PART, INTUMESCENT, LATEX ELASTOMER TESTED TO ASTM E 814. MINIMUM EXPANSION OF 3x AT 1000°F. 3M *FIRE BARRIER SEALANT CP 25WB* OR EQUAL.

FIRESTOP SEALANT: SINGLE COMPONENT NONCOMBUSTIBLE FIRE RATED SEALANT TESTED TO ASTM E 814. TESTED TO 3000°F. *BOSS 136 FIRESTOP/DRAFT SEALANT* MANUFACTURED BY ACCUMETRIC, LLC. OR EQUAL.


SEALANT SCHEDULE:

INTUMESCENT SEALANT: PROVIDE AT ALL PENETRATIONS THROUGH RATED CONSTRUCTION FOR PENETRATING ITEMS INCLUDING BUT NOT LIMITED TO: PVC PIPE; ROOF LEADER PIPES, GAS PIPES & LINES; SPRINKLER PIPES; ELECTRICAL & COMMUNICATIONS CABLES & WIRES; AND ALARM SYSTEM WIRES. DO NOT USE INTUMESCENT SEALANT AT DOMESTIC HOT WATER OR HYDRONIC HEATING SYSTEM PIPES.

FIRESTOP SEALANT: PROVIDE AT ALL PENETRATIONS THROUGH RATED CONSTRUCTION FOR PENETRATING ITEMS INCLUDING DOMESTIC HOT AND COLD WATER PIPES AND HYDRONIC HEATING SYSTEM PIPES.

NOTE:

FOR LOCATIONS OF RATED CONSTRUCTION, SEE ARCHITECTURAL FLOOR PLANS AND SECTIONS



© 2017 RYAN SENATORE ARCHITECTURE

OFFICE BUILDING
547 RIVERSIDE STREET
PORTLAND, MAINE



RYAN SENATORE ARCHITECTURE
565 CONGRESS STREET
PORTLAND, MAINE 04101
207-650-6414
senatorearchitecture.com

CONSULTANTS:

REVISIONS:

DATE: DECEMBER 29, 2017
PROJECT No. 1788
DRAWN BY: RJS, JPF
CHECKED BY: RJS
SCALE: AS NOTED

SHEET TITLE:
GENERAL NOTES, ABBREVIATIONS, AND LEGENDS

G0-1