



- PLUMBING DEMOLITION NOTES:**
1. REMOVE ALL EXISTING PLUMBING SYSTEMS WITHIN THESE AREAS INCLUDING FIXTURES, FLOOR DRAINS AND ALL ASSOCIATED SANITARY WASTE, VENT, WATER PIPING BACK TO MAIN. REFER TO PLUMBING FLOOR PLANS.
 2. PLUMBING CONTRACTOR SHALL REMOVE ALL EXISTING WATER PIPING ENTIRELY FROM BUILDING, WITH THE EXCEPTION OF MAIN ENTERING WATER SERVICE AND ASSEMBLY. REFER TO PLUMBING FLOOR PLANS.
 3. PLUMBING CONTRACTOR SHALL REMOVE ALL EXISTING COMPRESSED AIR PIPING, DROPS AND ASSOCIATED EQUIPMENT ENTIRELY FROM BUILDING.
 4. PLUMBING CONTRACTOR SHALL DEEP ALL EXISTING PLUMBING SYSTEMS TO REMAIN CAPPED AND CLEAN FROM CONSTRUCTION DEBRIS.
 5. EXISTING UNDERFLOOR SANITARY LINE AND EXTERIOR PUMP CHAMBER TO BE REMOVED, AND ABANDONED. CAP EXISTING SANITARY MAIN, REMOVE ALL CLEANOUTS VENTS, COORDINATE WITH GENERAL CONTRACTOR.
 6. EXISTING 2 LB. ELEVATED GAS LINE AND METER ETC. SHALL BE REMOVED AND ALL NEW .5 LB GAS SYSTEM TO BE INSTALLED. EXISTING JOHNSON AIR HEATING UNIT TO BE UTILIZED FOR TEMPORARY HEATING. INSPECT, SERVICE AND COORDINATE WITH GAS CO. AND HVAC CONTRACTOR. TOTALLY REMOVE ALL GAS PIPING, VENTING ETC. AFTER NEW HEATING SYSTEMS HAVE BEEN INSTALLED.
 7. EXISTING SPRINKLER SERVICE AND EQUIPMENT TO REMAIN.

- HVAC DEMOLITION NOTES:**
1. TOTALLY REMOVE ALL EXISTING HVAC UNITS, EXHAUST FANS, MAKE-UP AIR UNITS, UNIT HEATERS, DUCTWORK, DIFFUSERS GRILLES AND ALL ASSOCIATED CONTROLS, THERMOSTATS, CONDUIT AND CONTROL WIRING FROM THE ROOF AND CONFINES OF THE EXISTING BUILDING.
 2. EXISTING JOHNSON AIR ROTATION UNIT SHALL BE UTILIZED FOR TEMPORARY HEATING. REMOVE AFTER NEW HEATING EQUIPMENT HAS BEEN INSTALLED AND IN OPERATION.
 3. REFER TO DEMOLITION SPECIFICATIONS.
- ALL SHALL BE PROPERLY DISPOSED OF FOR HAZARDOUS MATERIALS. (SEE DEMOLITION & HVAC SPECS)

S.S.E.T SOUTH SHORE ENGINEERING TEAM INC.
 ELECTRICAL & MECHANICAL ENGINEERS - Phone: 781-331-4660 - Fax: 781-829-4405 - E-mail: SSETINC@AOL.COM
 720 WASHINGTON STREET - HANOVER, MA - COLLEGE PARK - YALE BUILDING

DION & SOKOL INC ○ **ARCHITECTS** **SUBBURY MA**

project no. 01-20	drawn GMP	checked CJW/JPS	date 01-21-2003	revisions:	
PLUMBING & HVAC DEMOLITION PLAN PHASE I					
WAREHOUSE FACILITY HARVEY INDUSTRIES 401 RIVERSIDE PORTLAND, ME					
DM-1					