



- CLEAN AND PAINT EXIST. CAST-IRON BOOK STACKS TO REMAIN. SEE SPECS
- CUSTOM WD BOOKCASES: SEE A10.04
- GC COORD. NEW STL FRAMING BELOW NEW CONC. SLAB @ FORMER STAIR OPNG. SEE STRUCT. DWGS
- (7) EXIST. HISTORIC ELEC. FLOOR BOXES TO REMAIN
- (4) CUSTOM WD READER PRINTER WORK TABLES
- (7) CUSTOM WD CARPETS. WIRED FOR DATA/LIGHTING

- NEW CLS-FIN. HDWD HANDRAIL: MOUNT TO EXISTING WALLS @ 3'-0" AFF. SEE 15/A8.01
- NEW WD ENCLOSURE AT FCUS. SEE MECH. DWGS - COORD. W/MILLWORK
- NEW FLUSH FLOOR BOX: GC TO COORDINATE FINAL LOCATION W/OWNER & ARCHITECT READING TABLES, N.I.C.
- REFINISH EXIST'G HANDRAIL & PT MTL PICKETS & POSTS HISTORIC DOORS REINSTALLED IN EXISTING OPENING. SEE DOOR SCHED.
- DOOR OPERATOR, SEE ELEC.
- CUSTOM CASEWORK ENCLOSURE AT FCU. SEE MECH. & COORD. W/ADJACENT WD LOCKERS
- WD LOCKERS, 3'h. SEE INT ELEV NEW FLUSH FLOOR BOX: GC TO COORDINATE FINAL LOCATION W/OWNER & ARCHITECT EXISTING BRICK CORBELLING. SEE ELEV.
- CUSTOM WD DESK: SEE A10.02 FURR OUT FOR CHASE FCU WITHIN GWS CONSTRUCTION: SEE MECH. DWGS - COORD.
- FIX EXIST DOOR IN CLOSED POSITION: ADD INT. GLASS ENERGY PANEL (ALTERNATE 2: CHILDREN'S GATE) WD-FRAME LATTICE: SEE A6.04 FOR MATERIALS AND DETAILING

- FIX STL FIRE DOOR IN OPEN POSITION
- WALL MOUNTED DRINKING FOUNTAIN. SEE PLUMB. DWGS
- FTR, SEE MECH. DWGS
- REFINISH EXIST'G WD'S TRIMMER
- CUSTOM WD MILLWORK TO HOUSE HVAC

- CLEAN & REPOINT HEARTH BRICK WHERE NEEDED
- CLEAN AND REINSTALL EXIST. WD BLINDS LINE OF TUNNEL BELOW (ALT. 1)
- NEW BRICK RETAINING WALL. DECORATIVE COURSING TO MATCH HISTORIC DESIGN. SEE A6.03
- EXISTING WALL PANEL AGAINST EXIST. BLDG TO REMAIN

- CONSTRUCTION PLAN NOTES, FOR EXISTING LIBRARY BUILDING**
1. PATCHING OF EXISTING FLOOR SURFACES: PATCH EXISTING FLOOR SURFACES WITH LIKE MATERIALS AS APPROVED BY ARCHITECT. WHERE EXISTING SURFACE-MOUNTED OR RECESSED ITEMS OR OTHER INTERIOR CONSTRUCTION ARE INDICATED TO BE REMOVED AT FLOORS, MATERIAL AND FINISH AT EXISTING FLOOR SURFACES IS INDICATED ON FINISH SCHEDULE. DEMOLITION OF ITEMS AT FLOORS IS SHOWN ON DEMOLITION DRAWINGS AND IN DIVISION 1 SPECIFICATION SECTION "SELECTIVE DEMOLITION".
 2. PATCHING OF EXISTING WALL SURFACES: PATCH EXISTING WALL SURFACES WITH LIKE MATERIALS WHERE EXISTING SURFACE-MOUNTED OR RECESSED ITEMS OR OTHER INTERIOR CONSTRUCTION ARE INDICATED TO BE REMOVED AT WALLS. MATERIAL AND FINISH AT EXISTING WALL SURFACES IS INDICATED ON FINISH SCHEDULE. DEMOLITION OF ITEMS AT WALLS IS SHOWN ON DEMOLITION DRAWINGS AND IN DIVISION 1 SPECIFICATION SECTION "SELECTIVE DEMOLITION".
 3. WORK AT EXISTING OPENINGS: REFER TO DIVISION 8 SPECIFICATION SECTION "WORK AT EXISTING OPENINGS" FOR WORK AT DOORS, FRAMES OR HARDWARE AT EXISTING OPENINGS INDICATED TO REMAIN.
 4. EXISTING STONE AND MOSAIC TILE: REFER TO DIVISION 9 SPECIFICATION SECTION "INTERIOR STONE RESTORATION" FOR CLEANING OF EXISTING SURFACES; REFER ALSO TO DIVISION 9 SECTION "MOSAIC TILE REPAIR".
 5. EXISTING WOOD WINDOWS, DOORS, FRAMES, CASINGS AND TRIM: REFER TO DIVISION 9 SPECIFICATION SECTION "PAINTING" FOR REFINISHING WORK.

- CONSTRUCTION PLAN NOTES, FOR NEW BUILDING ADDITION**
1. HORIZONTAL DIMENSIONS INDICATED ON DRAWING ARE TO FINISH SURFACES UNLESS OTHERWISE INDICATED.
 2. DIMENSIONING AT DOOR OPENINGS: DIMENSIONS INDICATED AT DOOR JAMBS ARE THE DISTANCE BETWEEN THE ADJACENT FINISH FACE OF PARTITION AND THE SCHEDULED CLEAR OPENING WIDTH.
 3. FINISH FLOOR ELEVATIONS INDICATED FOR NEW CONSTRUCTION SHALL ALIGN WITH ELEVATIONS OF EXISTING BUILDING AS INDICATED; VERIFY EXISTING ELEVATIONS.
 4. FLOOR TILE LAYOUT: CENTER FLOOR TILES IN ROOMS IN BOTH DIRECTIONS UNLESS OTHERWISE NOTED. OBTAIN ARCHITECT'S APPROVAL OF ALL LAYOUTS BEFORE PROCEEDING WITH WORK.

1 FIRST FLOOR PLAN - EXIST.
Scale: 1/4" = 1'-0"

