



ROOM NO.	ROOM NAME	FLOOR			WALLS								CEILING			REMARKS		
		MATL.	FIN.	BASE	N	E	S	W	GWB	CEILING	HT.							
B01	MECH. ROOM	CONC.	SEAL	RB	F7	CONC	-	CONC/GWB	-PTD	CONC	PTD	CONC	PTD	3	EXP.	-	7'-3"	rubber base at gwb walls only
B03	ELEC. ROOM	CONC.	SEAL	RB	F7	GWB	PTD	GWB	-	GWB	PTD	GWB	PTD	3	EXP.	-	7'-3"	
B04	EMERG. ELEC.	CONC.	SEAL	RB	F7	GWB	PTD	CONC	-	GWB	PTD	GWB	PTD	3	EXP.	-	7'-3"	
B02	ST-02 BASEMENT	TILE	-	MTL	F3	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	4	-	-	VARIES	2hr. Rated enclosure; tile @ treads and mid-landing, painted risers, conc. @ basement landing
G02	STORAGE	conc.	SEAL	RB	exst.	GWB/vp	PTD	GWB	PTD	vp	PTD	vp	PTD	4	vp	PTD	10'-4 1/2"	Tunnel has conc. floor and ceiling, gwb walls; Level 3 finish
G03	JANITOR CLOSET	conc.	SEAL	RB	exst.	brick	-	brick/GWB	-PTD	brick	-	brick	-	3	conc.	-	10'-4 1/2"	
G04	CORRIDOR	TILE	-	state	F5	GWB	PTD	GWB	PTD	vp	PTD	GWB	PTD	4	vp	PTD	10'-4 1/2"	Reuse state base as salvaged; 9'-0" soff. see RCP
G05	TECH. SERVICES	CPT	-	HDWD	F6	vp	PTD	GWB	PTD	GWB	PTD	vp/VP	PTD	4	ACT	-	8'-0"	9'-6" soffit @ ext. wall (2'-0" wide)
G06	MEN	TILE	-	CT	F5	GWB/CT	PTD/-	GWB/CT	PTD/-	GWB/CT	PTD/-	GWB/CT	PTD/-	4	GWB	PTD	8'-0"	Tile wainscoting to 3'-0" AFF
G07	WOMEN	TILE	-	CT	F5	GWB/CT	PTD/-	GWB/CT	PTD/-	GWB/CT	PTD/-	GWB/CT	PTD/-	4	GWB	PTD	8'-0"	Tile wainscoting to 3'-0" AFF
G08	SHORT-TERM STOR.	conc.	SEAL	RB	exst.	GWB	PTD	vp/VP	PTD	GWB	PTD	GWB	PTD	4	vp/VP	PTD	10'-4 1/2"	Patch existing plaster
G09	PHOTO	conc.	SEAL	RB	exst.	GWB	PTD	vp/VP	PTD	GWB	PTD	GWB	PTD	4	vp/VP	PTD	10'-4 1/2"	Patch existing plaster
G10	ELEVATOR MACHINE	conc.	SEAL	RB	exst.	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	3	GWB	PTD	10'-4 1/2"	1 hr. rated GWB ceiling
G11	CLOSET	CONC.	SEAL	RB	F7	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	3	GWB	PTD	8'-6"	
G12	ELEVATOR WAITING	TILE	-	TILE	F3	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	4	GWB	PTD	8'-6"	
G13	ENTRY VESTIBULE	MAT	-	TILE	F3	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	4	GWB	PTD	8'-6"	Recessed walk-off mat
G15	KITCHEN	TILE	-	TILE	F3	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	4	GWB	PTD	9'-4 3/4"	
G16	COLLECTION STOR.	CONC.	SEAL	RB	F4	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	4	EXP/GWB	PTD	9'-3"	2 hr. rated soff. @ b.o. duct shaft; coord w/mech.
G17	SPECIAL PROJECTS	CONC.	SEAL	HDWD	F4	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	4	GWB	PTD	9'-4 3/4"	
G18	GARDEN STOR.	CONC.	SEAL	RB	F4	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	3	EXP.	PTD	9'-3"	b.o. steel
G01	ST-01 GARDEN LEVEL	m. tile	POL	gr.	exst.	vp	PTD	vp/VP	PTD	vp/VP	PTD	GWB	PTD	-	vp	PTD	VARIES	new gwb wall below stairs
G14	ST-02 GARDEN LEVEL	TILE	-	MTL	F3	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	4	-	PTD	VARIES	2hr. Rated enci; tile at treads/landings only, ptd. risers
101	ENTRY	m. tile	POL	gr	exst.	vp/VP	PTD	vp	PTD	vp	PTD	vp/VP	PTD	-	vp	PTD	13'-8"	Replace 15 l.f. granite base, repair 10s.f. ex mosaic flooring; new 2 hr. rated shaft
102	COATS	m. tile	POL	gr	exst.	vp/VP	PTD	vp	PTD	vp	PTD	vp	PTD	-	vp	PTD	8'-6"	
103	WATER CLOSET	CT	-	CT	F5	GWB/CT	PTD/-	GWB/CT	PTD/-	GWB/CT	PTD/-	GWB/CT	PTD/-	4	VP	PTD	8'-6"	Tile wainscoting to 3'-0" AFF
104	READING ROOM	m. tile	POL	gr	exst.	vp/VP	PTD	vp/VP	PTD	vp	PTD	vp	PTD	-	vp	PTD	13'-9 1/2"	Replace 20 l.f. granite base, repair 20 s.f. exist. mosaic flooring
105	CAST IRON STACKS	m. tile	POL	mt/gr	exst.	vp	PTD	vp/VP	PTD	-	-	vp	PTD	-	gl	-	6'-6 1/2"	Clean and paint cast-iron framing
106	CLOSET	CONC.	SEAL	RB	F4	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	3	EXP	PTD	±5'-8"	
107	ELEVATOR WAITING	TILE	-	TILE	F3	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	4	GWB	PTD	10'-6"	2 hr. rated ceiling, 40 s.f. see rcp for location
108	CLOSET	CONC.	SEAL	RB	F4	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	4	GWB	PTD	13'-0"	
109	CONFERENCE ROOM	HDWD	CLR	HDWD	F1	GWB	PTD	GWB	PTD	GL/GWB	-PTD	GL	-	5	GWB	PTD	11'-0" / 13'-0"	Hardwood sliding shutters @ cw; gwb soffit, see rcps
110	COLLECTION STOR.	CONC.	SEAL	RB	F4	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	4	EXP.	PTD	12'-10"	b.o. steel
112	STAFF MTG ROOM	HDWD	CLR	HDWD	F1	GWB	PTD	GWB	PTD	GWB	PTD	GL	-	5	GWB	PTD	11'-0" / 13'-0"	Hardwood sliding shutters @ cw; gwb soffit, see rcps
113	LIBRARIAN OFFICE	HDWD	CLR	HDWD	F1	GWB	PTD	GWB	PTD	GWB	PTD	GL	-	5	GWB	PTD	11'-0" / 13'-0"	Hardwood sliding shutters @ cw; gwb soffit, see rcps
100	ST-01 FIRST FLOOR	m. tile	-	gr	exst.	vp	PTD	vp	PTD	vp	PTD	-	-	-	vp	PTD	VARIES	
111	ST-02 FIRST FLOOR	TILE	-	MTL	F3	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	4	-	PTD	VARIES	2hr. Rated enci; tile at treads/landings only, ptd. risers
M01	ELEVATOR WAITING	TILE	-	TILE	F3	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	4	EXP	PTD	18'-3"	b.o. deck
M02	CAST IRON STACKS	gl/GL	-	mtl	exst.	vp	PTD	vp	PTD	-	-	vp	PTD	-	vp	PTD	6'-10"	8 new glass floor plates (5 new, 3 replacements)
M03	ST-02 MEZZANINE	TILE	-	MTL	F3	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	4	-	-	VARIES	2hr. Rated enci; tile at treads/landings only, ptd. risers
202	READING ROOM VEST.	m. tile	-	gr	exst.	vp	PTD	vp	PTD	vp	PTD	vp	PTD	-	vp	PTD	11'-9"	
203	LOUNGE	m. tile	-	gr	exst.	vp/VP	PTD	vp	PTD	vp	PTD	vp/VP	PTD	-	vp	PTD	11'-9"	2 hr. rated shaft
204	READING ROOM	m. tile	-	gr	exst.	vp	PTD	vp/VP	PTD	vp	PTD	vp	PTD	-	vp	PTD	11'-9"	Plaster work @ 75% E wall; repair 60s.f. terrazzo
205	CAST IRON STACKS	gl/GL	-	mtl	exst.	vp	PTD	vp	PTD	vp	PTD	vp	PTD	-	vp	PTD	11'-9"	7 new glass floor plates (5 new, 2 replacements)
206	NOT USED																	
207	ELEVATOR WAITING	TILE	-	TILE	F3	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	4	GWB	PTD	8'-6"	
209	MAINE MEMORY OFFICES	CPT	-	HDWD	F2	GWB	PTD	GWB	PTD	GL/GWB	-PTD	GL	-	5	GWB	PTD	9'-6" / 10'-10"	Hardwood sliding shutters @ cw; gwb soffit, see rcps
210	OFFICE	CPT	-	HDWD	F2	GWB	PTD	GWB	PTD	GWB	PTD	GL	-	5	GWB	PTD	9'-6" / 10'-10"	Hardwood sliding shutters @ cw; gwb soffit, see rcps
212	COLLECTION STOR.	CONC	SEAL	RB	F4	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	4	EXP.	PTD	9'-4"	b.o. steel
201	ST-01 SECOND FLOOR	m. tile	-	gr	exst.	vp	PTD	vp	PTD	vp	PTD	-	-	-	vp	PTD	VARIES	
211	ST-02 SECOND FLOOR	TILE	-	MTL	F3	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	4	-	PTD	VARIES	2hr. Rated enci; tile at treads/landings only, ptd. risers
R01	ST-02 PENTHOUSE	TILE	-	MTL	F3	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	4	EXP.	PTD	-	2hr. Rated enci; tile at treads/mid landing only, ptd. Risers; conc. @ pent landing
R02	MECHANICAL	CONC	SEAL	RB	F7	GWB	PTD	GWB	PTD	GWB	PTD	GWB	PTD	3	EXP.	PTD	-	

KEY	FLOOR TYPE
UPPERCASE = NEW	F1 HDWD
lowercase = existing	F2 CPT
	F3 TILE
CONC	F4 TOPPING SLAB
CPT	F5 TILE ON EXIST. CONC.
CT	F6 CPT ON EXIST. CONC.
EXST	F7 CONC. S.O.G.
EXP	
GL	
GR	
GWB	
HDWD	
M. TILE	
MTL	
POL	
PTD	
RB	
TILE	
VP	

1 FINISH SCHEDULE  
Scale: NO SCALE

**SCHWARTZ / SILVER ARCHITECTS INC.**

75 Kneeland Street  
Boston, Massachusetts 02111 Telephone 617/542-6650  
Facsimile 617/951-0779

---

**MAINE HISTORICAL SOCIETY**  
489 CONGRESS ST.  
PORTLAND, MAINE

---

**PROJECT**

**DATE** 09/13/07 **REVISIONS**

REVISION NUMBER	DESCRIPTION	DATE	BY	DATE
REVISION 01				

---

**DRAWING NUMBER** A11.02 **FINISH SCHEDULE FLOOR DETAILS**