



D.F. INTERNALLY ILLUMINATED FREESTANDING SIGN

12 X 8 - 96 SQ. FT.

(1) D.F. 12'-0" X 8'-0" X 1'-2" INTERNALLY ILLUMINATED SIGN

COLORS: FACES, POLE WRAP, REVEAL AND ADDRESS BAND TO MATCH OR COMPLEMENT BUILDING COLORS

(1) TENANT PANEL 56" X 8'-0" FACE WITH JIGGED OUT COPY BACKED UP WITH ACRYLIC & VINYL

(3) TENANT PANELS 27 1/4" X 8'-0" ALUMINUM FACES WITH JIGGED OUT COPY BACKED UP WITH ACRYLIC & VINYL


CUSTOM TENANT ART & COLORS
VECTOR ART, COLOR SPECS & PRINT FILES WILL BE NEEDED FOR PRODUCTION

18.625 LARGE CAP
14 1/2" SMALL CAP
1' X 7'-0" V.O.

8" ADDRESS COPY: 1/2" CUT OUT COMPOSITE / PAINTED BLACK / MOUNTING: _____

(2) 6" SQ. POLES
DIRECT SET _____ O.C.
BASE 3'-0" X 3'-0" X 6'-0" DEEP

CRUSHED ROCK

CLIENT	
ACCEPTANCE SIGNATURE _____	DATE _____
BAILEY SIGN SALES REPRESENTATIVE	
APPROVED _____	DATE _____
 <p>www.baileysign.com 9 Thomas Drive Col. Westbrook Executive Park Westbrook, ME 04092 207-774-2843 / 1-800-539-SIGN Fax: 774-1193 E-Mail: sales@baileysign.com</p>	
CUSTOMER / SIGN LOCATION	
BOUOS	
765 WARREN AVE. PORTLAND, MAINE	
SALESPERSON: BB	DRAWN BY: LWM
PS: # D-176	W.O. # _____
SCALE 1/4" = 1'	DATE 7/10/13
REVISION # / DATE / NOTES / INITIALS	
DRAWING #	
07014 D BASE	
SHEET _____ OF _____	



PERMIT DRAWING