

City of Portland, Maine – Building or Use Permit Application 389 Congress Street, 04101, Tel: (207) 874-8703, FAX: 874-8716

Location of Construction: 741 Warren Ave.		Owner: Warren Ave Corporation		Phone:		Permit No: 980051	
Owner Address: 49 Omni Circle, Auburn, ME		Lessee/Buyer's Name:		Phone:		BusinessName:	
Contractor Name: Sheridan Corp		Address: POBox 689, Westbrook 04092		Phone: 774-6138		<div style="border: 2px solid black; padding: 5px; text-align: center;"> PERMIT ISSUED Permit Issued: <div style="border: 1px solid black; padding: 5px; margin: 5px 0;"> JAN 28 1998 </div> CITY OF PORTLAND Zone: CBL: 316-A-5 </div>	
Past Use: Office		Proposed Use: int reno		COST OF WORK: \$ 26,000.00 PERMIT FEE: \$ 150.00			
Proposed Project Description: Interior renovations as per plans		FIRE DEPT. <input checked="" type="checkbox"/> Approved <input type="checkbox"/> Denied Signature: <i>ADM7</i>		INSPECTION: Use Group: B Type: 20 Signature: <i>Boca 96</i>		Zoning Approval: Special Zone or Reviews: <input type="checkbox"/> Shoreland <input type="checkbox"/> Wetland <input type="checkbox"/> Flood Zone <input type="checkbox"/> Subdivision <input type="checkbox"/> Site Plan maj <input type="checkbox"/> minor <input type="checkbox"/> mm <input type="checkbox"/>	
		PEDESTRIAN ACTIVITIES DISTRICT (P.A.D.) Action: Approved <input type="checkbox"/> Approved with Conditions: <input type="checkbox"/> Denied <input type="checkbox"/>		Signature: _____ Date: _____			
		Permit Taken By: Vicki Dover		Date Applied For: 1/16/98			

- This permit application does not preclude the Applicant(s) from meeting applicable State and Federal rules.
- Building permits do not include plumbing, septic or electrical work.
- Building permits are void if work is not started within six (6) months of the date of issuance. False information may invalidate a building permit and stop all work..

Call contractor for P/U

PERMIT ISSUED WITH REQUIREMENTS

PERMIT ISSUED WITH REQUIREMENTS

CERTIFICATION

I hereby certify that I am the owner of record of the named property, or that the proposed work is authorized by the owner of record and that I have been authorized by the owner to make this application as his authorized agent and I agree to conform to all applicable laws of this jurisdiction. In addition, if a permit for work described in the application is issued, I certify that the code official's authorized representative shall have the authority to enter all areas covered by such permit at any reasonable hour to enforce the provisions of the code(s) applicable to such permit

SIGNATURE OF APPLICANT <i>Ken Lamoreaux</i> Sheridan Corp	ADDRESS:	DATE: 1/16/98	PHONE: 774-6138
---	----------	------------------	--------------------

RESPONSIBLE PERSON IN CHARGE OF WORK, TITLE	PHONE:
---	--------

Action:

Approved
 Approved with Conditions
 Denied

Date: 1/16/98

CEO DISTRICT

7

K. [unclear]

COMMENTS

1/31/98 - Work Complete - No Structural Changes

Issue CJO

Entire - Office Space/ Training Center

No Restrictions

Inspection Record

Type	Date
Foundation: _____	_____
Framing: _____	_____
Plumbing: _____	_____
Final: _____	_____
Other: _____	_____



CITY OF PORTLAND, MAINE
Department of Building Inspection

Certificate of Occupancy

LOCATION 741 Warren Ave (316-A-005)

Issued to Warren Ave Corp.

Date of Issue 03 February 1998

This is to certify that the building, premises, or part thereof, at the above location, built — altered — changed as to use under Building Permit No. 980051, has had final inspection, has been found to conform substantially to requirements of Zoning Ordinance and Building Code of the City, and is hereby approved for occupancy or use, limited or otherwise, as indicated below.

PORTION OF BUILDING OR PREMISES

APPROVED OCCUPANCY

Entire

Office Space/Training Center

Limiting Conditions:

This certificate supersedes
certificate issued

Approved:

2/3/98
(Date)

K. Small
Inspector

Samuel [Signature]
Inspector of Buildings

Notice: This certificate identifies lawful use of building or premises, and ought to be transferred from owner to owner when property changes hands. Copy will be furnished to owner or lessee for one dollar.

NO
Elec
check
OK

2/4/98

BUILDING PERMIT REPORT


DATE: 1/27/98 ADDRESS: 741 Warren Ave
 REASON FOR PERMIT: renovation
 BUILDING OWNER: Warren Ave Corp
 CONTRACTOR: Sheridan Corp
 PERMIT APPLICANT: Ken Lamoreaux APPROVAL: *1, *8, *17, *18, *19, *20 ~~DENIED~~
 USE GROUP B BOCA 1996 CONSTRUCTION TYPE 2C

CONDITION(S) OF APPROVAL

- *1. This permit does not excuse the applicant from meeting applicable State and Federal rules and laws.
2. Before concrete for foundation is placed, approvals from the Development Review Coordinator and Inspection Services must be obtained. (A 24 hour notice is required prior to inspection)
3. Precaution must be taken to protect concrete from freezing.
4. It is strongly recommended that a registered land surveyor check all foundation forms before concrete is placed. This is done to verify that the proper setbacks are maintained.
5. Private garages located beneath habitable rooms in occupancies in Use Group R-1, R-2, R-3 or I-1 shall be separated from adjacent interior spaces by fire partitions and floor/ceiling assembly which are constructed with not less than 1-hour fire resisting rating. Private garages attached side-by-side to rooms in the above occupancies shall be completely separated from the interior spaces and the attic area by means of ½ inch gypsum board or the equivalent applied to the garage means of ½ inch gypsum board or the equivalent applied to the garage side. (Chapter 4 Section 407.0 of the BOCA/1996)
6. All chimneys and vents shall be installed and maintained as per Chapter 12 of the City's Mechanical Code. (The BOCA National Mechanical Code/1993).
7. Sound transmission control in residential building shall be done in accordance with Chapter 12 section 1214.0 of the city's building code.
- *8. Guardrails & Handrails: A guardrail system is a system of building components located near the open sides of elevated walking surfaces for the purpose of minimizing the possibility of an accidental fall from the walking surface to the lower level. Minimum height all Use Groups 42", except Use Group R which is 36". In occupancies in Use Group A, B, H-4, I-1, I-2 M and R and public garages and open parking structures, open guards shall have balusters or be of solid material such that a sphere with a diameter of 4" cannot pass through any opening. Guards shall not have an ornamental pattern that would provide a ladder effect. (Handrails shall be a minimum of 34" but not more than 38". Use Group R-3 shall not be less than 30", but not more than 38".)
9. Headroom in habitable space is a minimum of 7'6".
10. Stair construction in Use Group R-3 & R-4 is a minimum of 10" tread and 7 3/4" maximum rise. All other Use group minimum 11" tread, 7" maximum rise.
11. The minimum headroom in all parts of a stairway shall not be less than 80 inches. (6' 8")
12. Every sleeping room below the fourth story in buildings of use Groups R and I-1 shall have at least one operable window or exterior door approved for emergency egress or rescue. The units must be operable from the inside without the use of special knowledge or separate tools. Where windows are provided as means of egress or rescue they shall have a sill height not more than 44 inches (1118mm) above the floor. All egress or rescue windows from sleeping rooms shall have a minimum net clear opening height dimension of 24 inches (610mm). The minimum net clear opening width dimension shall be 20 inches (508mm), and a minimum net clear opening of 5.7 sq. ft.
13. Each apartment shall have access to two (2) separate, remote and approved means of egress. A single exit is acceptable when it exits directly from the apartment to the building exterior with no communications to other apartment units.
14. All vertical openings shall be enclosed with construction having a fire rating of at least one (1) hour, including fire doors with self closer's.
15. The boiler shall be protected by enclosing with (1) hour fire-rated construction including fire doors and ceiling, or by providing automatic extinguishment.
16. All single and multiple station smoke detectors shall be of an approved type and shall be installed in accordance with the provisions of the City's Building Code Chapter 9, Section 19, 920.3.2 (BOCA National Building Code/1996), and NFPA 101 Chapter 18 & 19. (Smoke detectors shall be installed and maintained at the following locations):
 - In the immediate vicinity of bedrooms
 - In all bedrooms

In each story within a dwelling unit, including basements
In addition to the required AC primary power source, required smoke detectors in occupancies in Use Groups R-2, R-3 and
I-1 shall receive power from a battery when the AC primary power source is interrupted. (Interconnection is required)

- 17. A portable fire extinguisher shall be located as per NFPA #10. They shall bear the label of an approved agency and be of an approved type.
- 18. The Fire Alarm System shall be maintained to NFPA #72 Standard.
- 19. The Sprinkler System shall maintained to NFPA #13 Standard.
- 20. All exit signs, lights, and means of egress lighting shall be done in accordance with Chapter 10 Section & Subsections 1023. & 1024. Of the City's building code. (The BOCA National Building Code/1996)
- 21. No construction or demolition work shall begin until you have obtained permits for dumpsters or containers. A work Stop Order shall be issued if this requirement is not met.
- 22. Section 25-135 of the Municipal Code for the City of Portland states, "No person or utility shall be granted a permit to excavate or open any street or sidewalk from the time of November 15 of each year to April 15 of the following year".
- 23. The builder of a facility to which Section 4594-C of the Maine State Human Rights Act Title 5 MRSA refers, shall obtain a certification from a design professional that the plans commencing construction of the facility, the builder shall submit the certification to the Division of Inspection Services.
- 24. This permit does not excuse the applicant from obtaining any license which may be needed from the City Clerk's office.
- 25. Ventilation shall meet the requirements of Chapter 12 Sections 1210. of the City's Building Code.
- 26. All electrical, plumbing and HVAC permits must be obtained by a Master Licensed holders of their trade.
- 27. All requirements must be met before a final Certificate of Occupancy is issued.
- 28. All building elements shall meet the fastening schedule as per Table 2305.2 of the City's Building Code. (The BOCA National Building Code/1996).
- 29. Ventilation of spaces within a building shall be done in accordance with the City's Mechanical Code (The BOCA National Mechanical Code/1993).
- 30.
- 31.
- 32.
- 33.
- 34.


P. Samuel Hoff, Code Enforcement
cc: Lt. McDougall, PFD
Marge Schmuckal

DEBT01 Debtors Detail Screen 16 Jan 98 07:42 VAD
 Ref Nbr Name of Debtor Total Due
 003770 WARREN AVENUE CORPORATION From All Accts
 WARREN AVE 0000739 15,910.81

Trans Nbr	Trans Type	Account Number Account Description	Pay Plan Date	Exempt Flag	Total Amount Due	Paid Flag
00001	RT	98W07450 316 A00500101	/ / 9801		15,910.81	
			/ /			
			/ /			
			/ /			
			/ /			
			/ /			
			/ /			

F2 to View Next Debtor F9 to View More Trans Msg-wait to Return [_

- *payment plan*
OK per PSH

KEEP THIS PORTION

ACCOUNT NUMBER **W07450-98**

1998 REAL ESTATE PROPERTY TAX STATEMENT
City of Portland

CBL
316 - A - 005 - 001

Fiscal Year 1998
July 1, 1997 - June 30, 1998

LENDING INST.

Owner of Record as of April 1, 1997

WARREN AVENUE CORPORATION
P O BOX 262
OLD ORCHARD BEACH ME 04064

Assessed Property Description
316-A-5
318-A-11
WARREN AVE 741-747
228690 SF

CURRENT BILLING DISTRIBUTION

School	\$ 16,558.61
Public Works	\$ 2,283.94
Parks & Recreation	\$ 888.20
Fire	\$ 2,791.49
Police	\$ 2,886.65
Debt Repayments	\$ 2,728.04
General Government	\$ 1,175.69
County	\$ 1,046.81
Health & Human Services	\$ 793.04
Library	\$ 1,046.81
Metro Transit District	\$ 761.31
Enterprise Funds	\$ 126.89
Regional Waste Systems	\$ 475.82

CURRENT BILLING INFORMATION

Land Value	\$ 191,160.00
Building Value	\$ 1,100,430.00
Total Value	\$ 1,291,590.00
Exemptions	\$.00
Taxable Value	\$ 1,291,590.00
Tax Rate	\$ 24.56
TOTAL TAX	\$ 31,721.44
AMOUNT PAID	\$.00

Remittance Instructions

To avoid standing in line, it is recommended that taxes be paid by mail. Please make check or money order payable to: **CITY OF PORTLAND**. Credit cards are not accepted for property tax payments.

Use enclosed envelope to return your payment or mail to:

City of Portland
P.O. Box 544
Portland, ME 04112 - 0544

9116197
✓ 1081#
Pd 15860.72

Use top right margin for change of address and check off box on return envelope.

WARREN AVE. CORP.
P.O. BOX 262
OLD ORCHARD BEACH, ME 04064

085412 32-60/112

1081

Sept 16 19 97

PAY TO THE ORDER OF

City of Portland

\$ 15,860.72

Fifteen thousand eight hundred sixty and 72/100 DOLLARS




Key Bank of Maine
Kennebunk, Maine 04043 148

MEMO

Bette A. L. [Signature]

⑆0⑆1⑆200608⑆00 200⑆6⑆4⑆4 ⑆?⑆ 108⑆ ⑆000⑆5860⑆7⑆2⑆⑆



7 4 4 2 0 4 4

ENDORSE HERE

FOR DEPOSIT ONLY
CITY OF PORTLAND, ME
KEY BANK 00-000-748
FINANCE TREASURY

0112
00601

SEP 19 1997
SEP 17 1997

SEP 17 1997