BRADCO Supply

If you have questions on this material, please call me.

Sincerely,

SEBAGO TECHNICS, INC

Stephen G. Doe, R.L.A. Landscape Architect

SGD:sgd/kn/jc

Enc.

cc: Howard "Skip" Roberts

David Fagnaunt BRADCO Supply
Les Friedman Wickes Lumber
Phillip Morin PM Construction

Tom Errico Wilber Smith Associates

Steve Bushey DeLuca-Hoffman



September 28,2005

Steve Doe, R.L.E. Sebago Technics PO **Box** 1339 Westbrook, Me. 04098

Re: 238 Riverside St.-Portland

Steve:

This letter is to confirm there should **be** an adequate supply of clean and healthful water to serve the needs of the proposed warehouse building at 238 Riverside St. in Portland. Checking District records, I find there is a 12"CI water main on the west side of Riverside St. as well as a water hydrant located in front of the property.

Service records for 238 Riverside indicate there is an **8**" fire service and a 1"domestic water service tapped off the **8**" fire service. See enclosed service record.

The current data from the nearest hydrant indicates there should be adequate capacity **of** water to serve the needs of your proposed project.

Hydrant Location: Riverside St. 300' north of Campbell St.

Hydrant# 1264

Static pressure = 82 PSI Residual pressure = 74 **PSI** Flow = 1393 GPM Last Tested = 9/9/2004

If the District can be of further assistance in this matter, please Yet us know.

Sincerely,

Portland Water District

dem " were

Jim Pandiscio

Means Coordinator



