

City of Portland, Maine – Building or Use Permit Application 389 Congress Street, 04101, Tel: (207) 874-8703, FAX: 874-8716

Location of Construction: 260 Riverside St		Owner: Pro Lube		Phone:		Permit No:	
Owner Address:		Lessee/Buyer's Name: Jiffy Lube		Phone:		BusinessName:	
Contractor Name: Sign Design, Inc.		Address: 743 Broadway So. Ptld, ME		Phone: 04106 799-2000		Permit Issued:	
Past Use: Auto Service		Proposed Use: Same		COST OF WORK: \$		PERMIT FEE: \$ 44.40	
				FIRE DEPT. <input type="checkbox"/> Approved <input type="checkbox"/> Denied		INSPECTION: Use Group: Type:	
Proposed Project Description: Erect Sign				Signature:		Signature:	
				PEDESTRIAN ACTIVITIES DISTRICT (P.A.D.) Action: Approved <input type="checkbox"/> Approved with Conditions: <input type="checkbox"/> Denied <input type="checkbox"/>		Zone: CBL: 316-B-006	
Permit Taken By: Mary Gresik		Date Applied For: 27 August 1997				Zoning Approval: Special Zone or Reviews: <input type="checkbox"/> Shoreland <input type="checkbox"/> Wetland <input type="checkbox"/> Flood Zone <input type="checkbox"/> Subdivision <input type="checkbox"/> Site Plan maj <input type="checkbox"/> minor <input type="checkbox"/> mm <input type="checkbox"/>	

1. This permit application does not preclude the Applicant(s) from meeting applicable State and Federal rules.
2. Building permits do not include plumbing, septic or electrical work.
3. Building permits are void if work is not started within six (6) months of the date of issuance. False information may invalidate a building permit and stop all work..

Zoning Appeal

Variance
 Miscellaneous
 Conditional Use
 Interpretation
 Approved
 Denied

Historic Preservation

Not in District or Landmark
 Does Not Require Review
 Requires Review

Action:

Approved
 Approved with Conditions
 Denied

Date: _____

CERTIFICATION

I hereby certify that I am the owner of record of the named property, or that the proposed work is authorized by the owner of record and that I have been authorized by the owner to make this application as his authorized agent and I agree to conform to all applicable laws of this jurisdiction. In addition, if a permit for work described in the application is issued, I certify that the code official's authorized representative shall have the authority to enter all areas covered by such permit at any reasonable hour to enforce the provisions of the code(s) applicable to such permit

SIGNATURE OF APPLICANT <i>Paul Acker</i>		ADDRESS: 743 BROADWAY So. Portland		DATE: 27 August 1997		PHONE:	
RESPONSIBLE PERSON IN CHARGE OF WORK, TITLE PAUL ACKER SALES						PHONE: 799-2000	

CEO DISTRICT

SIGNAGE

PLEASE ANSWER ALL QUESTIONS

Address: 2160 RIVERSIDE ST. Zone: B-4

Owner: PRO LUBE INC. Assessors #: _____

Applicant: SIGN DESIGN INC. / PRO LUBE INC

Single Tenant Lot?: Yes No *shows to 25' tall*

Multi Tenant Lot?: Yes No *see design*

Freestanding (Ext pole sign)? Yes No Dimensions 61' x 18' *(note 65' max)*

More than (1) one sign?: Yes No Dimensions _____

Bldg Wall Sign (att to bldg)? Yes No Dimensions 35.25' per *Spec sheets*

List all existing signage and their dimensions:
NONE

Lot Frontage(feet): 60' Tenant Frontage(feet): 60' x 25'

AWNINGS

Awning?: Yes No Is Awning Backlit?: Yes No

Is there any communication, message, trademark or symbol on awning? _____

Height of Awning?: _____

PLEASE NOTE: Approvals for signs on the Public Sidewalk and temporary signs come under different requirements and regulations.

ALSO: See reverse side for additional information, requirements and materials needed for signage application submittal.

SPECIFICATIONS

* USING "I" OF THESE ON CURB CUT AT RIVERSIDE ST

1'6" x 3' DIRECTIONAL SIGNS

Illuminated, double faced roadside signs available in three versions:

1. ENTER on each side;
2. EXIT on each side;
3. ENTER on one side and EXIT on the other.

DIMENSIONS:	1'6" x 3'1"
SQUARE FOOTAGE:	4.62
FACES:	.100" SG-100 Polycarbonate pan faces with screened graphics
DECORATION:	Screened, Flame Red (FR-1-585) and White (FR-1-110)
CABINET:	Extruded aluminum, primed and painted
ELECTRICAL:	1.60 total AMPS, 1-15 AMP circuit, 120V with 2 #12 lead wires
INSTALLATION:	Center pole mount

Non-illuminated versions are available by special order.

HERITAGE MERCHANDISING
has illuminated and non-illuminated
directional signs.

SPECIFICATIONS

*NOT USING NEON, ~~FLUORESCENT TUBES INSIDE~~
NON-ILLUMINATED*

BUILDING LETTERS/FIXED COPY SIGN

Illuminated/neon letters mounted on a raceway that is also an illuminated panel sign. This unique sign is available in four versions:

- ~~1. Red neon letters trimmed in white, with a white raceway panel with slogan, "America's Favorite Oil Change," encased in mahogany brown cabinet.~~
- ~~2. As above except with a white raceway panel with slogan, "14-Point-Oil-Filter-Fluid-Service." (Optional by special order.) Encased in mahogany brown cabinet.~~
- ~~3. White neon letters with a white raceway panel with slogan, "America's Favorite Oil Change," in red. (Optional by special order.)~~
- ~~4. As in 3 above except with a white raceway panel with slogan, "14-Point-Oil-Filter-Fluid-Service," in red. (Optional by special order.)~~

~~DIMENSIONS: 3'x11'9"~~

~~SQUARE FOOTAGE: 35.25 (squared)
28.2 (sign area only)~~

~~FACES: .187" white pigmented acrylic letters with red translucent film raceway panel .187" white pigmented acrylic fixed copy strip with mahogany brown screened copy. Red letter faces trimmed with white edge molding.~~

~~CABINET: .050" aluminum sides with .063" aluminum backs, primed and painted mahogany brown. Remove letter faces for access.~~

~~ELECTRICAL: 14 total AMPS, 1-20 AMP circuit, 120V with 2 #12 lead wires per section (Jiffy and Lube are separate sections)~~

~~INSTALLATION: 1 1/2" x 3/16" mounting bars with 8/16" diameter mounting bolts~~

INDIVIDUAL LETTERS

~~6' WALL MOUNT LOGO SIGN~~

~~Single faced, illuminated wall sign in standard and reverse logo versions, ideal for mounting on either side or both sides of the building.~~

~~DIMENSIONS: 67" x 6'5 1/8"~~

~~SQUARE FOOTAGE: 18.9 (sign area only)~~

~~FACES: .125" SG-100 Polycarbonate pan face with 5/8" embossed graphics~~

~~DECORATION: Screened, Flame Red (FR-1-585) and White (FR-1-110)~~

~~CABINET: Extruded aluminum 8" wide with 1" face retainer, primed and painted mahogany. Remove screws from retainer for service.~~

~~ELECTRICAL: 3.0 total AMPS, 1-15 AMP circuit, 120V with 2 #12 lead wires~~

~~INSTALLATION: Wall mount with 3/8" diameter bolts~~

~~3'7" x 8' WALL MOUNT READERBOARD~~

~~Single faced, illuminated with four lines of track. Typical installation is on the arrow point side of the 6' wall mount logo sign.~~

~~DIMENSIONS: 37" x 8'1 1/8"~~

~~SQUARE FOOTAGE: 28.98~~

~~FACES: .125" SG-100 Polycarbonate pan face with four lines of zip track~~

~~DECORATION: Screened, white only (FR-1-110)~~

~~CABINET: Extruded aluminum 10" wide, primed and painted mahogany. Face hinged for service.~~

~~ELECTRICAL: 3.0 total AMPS, 1-15 AMP circuit~~

~~INSTALLATION: Wall mount with 3/8" diameter bolts~~

BUILDING IDENTIFICATION

jiffylube

America's Favorite Oil Change

BUILDING LETTERS
FIXED COPY SIGN



6' Wall Mount Logo Sign
with 2' x 9' Wall Mount Readerboard