



DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK



# CITY OF PORTLAND

# BUILDING

# PERMIT

This is to certify that \* 410 RIVERSIDE ST LLC

Located At 410 RIVERSIDE

Job ID: 2011-01-240-FAFS

CBI: 320 - - A - 002 - 001 - - - -

has permission to install Fire Suppression System

provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statues of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of the buildings and structures, and of the application on file in the department.

Notification of inspection and written permission procured before this building or part thereof is lathed or otherwise closed-in. 48 HOUR NOTICE IS REQUIRED.

A final inspection must be completed by owner before this building or part thereof is occupied. If a certificate of occupancy is required, it must be procured prior to occupancy.

\_\_\_\_\_  
**Fire Prevention Officer**

**Code Enforcement Officer / Plan Reviewer**

THIS CARD MUST BE POSTED ON THE STREET SIDE OF THE PROPERTY.  
PENALTY FOR REMOVING THIS CARD

## BUILDING PERMIT INSPECTION PROCEDURES

Please call 874-8703 or 874-8693 (ONLY)

or email: [buildinginspections@portlandmaine.gov](mailto:buildinginspections@portlandmaine.gov)

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the city of Portland Inspections Services for the following inspections. Appointments must be requested 48 to 72 hours in advance of the required inspection. The inspection date will need to be confirmed by this office.

- **Please read the conditions of approval that is attached to this permit!! Contact this office if you have any questions.**
- **Permits expire in 6 months. If the project is not started or ceases for 6 months.**
- **If the inspection requirements are not followed as stated below additional fees may be incurred due to the issuance of a "Stop Work Order" and subsequent release to continue.**

1.

The project cannot move to the next phase prior to the required inspection and approval to continue, REGARDLESS OF THE NOTICE OF CIRCUMSTANCES.

IF THE PERMIT REQUIRES A CERTIFICATE OF OCCUPANCY, IT MUST BE PAID FOR AND ISSUED TO THE OWNER OR DESIGNEE BEFORE THE SPACE MAY BE OCCUOPIED.



*Strengthening a Remarkable City. Building a Community for Life • [www.portlandmaine.gov](http://www.portlandmaine.gov)*

Director of Planning and Urban Development  
Penny St. Louis Littell

Job ID: 2011-01-240-FAFS

Located At 410 RIVERSIDE

CBI,320 - - A - 002 - 001 - - - - -

## **Conditions of Approval:**

### **Zoning**

410 Riverside St. / 51 Ingorsoll Dr.

1. This property shall remain a warehouse, production & distribution of medical gasses. Any change of use shall require a separate permit application for review and approval.

**City of Portland, Maine - Building or Use Permit Application**  
 389 Congress Street, 04101 Tel: (207) 874-8703, FAX: (207) 8716

Job No: 2011-01-240-FAFS	Date Applied: 1/11/2011	CBL: 320 - - A - 002 - 001 - - - - -	
Location of Construction: 410 RIVERSIDE /51 Ingersoll Dr	Owner Name: * 410 RIVERSIDE ST LLC	Owner Address: 70 INGERSOLL DR PORTLAND, ME - MAINE 04103	Phone:
Business Name: Airgas	Contractor Name: Garland, Scott	Contractor Address: P.O. Box 1285 LEWISTON MAINE04240	Phone:
Lessee/Buyer's Name:	Phone:	Permit Type: FIRE SYS NWB - Fire Suppression Non-Water Based	Zone: I-M
Past Use: Warehouse-Production & distribution of medical gasses (Airgas)	Proposed Use: Same - Warehouse - production & distribution of medical gasses (Airgas)	Cost of Work:	CEO District:
		Fire Dept: <input checked="" type="checkbox"/> Approved /w conditions <input type="checkbox"/> Denied <input type="checkbox"/> N/A	Inspection: Use Group: Type: <i>Sprinkler</i>
		Signature: <i>KG</i>	Signature: <i>[Signature]</i>
Proposed Project Description: <b>install Fire Suppression Sys</b>		Pedestrian Activities District (P.A.D.)	
Permit Taken By:	<b>Zoning Approval</b>		

Special Zone or Reviews	Zoning Appeal	Historic Preservation
<input type="checkbox"/> Shoreland <input type="checkbox"/> Wetlands <input type="checkbox"/> Flood Zone <input type="checkbox"/> Subdivision <input type="checkbox"/> Site Plan <input type="checkbox"/> Maj <input type="checkbox"/> Min <input type="checkbox"/> MM Date: <i>OK with conditions 1/13/11</i>	<input type="checkbox"/> Variance <input type="checkbox"/> Miscellaneous <input type="checkbox"/> Conditional Use <input type="checkbox"/> Interpretation <input type="checkbox"/> Approved <input type="checkbox"/> Denied Date:	<input checked="" type="checkbox"/> Not in Dist or Landmark <input type="checkbox"/> Does not Require Review <input type="checkbox"/> Requires Review <input type="checkbox"/> Approved <input type="checkbox"/> Approved w/Conditions <input type="checkbox"/> Denied Date: <i>[Signature]</i>

**CERTIFICATION**

I hereby certify that I am the owner of record of the named property, or that the proposed work is authorized by the owner of record and that I have been authorized by the owner to make this application as his authorized agent and I agree to conform to all applicable laws of this jurisdiction. In addition, if a permit for work described in the application is issued, I certify that the code official's authorized representative shall have the authority to enter all areas covered by such permit at any reasonable hour to enforce the provision of the code(s) applicable to such permit.

SIGNATURE OF APPLICANT	ADDRESS	DATE	PHONE
RESPONSIBLE PERSON IN CHARGE OF WORK, TITLE		DATE	PHON

**Job Summary Report**  
**Job ID: 2011-01-240-FAFS**

**Job Type:** Fire Alarm / Suppression  
**Job Description:** 51 Ingersoll Drive / 410 Riverside St Airgas  
**Job Year:** 2010  
**Building Job Status Code:** Initiate Plan Review  
**Pin Value:** 419  
**Tenant Name:**  
**Job Application Date:** Public Building Flag: N  
**Tenant Number:**  
**Estimated Value:** 6,000  
**Square Footage:**  
**Related Parties:** \* 410 RIVERSIDE ST LLC  
 Property Owner  
 Sprinkler Systems Inc - Scott Garland  
 FIRE ALARM INSTALLER

**Job Charges**

Fee Code Description	Charge Amount	Permit Charge Adjustment	Net Charge Amount	Payment Date	Receipt Number	Payment Amount	Payment Adjustment Amount	Net Payment Amount	Outstanding Balance

**Location ID: 34520**

**Location Details**

Alternate Id	Parcel Number	Census Tract	GIS X	GIS Y	GIS Z	GIS Reference	Longitude	Latitude
R17390	320	A 002 001	M				-70.328422	43.691175

Location Type	Subdivision Code	Subdivision Sub Code	Related Persons	Address(es)
				410 RIVERSIDE STREET WEST

Location Use Code	Variance Code	Use Zone Code	Fire Zone Code	Inside Outside Code	District Code	General Location Code	Inspection Area Code	Jurisdiction Code
WAREHOUSE & STORAGE	NOT APPLICABLE						DISTRICT 8	RIVERSIDE

**Structure Details**

**Structure:** Office/ Production & Distribution Airgas  
*warehouse / production & distribution of medical gases*

**Occupancy Type Code:**

Structure Type Code	Structure Status Type	Square Footage	Estimated Value	Address
Industrial Building	0			410 RIVERSIDE STREET WEST

**Longitude** Latitude GIS X GIS Y GIS Z GIS Reference

User Defined Property Value

**Permit #: FIRE SYS NWB-669**

**Permit Data**

**Job Summary Report**  
**Job ID: 2011-01-240-FAFS**

Report generated on Jan 11, 2011 11:40:08 AM

Location Id	Structure Description	Permit Status	Permit Description	Issue Date	Reissue Date	Expiration Date
34520	Office/ Production & Distribution Airgas	Initialized	install Fire Suppression System			

Inspection Id	Inspection Type	Inspection Result Status	Inspection Status Date	Scheduled Start Timestamp	Result Status Date	Final Inspection Flag
<b>Inspection Details</b>						

Fee Code Description	Charge Amount	Permit Charge Adjustment	Permit Charge Adj Remark	Payment Date	Receipt Number	Payment Amount	Payment Adj Amount	Payment Adj Comment
Job Valuation Fees	\$80.00							

PDF E-mail



# Fire Suppression System Permit

If you or the property owner owes real estate or property taxes or user charges on any property within the city, payment arrangements must be made before permits of any kind are accepted.

Installation address: 51 Ingersoll Dr. CBL: 320-A-2-

Exact location: (within structure) AirGas

Type of occupancy(s) (NFPA & ICC): EXTRA HAZARD GROUP 1

Building owner: AIRGAS

Managing Supervisor: Scott E. Garlowel License No: 278

Supervisor phone: 775-1521 E-mail: scottssi@maine.ff.com

Installing contractor: Sprinkler Systems, Inc. License No: 093

Contractor phone: 775-1521 E-mail: Krissi@maine.ff.com

The suppression work to be done will be: New:  Renovation:  Addition to existing system:

This is an amendment to an existing permit: Yes:  NO  Permit no: \_\_\_\_\_

NFPA Standard will this system is designed to: NFPA #13 Edition: 2007

\*Non-NFPA systems are not approved for use within the City of Portland.

Attach all design information and complete approved submittals as may be required by the State Fire Marshal's Office.

Contractor shall verify location and type of all FDCs shall be approved in writing by the Fire Prevention Bureau.

<p>COST OF WORK: <u>\$6,000</u></p> <p>PERMIT FEE: <u>\$80.00</u> (\$10 PER \$1,000 + \$30 FOR THE FIRST \$1,000)</p>
---

Download a new copy of this document from [www.portlandmaine.gov](http://www.portlandmaine.gov) for every submittal. Submit all information to the Building Inspections Department, 389 Congress Street, Room 315, Portland, Maine 04101.

Prior to acceptance of any fire protection system, a complete commissioning and acceptance test must be coordinated with all fire system contractors and the Fire Department, and proper documentation of such test(s) provided.

All installation(s) must comply with NFPA and the Fire Department Technical Standard(s).

Applicant signature: [Signature] Date: 12-22-10

RECEIVED  
JUN 10 2011  
Dept of Building Inspections  
City of Portland Maine

## **FIRE CONDITIONS**

1. Installation shall comply with City Code Chapter 10.
2. The Fire alarm and Sprinkler systems shall be reviewed by a licensed contractor[s] for code compliance. Compliance letters are
3. required.
4. Fire department connection type and location shall be approved in writing by fire prevention bureau.
5. System acceptance and commissioning must be coordinated with alarm and suppression system contractors and the Fire Department. Call 874-8703 to schedule.
6. Installation of a sprinkler or fire alarm system requires a Knox Box to be installed per city ordinance.
7. The Fire Department will require knox locking caps on all Fire Department Connections on the exterior of the building.
8. Application requires State Fire Marshal approval.
9. The sprinkler system shall be installed in accordance with NFPA 13.
10. checked at the end of each day to insure the system has been placed back in service.
11. Sprinkler protection shall be maintained. Where the system is to be shut down for maintenance or repair, the system shall be





State of Maine  
Department of Public Safety



Fire Sprinkler System Permit

# 9345

Airgas

Located at: 51 Ingersoll Dr.  
In the Town of: Portland  
Occupancy/Use: Warehouse  
Type of System: NFPA 13

Permission is hereby given to:

**Sprinkler Systems, Inc.**

PO Box 1285  
Lewiston, ME 042431285  
Contractor License # 93

to begin installation according to plans submittal approved by the Office of State Fire Marshal. The submittal is filed under log # 2101449, and no departure from the application submittal shall be made without prior approval in writing. This permit is issued under the provisions of Title 32, Chapter 20. Nothing herein shall excuse the holder of this permit from failure to comply with local ordinances, zoning laws, or other pertinent legal restrictions. This permit shall be displayed at the construction site or be made readily available.

This permit was issued on 12/31/2010 for a fee paid of \$100.00

*This permit will expire at midnight on Wednesday, June 29, 2011*

The expiration date applies only if the installation has not begun by that date and no permission has been granted to extend the date. Once installation begins, then the permit is valid for however long it takes to complete the installation, assuming that the work is fairly continuous.

Anne H. Jordan  
Commissioner


*The type of Fire Department Connection and its location is to be according to the Local Fire Department*

Within 30 days of the completion of a new fire sprinkler system or an addition to an existing fire sprinkler system, a fire sprinkler system contractor shall provide to the Licensing and Inspections Unit a copy of this permit signed and dated by the certified Responsible Managing Supervisor representing that the fire sprinkler system has been installed according to specifications of the approved plan to the best of the supervisor's knowledge, information, and belief. This requirement is part of the sprinkler law, and neglect of this duty is grounds to not renew the contractor's license to do work in the State of Maine. All renewed sprinkler licenses are good for two years and expire on a June 30th.

Job completed, tested and verified on date of \_\_\_\_\_

RMS for this job: Garland Scott E.

RMS Signature: \_\_\_\_\_



... Fire Protection by Computer Design

Sprinkler Systems, Inc.  
2-4 Avon Street  
P.O. Box 1285  
Lewiston, Maine 04240  
207-782-0104

Job Name : Air Gas  
Building : WAREHOUSE  
Location : 51 INGERSOLL DR., PORTLAND, ME 04103  
System : 1 OF 1  
Contract : 10089  
Data File : AIRGAS1(B).WXF

Hydraulic Design Information Sheet

Name - AIRGAS Date - 12-15-2010  
 Location - 51 INGERSOLL DR., PORTLAND, ME 04103  
 Building - WAREHOUSE System No. - 1 OF 1  
 Contractor - OWNER Contract No. - 10089  
 Calculated By - KRISTOPHER J. FISH Drawing No. - 1 OF 1  
 Construction: ( ) Combustible (X) Non-Combustible Ceiling Height - OBJ  
 Occupancy - INDUSTRIAL WAREHOUSE

S (X) NFPA 13 ( ) Lt. Haz. Ord.Haz.Gp. ( ) 1 ( ) 2 ( ) 3 (X) Ex.Haz.  
 Y ( ) NFPA 231 ( ) NFPA 231C ( ) Figure Curve

S Other

T Specific Ruling

Made By

Date

M	Area of Sprinkler Operation	- 2000 SF	System Type	Sprinkler/Nozzle
	Density	- .3	(X) Wet	Make RELIABLE
D	Area Per Sprinkler	- 90	( ) Dry	Model G
E	Elevation at Highest Outlet	- 69.750	( ) Deluge	Size 17/32" X 3/4"
S	Hose Allowance - Inside	-	( ) Preaction	K-Factor 8.0
I	Rack Sprinkler Allowance	-	( ) Other	Temp.Rat.286 DEG
G	Hose Allowance - Outside	- 500 GPM	AT X1	

N

Note DESIGN AREA #1 - WAREHOUSE

Calculation Flow Required - 847.13 Press Required - 31.072 AT BASE OF RISER  
 Summary C-Factor Used: 120 Overhead 140 Underground

W	Water Flow Test:	Pump Data:	Tank or Reservoir:
A	Date of Test - 7-27-2005		Cap. -
T	Time of Test -	Rated Cap.-	Elev.-
E	Static Press - 82	@ Press -	
R	Residual Press - 80	Elev. -	Well
	Flow - 2576		Proof Flow
S	Elevation - 62		

U

P Location - WATER WAS FLOWED FROM HYD 4305 ON RIVERSIDE ST FROM A 12"  
 P CIRCULATING CITY MAIN. TEST GUAGES READ FROM HYD 1541 ON RIVERSIDE ST.  
 L Source of Information - PORTLAND WATER DISTRICT

Y

C	Commodity	Class	Location
O	Storage Ht.	Area	Aisle W.
M	Storage Method:	Solid Piled	% Palletized % Rack
M	( ) Single Row	( ) Conven. Pallet	( ) Auto. Storage ( ) Encap.
S	( ) Double Row	( ) Slave Pallet	( ) Solid Shelf ( ) Non
T	( ) Mult. Row		( ) Open Shelf

O

R K Flue Spacing Clearance:Storage to Ceiling  
 A Longitudinal Transverse

G

E Horizontal Barriers Provided:

# Fittings Used Summary

Sprinkler Systems, Inc.  
Air Gas

Fitting Legend Abbrev. Name	1/2	3/4	1	1 1/4	1 1/2	2	2 1/2	3	3 1/2	4	5	6	8	10	12	14	16	18	20	24
E 90' Standard Elbow	2	2	2	3	4	5	6	7	8	10	12	14	18	22	27	35	40	45	50	61
G Generic Gate Valve	0	0	0	0	0	1	1	1	1	2	2	3	4	5	6	7	8	10	11	13
T 90' Flow Thru Tee	3	4	5	6	8	10	12	15	17	20	25	30	35	50	60	71	81	91	101	121
Z Generic Flow Switch	2	2	2	3	4	5	6	7	8	10	12	14	18	22	27	35	40	45	50	61
Zac Ames 2000SS	Fitting generates a Fixed Loss Based on Flow																			

## Units Summary

Diameter Units Inches  
 Length Units Feet  
 Flow Units US Gallons per Minute  
 Pressure Units Pounds per Square Inch

Pressure / Flow Summary - STANDARD

Sprinkler Systems, Inc.  
Air Gas

Page 4  
Date 12-15-2010

Node No.	Elevation	K-Fact	Pt Actual	Pn	Flow Actual	Density	Area	Press Req.
1	69.75	8	13.32	na	29.19	0.3	70.553	7.0
2	69.75	8	13.36	na	29.24	0.3	90	11.391
3	69.75	8	13.62	na	29.52	0.3	90	11.391
4	69.75	8	14.16	na	30.1	0.3	90	11.391
5	69.75	8	15.0	na	30.98	0.3	90	11.391
6	69.75	8	15.08	na	31.07	0.3	90	11.391
7	69.75	8	13.39	na	29.27	0.3	70.553	7.0
8	69.75	8	13.43	na	29.32	0.3	90	11.391
9	69.75	8	13.69	na	29.6	0.3	90	11.391
10	69.75	8	14.23	na	30.18	0.3	90	11.391
11	69.75	8	15.08	na	31.07	0.3	90	11.391
12	69.75	8	15.16	na	31.15	0.3	90	11.391
13	69.75	8	13.64	na	29.55	0.3	70.553	7.0
14	69.75	8	13.69	na	29.6	0.3	90	11.391
15	69.75	8	13.95	na	29.88	0.3	90	11.391
16	69.75	8	14.51	na	30.47	0.3	90	11.391
17	69.75	8	15.37	na	31.36	0.3	90	11.391
18	69.75	8	15.45	na	31.44	0.3	90	11.391
19	69.75	8	11.35	na	26.95	0.3	70.553	7.0
20	69.75	8	11.39	na	27.0	0.3	90	11.391
21	69.75	8	11.61	na	27.26	0.3	90	11.391
22	69.75	8	12.65	na	28.46	0.3	70.553	7.0
23	69.75	8	14.6	na	30.57	0.3	90	11.391
24	69.75	8	15.98	na	31.98	0.3	90	11.391
25	69.75	8	16.06	na	32.06	0.3	90	11.391
26	69.75	8	17.08	na	33.06	0.3	90	11.391
27	69.75	8	17.17	na	33.14	0.3	90	11.391
28	69.75	8	17.69	na	33.65	0.3	90	11.391
A	69.75		15.68	na				
B	69.75		15.76	na				
C	69.75		16.06	na				
D	69.75		16.69	na				
E	69.75		17.84	na				
F	69.75		24.34	na				
G	66.25		30.16	na				
RT	66.25		31.07	na				
RB	48.25		43.54	na				
X1	59.0		61.21	na	500.0			
TEST	62.0		61.54	na				

The maximum velocity is 19.07 and it occurs in the pipe between nodes E and F

Final Calculations - Hazen-Williams

Sprinkler Systems, Inc.  
Air Gas

Page 5  
Date 12-15-2010

Hyd. Ref. Point	Qa Qt	Dia. "C" Pf/Ft	Fitting or Eqv. Ln.	Pipe Ftng's Total	Pt Pe Pf	Pt Pv Pn	*****	Notes	*****
1	29.19	2.157	0.0	6.000	13.316			K Factor = 8.00	
to		120	0.0	0.0	0.0				
2	29.19	0.0078	0.0	6.000	0.047			Vel = 2.56	
2	29.25	2.157	0.0	9.000	13.363			K Factor = 8.00	
to		120	0.0	0.0	0.0				
3	58.44	0.0282	0.0	9.000	0.254			Vel = 5.13	
3	29.52	2.157	0.0	9.000	13.617			K Factor = 8.00	
to		120	0.0	0.0	0.0				
4	87.96	0.0602	0.0	9.000	0.542			Vel = 7.72	
4	30.10	2.157	1T 12.307	2.333	14.159			K Factor = 8.00	
to		120	0.0	12.307	0.0				
A	118.06	0.1038	0.0	14.640	1.520			Vel = 10.37	
	0.0								
	118.06				15.679			K Factor = 29.82	
5	30.98	2.157	0.0	9.000	15.001			K Factor = 8.00	
to		120	0.0	0.0	0.0				
6	30.98	0.0088	0.0	9.000	0.079			Vel = 2.72	
6	31.07	2.157	1T 12.307	6.667	15.080			K Factor = 8.00	
to		120	0.0	12.307	0.0				
A	62.05	0.0316	0.0	18.974	0.599			Vel = 5.45	
	0.0								
	62.05				15.679			K Factor = 15.67	
7	29.27	2.157	0.0	6.000	13.387			K Factor = 8.00	
to		120	0.0	0.0	0.0				
8	29.27	0.0078	0.0	6.000	0.047			Vel = 2.57	
8	29.32	2.157	0.0	9.000	13.434			K Factor = 8.00	
to		120	0.0	0.0	0.0				
9	58.59	0.0284	0.0	9.000	0.256			Vel = 5.14	
9	29.60	2.157	0.0	9.000	13.690			K Factor = 8.00	
to		120	0.0	0.0	0.0				
10	88.19	0.0604	0.0	9.000	0.544			Vel = 7.74	
10	30.18	2.157	1T 12.307	2.333	14.234			K Factor = 8.00	
to		120	0.0	12.307	0.0				
B	118.37	0.1043	0.0	14.640	1.527			Vel = 10.39	
	0.0								
	118.37				15.761			K Factor = 29.82	
11	31.07	2.157	0.0	9.000	15.080			K Factor = 8.00	
to		120	0.0	0.0	0.0				
12	31.07	0.0088	0.0	9.000	0.079			Vel = 2.73	
12	31.14	2.157	1T 12.307	6.667	15.159			K Factor = 8.00	
to		120	0.0	12.307	0.0				
B	62.21	0.0317	0.0	18.974	0.602			Vel = 5.46	

Final Calculations - Standard

Sprinkler Systems, Inc.  
Air Gas

Page 6  
Date 12-15-2010

Hyd. Ref. Point	Qa Qt	Dia. "C" Pf/Ft	Fitting or Eqv. Ln.	Pipe Ftng's Total	Pt Pe Pf	Pt Pv Pn	*****	Notes	*****
	0.0 62.21					15.761		K Factor = 15.67	
13 to 14	29.55	2.157 120	0.0 0.0	6.000 0.0	13.643 0.0			K Factor = 8.00	
14 to 15	29.55	0.0080	0.0	6.000	0.048			Vel = 2.59	
14 to 15	29.60	2.157 120	0.0 0.0	9.000 0.0	13.691 0.0			K Factor = 8.00	
15 to 16	59.15	0.0289	0.0	9.000	0.260			Vel = 5.19	
15 to 16	29.88	2.157 120	0.0 0.0	9.000 0.0	13.951 0.0			K Factor = 8.00	
16 to C	89.03	0.0616	0.0	9.000	0.554			Vel = 7.82	
16 to C	30.47	2.157 120	1T 12.307 0.0	2.333 12.307	14.505 0.0			K Factor = 8.00	
	119.5	0.1061	0.0	14.640	1.554			Vel = 10.49	
	0.0 119.50					16.059		K Factor = 29.82	
17 to 18	31.36	2.157 120	0.0 0.0	9.000 0.0	15.366 0.0			K Factor = 8.00	
18 to C	31.36	0.0090	0.0	9.000	0.081			Vel = 2.75	
18 to C	31.44	2.157 120	1T 12.307 0.0	6.667 12.307	15.447 0.0			K Factor = 8.00	
	62.8	0.0323	0.0	18.974	0.612			Vel = 5.51	
	0.0 62.80					16.059		K Factor = 15.67	
19 to 20	26.95	2.157 120	0.0 0.0	6.000 0.0	11.350 0.0			K Factor = 8.00	
20 to 21	26.95	0.0068	0.0	6.000	0.041			Vel = 2.37	
20 to 21	27.00	2.157 120	0.0 0.0	9.000 0.0	11.391 0.0			K Factor = 8.00	
21 to 22	53.95	0.0243	0.0	9.000	0.219			Vel = 4.74	
21 to 22	27.26	2.157 120	2E 12.307 0.0	7.750 12.307	11.610 0.0			K Factor = 8.00	
22 to 23	81.21	0.0520	0.0	20.057	1.042			Vel = 7.13	
22 to 23	28.46	2.157 120	2E 12.307 0.0	9.250 12.307	12.652 0.0			K Factor = 8.00	
23 to D	109.67	0.0906	0.0	21.557	1.953			Vel = 9.63	
23 to D	30.57	2.157 120	1T 12.307 0.0	2.333 12.307	14.605 0.0			K Factor = 8.00	
	140.24	0.1427	0.0	14.640	2.089			Vel = 12.31	
	0.0 140.24					16.694		K Factor = 34.32	

Final Calculations - Standard

Sprinkler Systems, Inc.  
Air Gas

Page 7  
Date 12-15-2010

Hyd. Ref. Point	Qa Qt	Dia. "C" Pf/Ft	Fitting or Eqv. Ln.	Pipe Ftng's Total	Pt Pe Pf	Pt Pv Pn	*****	Notes	*****
24 to 25	31.98	2.157 120	0.0 0.0	9.000 0.0	15.976 0.0			K Factor = 8.00	
25 to D	31.98	0.0092	0.0	9.000	0.083			Vel = 2.81	
25 to D	32.06	2.157 120	1T 12.307 0.0	6.667 12.307	16.059 0.0			K Factor = 8.00	
	64.04	0.0335	0.0	18.974	0.635			Vel = 5.62	
	0.0 64.04				16.694			K Factor = 15.67	
26 to 27	33.06	2.157 120	0.0 0.0	9.000 0.0	17.077 0.0			K Factor = 8.00	
27 to E	33.06	0.0098	0.0	9.000	0.088			Vel = 2.90	
27 to E	33.14	2.157 120	1T 12.307 0.0	6.667 12.307	17.165 0.0			K Factor = 8.00	
	66.2	0.0356	0.0	18.974	0.676			Vel = 5.81	
	0.0 66.20				17.841			K Factor = 15.67	
28 to E	33.65	2.157 120	1T 12.307 0.0	2.333 12.307	17.692 0.0			K Factor = 8.00	
	33.65	0.0102	0.0	14.640	0.149			Vel = 2.95	
	0.0 33.65				17.841			K Factor = 7.97	
A to B	180.11	4.26 120	0.0 0.0	10.000 0.0	15.679 0.0				
B to C	180.11	0.0082	0.0	10.000	0.082			Vel = 4.05	
B to C	180.59	4.26 120	0.0 0.0	10.000 0.0	15.761 0.0				
C to D	360.7	0.0298	0.0	10.000	0.298			Vel = 8.12	
C to D	182.30	4.26 120	0.0 0.0	10.000 0.0	16.059 0.0				
D to E	543.0	0.0635	0.0	10.000	0.635			Vel = 12.22	
D to E	204.28	4.26 120	0.0 0.0	10.000 0.0	16.694 0.0				
E to F	747.28	0.1147	0.0	10.000	1.147			Vel = 16.82	
E to F	99.85	4.26 120	1E 13.167 0.0	31.750 13.167	17.841 0.0				
F to G	847.13	0.1446	0.0	44.917	6.494			Vel = 19.07	
F to G	0.0	4.26 120	1T 26.334 0.0	3.500 26.334	24.335 1.516				
G to RT	847.13	0.1446	0.0	29.834	4.314			Vel = 19.07	
G to RT	0.0	6.357 120	1T 37.72 0.0	6.333 37.720	30.165 0.0				
	847.13	0.0206	0.0	44.053	0.907			Vel = 8.56	



Final Calculations - Standard

Sprinkler Systems, Inc.  
Air Gas

Page 8  
Date 12-15-2010


Hyd. Ref. Point	Qa  Qt	Dia. "C" Pf/Ft	Fitting or Eqv. Ln.	Pipe Ftng's Total	Pt Pe Pf	Pt Pv Pn	*****	Notes	*****
RT	0.0	6.357	1Z	17.603	17.833	31.072			
to		120	1Zac	0.0	17.603	11.739			
RB	847.13	0.0206		0.0	35.436	0.729		* Fixed loss = 3.944	
								Vel = 8.56	
RB	0.0	6.16	2E	40.168	1150.000	43.540			
to		140	1T	43.037	87.509	-4.656			
X1	847.13	0.0180	1G	4.304	1237.509	22.326		Vel = 9.12	
X1	500.00	12.34		0.0	1130.000	61.210		Qa = 500	
to		140		0.0	0.0	-1.299			
TEST	1347.13	0.0014		0.0	1130.000	1.631		Vel = 3.61	
	0.0								
	1347.13					61.542		K Factor = 171.72	

# Water Supply Curve (C)

Sprinkler Systems, Inc.  
Air Gas


City Water Supply:  
C1 - Static Pressure : 82  
C2 - Residual Pressure: 80  
C2 - Residual Flow : 2576

Demand:  
D1 - Elevation : 3.357  
D2 - System Flow : 847.13  
D2 - System Pressure : 61.542  
Hose (Adj City) : 500  
Hose (Demand) : 1347.13  
D3 - System Demand : 19.855  
Safety Margin





PDF-E-Mail



... Fire Protection by Computer Design

Sprinkler Systems, Inc.  
2-4 Avon Street  
P.O. Box 1285  
Lewiston, Maine 04240  
207-782-0104

Job Name : Air Gas  
Building : WAREHOUSE  
Location : 51 INGERSOLL DR., PORTLAND, ME 04103  
System : 1 OF 1  
Contract : 10089  
Data File : AIRGAS1(B).WXF

Hydraulic Design Information Sheet

Name - AIRGAS  
Location - 51 INGERSOLL DR., PORTLAND, ME 04103  
Building - WAREHOUSE  
Contractor - OWNER  
Calculated By - KRISTOPHER J. FISH  
Construction: ( ) Combustible (X) Non-Combustible  
Occupancy - INDUSTRIAL WAREHOUSE

Date - 12-15-2010  
System No. - 1 OF 1  
Contract No. - 10089  
Drawing No. - 1 OF 1  
Ceiling Height - OBJ

S (X) NFPA 13 ( ) Lt. Haz. Ord.Haz.Gp. ( ) 1 ( ) 2 ( ) 3 (X) Ex.Haz.  
Y ( ) NFPA 231 ( ) NFPA 231C ( ) Figure Curve  
S Other

T Specific Ruling Made By Date

M	Area of Sprinkler Operation - 2000 SF	System Type	Sprinkler/Nozzle
	Density - .3	(X) Wet	Make RELIABLE
D	Area Per Sprinkler - 90	( ) Dry	Model G
E	Elevation at Highest Outlet - 69.750	( ) Deluge	Size 17/32" X 3/4"
S	Hose Allowance - Inside -	( ) Preaction	K-Factor 8.0
I	Rack Sprinkler Allowance -	( ) Other	Temp.Rat.286 DEG
G	Hose Allowance - Outside - 500 GPM	AT X1	

Note DESIGN AREA #1 - WAREHOUSE

Calculation Flow Required - 847.13 Press Required - 31.072 AT BASE OF RISER  
Summary C-Factor Used: 120 Overhead 140 Underground

W	Water Flow Test:	Pump Data:	Tank or Reservoir:
A	Date of Test - 7-27-2005		Cap. -
T	Time of Test -	Rated Cap.-	Elev.-
E	Static Press - 82	@ Press -	
R	Residual Press - 80	Elev. -	Well
	Flow - 2576		Proof Flow
S	Elevation - 62		

U Location - WATER WAS FLOWED FROM HYD 4305 ON RIVERSIDE ST FROM A 12"  
P CIRCULATING CITY MAIN. TEST GUAGES READ FROM HYD 1541 ON RIVERSIDE ST.  
L Source of Information - PORTLAND WATER DISTRICT  
Y

C	Commodity	Class	Location
O	Storage Ht.	Area	Aisle W.
M	Storage Method:	Solid Piled %	Palletized % Rack
	( ) Single Row	( ) Conven. Pallet	( ) Auto. Storage ( ) Encap.
S R	( ) Double Row	( ) Slave Pallet	( ) Solid Shelf ( ) Non
T A	( ) Mult. Row		( ) Open Shelf

R K Flue Spacing Clearance:Storage to Ceiling  
A Longitudinal Transverse

E Horizontal Barriers Provided:

# Fittings Used Summary

Sprinkler Systems, Inc.  
Air Gas

Fitting Legend Abbrev. Name	1/2	3/4	1	1 1/4	1 1/2	2	2 1/2	3	3 1/2	4	5	6	8	10	12	14	16	18	20	24
E 90' Standard Elbow	2	2	2	3	4	5	6	7	8	10	12	14	18	22	27	35	40	45	50	61
G Generic Gate Valve	0	0	0	0	0	1	1	1	1	2	2	3	4	5	6	7	8	10	11	13
T 90' Flow Thru Tee	3	4	5	6	8	10	12	15	17	20	25	30	35	50	60	71	81	91	101	121
Z Generic Flow Switch	2	2	2	3	4	5	6	7	8	10	12	14	18	22	27	35	40	45	50	61
Zac Ames 2000SS	Fitting generates a Fixed Loss Based on Flow																			

## Units Summary

- Diameter Units Inches
- Length Units Feet
- Flow Units US Gallons per Minute
- Pressure Units Pounds per Square Inch

Pressure / Flow Summary - STANDARD

Sprinkler Systems, Inc.  
Air Gas

Page 4  
Date 12-15-2010

Node No.	Elevation	K-Fact	Pt Actual	Pn	Flow Actual	Density	Area	Press Req.
1	69.75	8	13.32	na	29.19	0.3	70.553	7.0
2	69.75	8	13.36	na	29.24	0.3	90	11.391
3	69.75	8	13.62	na	29.52	0.3	90	11.391
4	69.75	8	14.16	na	30.1	0.3	90	11.391
5	69.75	8	15.0	na	30.98	0.3	90	11.391
6	69.75	8	15.08	na	31.07	0.3	90	11.391
7	69.75	8	13.39	na	29.27	0.3	70.553	7.0
8	69.75	8	13.43	na	29.32	0.3	90	11.391
9	69.75	8	13.69	na	29.6	0.3	90	11.391
10	69.75	8	14.23	na	30.18	0.3	90	11.391
11	69.75	8	15.08	na	31.07	0.3	90	11.391
12	69.75	8	15.16	na	31.15	0.3	90	11.391
13	69.75	8	13.64	na	29.55	0.3	70.553	7.0
14	69.75	8	13.69	na	29.6	0.3	90	11.391
15	69.75	8	13.95	na	29.88	0.3	90	11.391
16	69.75	8	14.51	na	30.47	0.3	90	11.391
17	69.75	8	15.37	na	31.36	0.3	90	11.391
18	69.75	8	15.45	na	31.44	0.3	90	11.391
19	69.75	8	11.35	na	26.95	0.3	70.553	7.0
20	69.75	8	11.39	na	27.0	0.3	90	11.391
21	69.75	8	11.61	na	27.26	0.3	90	11.391
22	69.75	8	12.65	na	28.46	0.3	70.553	7.0
23	69.75	8	14.6	na	30.57	0.3	90	11.391
24	69.75	8	15.98	na	31.98	0.3	90	11.391
25	69.75	8	16.06	na	32.06	0.3	90	11.391
26	69.75	8	17.08	na	33.06	0.3	90	11.391
27	69.75	8	17.17	na	33.14	0.3	90	11.391
28	69.75	8	17.69	na	33.65	0.3	90	11.391
A	69.75		15.68	na				
B	69.75		15.76	na				
C	69.75		16.06	na				
D	69.75		16.69	na				
E	69.75		17.84	na				
F	69.75		24.34	na				
G	66.25		30.16	na				
RT	66.25		31.07	na				
RB	48.25		43.54	na				
X1	59.0		61.21	na	500.0			
TEST	62.0		61.54	na				

The maximum velocity is 19.07 and it occurs in the pipe between nodes E and F

Final Calculations - Hazen-Williams

Sprinkler Systems, Inc.  
Air Gas

Page 5  
Date 12-15-2010

Hyd. Ref. Point	Qa Qt	Dia. "C" Pf/Ft	Fitting or Eqv. Ln.	Pipe Ftng's Total	Pt Pe Pf	Pt Pv Pn	*****	Notes	*****
1	29.19	2.157	0.0	6.000	13.316			K Factor = 8.00	
to		120	0.0	0.0	0.0				
2	29.19	0.0078	0.0	6.000	0.047			Vel = 2.56	
2	29.25	2.157	0.0	9.000	13.363			K Factor = 8.00	
to		120	0.0	0.0	0.0				
3	58.44	0.0282	0.0	9.000	0.254			Vel = 5.13	
3	29.52	2.157	0.0	9.000	13.617			K Factor = 8.00	
to		120	0.0	0.0	0.0				
4	87.96	0.0602	0.0	9.000	0.542			Vel = 7.72	
4	30.10	2.157	1T 12.307	2.333	14.159			K Factor = 8.00	
to		120	0.0	12.307	0.0				
A	118.06	0.1038	0.0	14.640	1.520			Vel = 10.37	
	0.0								
	118.06				15.679			K Factor = 29.82	
5	30.98	2.157	0.0	9.000	15.001			K Factor = 8.00	
to		120	0.0	0.0	0.0				
6	30.98	0.0088	0.0	9.000	0.079			Vel = 2.72	
6	31.07	2.157	1T 12.307	6.667	15.080			K Factor = 8.00	
to		120	0.0	12.307	0.0				
A	62.05	0.0316	0.0	18.974	0.599			Vel = 5.45	
	0.0								
	62.05				15.679			K Factor = 15.67	
7	29.27	2.157	0.0	6.000	13.387			K Factor = 8.00	
to		120	0.0	0.0	0.0				
8	29.27	0.0078	0.0	6.000	0.047			Vel = 2.57	
8	29.32	2.157	0.0	9.000	13.434			K Factor = 8.00	
to		120	0.0	0.0	0.0				
9	58.59	0.0284	0.0	9.000	0.256			Vel = 5.14	
9	29.60	2.157	0.0	9.000	13.690			K Factor = 8.00	
to		120	0.0	0.0	0.0				
10	88.19	0.0604	0.0	9.000	0.544			Vel = 7.74	
10	30.18	2.157	1T 12.307	2.333	14.234			K Factor = 8.00	
to		120	0.0	12.307	0.0				
B	118.37	0.1043	0.0	14.640	1.527			Vel = 10.39	
	0.0								
	118.37				15.761			K Factor = 29.82	
11	31.07	2.157	0.0	9.000	15.080			K Factor = 8.00	
to		120	0.0	0.0	0.0				
12	31.07	0.0088	0.0	9.000	0.079			Vel = 2.73	
12	31.14	2.157	1T 12.307	6.667	15.159			K Factor = 8.00	
to		120	0.0	12.307	0.0				
B	62.21	0.0317	0.0	18.974	0.602			Vel = 5.46	



Final Calculations - Standard

Sprinkler Systems, Inc.  
Air Gas

Page 6  
Date 12-15-2010

Hyd. Ref. Point	Qa Qt	Dia. "C" Pf/Ft	Fitting or Eqv. Ln.	Pipe Ftng's Total	Pt Pe Pf	Pt Pv Pn	*****	Notes	*****
	0.0 62.21					15.761		K Factor = 15.67	
13 to 14	29.55	2.157 120	0.0 0.0	6.000 0.0	13.643 0.0			K Factor = 8.00	
14 to 15	29.55	0.0080	0.0	6.000	0.048			Vel = 2.59	
14 to 15	29.60	2.157 120	0.0 0.0	9.000 0.0	13.691 0.0			K Factor = 8.00	
15 to 16	59.15	0.0289	0.0	9.000	0.260			Vel = 5.19	
15 to 16	29.88	2.157 120	0.0 0.0	9.000 0.0	13.951 0.0			K Factor = 8.00	
16 to C	89.03	0.0616	0.0	9.000	0.554			Vel = 7.82	
16 to C	30.47	2.157 120	1T 12.307 0.0	2.333 12.307	14.505 0.0			K Factor = 8.00	
	119.5	0.1061	0.0	14.640	1.554			Vel = 10.49	
	0.0 119.50					16.059		K Factor = 29.82	
17 to 18	31.36	2.157 120	0.0 0.0	9.000 0.0	15.366 0.0			K Factor = 8.00	
18 to C	31.36	0.0090	0.0	9.000	0.081			Vel = 2.75	
18 to C	31.44	2.157 120	1T 12.307 0.0	6.667 12.307	15.447 0.0			K Factor = 8.00	
	62.8	0.0323	0.0	18.974	0.612			Vel = 5.51	
	0.0 62.80					16.059		K Factor = 15.67	
19 to 20	26.95	2.157 120	0.0 0.0	6.000 0.0	11.350 0.0			K Factor = 8.00	
20 to 21	26.95	0.0068	0.0	6.000	0.041			Vel = 2.37	
20 to 21	27.00	2.157 120	0.0 0.0	9.000 0.0	11.391 0.0			K Factor = 8.00	
21 to 22	53.95	0.0243	0.0	9.000	0.219			Vel = 4.74	
21 to 22	27.26	2.157 120	2E 12.307 0.0	7.750 12.307	11.610 0.0			K Factor = 8.00	
22 to 23	81.21	0.0520	0.0	20.057	1.042			Vel = 7.13	
22 to 23	28.46	2.157 120	2E 12.307 0.0	9.250 12.307	12.652 0.0			K Factor = 8.00	
23 to D	109.67	0.0906	0.0	21.557	1.953			Vel = 9.63	
23 to D	30.57	2.157 120	1T 12.307 0.0	2.333 12.307	14.605 0.0			K Factor = 8.00	
	140.24	0.1427	0.0	14.640	2.089			Vel = 12.31	
	0.0 140.24					16.694		K Factor = 34.32	

Final Calculations - Standard

Sprinkler Systems, Inc.  
Air Gas

Page 7  
Date 12-15-2010

Hyd. Ref. Point	Qa Qt	Dia. "C" Pf/Ft	Fitting or Eqv. Ln.	Pipe Ftng's Total	Pt Pe Pf	Pt Pv Pn	*****	Notes	*****
24 to 25	31.98	2.157 120	0.0	9.000	15.976			K Factor = 8.00	
	31.98	0.0092	0.0	9.000	0.083			Vel = 2.81	
25 to D	32.06	2.157 120	1T 12.307	6.667	16.059			K Factor = 8.00	
	64.04	0.0335	0.0	18.974	0.635			Vel = 5.62	
	0.0 64.04					16.694		K Factor = 15.67	
26 to 27	33.06	2.157 120	0.0	9.000	17.077			K Factor = 8.00	
	33.06	0.0098	0.0	9.000	0.088			Vel = 2.90	
27 to E	33.14	2.157 120	1T 12.307	6.667	17.165			K Factor = 8.00	
	66.2	0.0356	0.0	18.974	0.676			Vel = 5.81	
	0.0 66.20					17.841		K Factor = 15.67	
28 to E	33.65	2.157 120	1T 12.307	2.333	17.692			K Factor = 8.00	
	33.65	0.0102	0.0	14.640	0.149			Vel = 2.95	
	0.0 33.65					17.841		K Factor = 7.97	
A to B	180.11	4.26 120	0.0	10.000	15.679				
	180.11	0.0082	0.0	10.000	0.082			Vel = 4.05	
B to C	180.59	4.26 120	0.0	10.000	15.761				
	360.7	0.0298	0.0	10.000	0.298			Vel = 8.12	
C to D	182.30	4.26 120	0.0	10.000	16.059				
	543.0	0.0635	0.0	10.000	0.635			Vel = 12.22	
D to E	204.28	4.26 120	0.0	10.000	16.694				
	747.28	0.1147	0.0	10.000	1.147			Vel = 16.82	
E to F	99.85	4.26 120	1E 13.167	31.750	17.841				
	847.13	0.1446	0.0	44.917	6.494			Vel = 19.07	
F to G	0.0	4.26 120	1T 26.334	3.500	24.335				
	847.13	0.1446	0.0	29.834	4.314			Vel = 19.07	
G to RT	0.0	6.357 120	1T 37.72	6.333	30.165				
	847.13	0.0206	0.0	44.053	0.907			Vel = 8.56	

Hyd. Ref. Point	Qa Qt	Dia. "C" Pf/Ft	Fitting or Eqv. Ln.	Pipe Ftng's Total	Pt Pe Pf	Pt Pv Pn	*****	Notes	*****
RT to RB	0.0 847.13	6.357 120 0.0206	1Z 17.603 1Zac 0.0	17.833 17.603 35.436	31.072 11.739 0.729			* Fixed loss = 3.944 Vel = 8.56	
RB to X1	0.0 847.13	6.16 140 0.0180	2E 40.168 1T 43.037 1G 4.304	1150.000 87.509 1237.509	43.540 -4.656 22.326			Vel = 9.12	
X1 to TEST	500.00 1347.13	12.34 140 0.0014	0.0 0.0 0.0	1130.000 0.0 1130.000	61.210 -1.299 1.631			Qa = 500 Vel = 3.61	
	0.0 1347.13				61.542			K Factor = 171.72	

# Water Supply Curve (C)

Sprinkler Systems, Inc.  
Air Gas

City Water Supply:  
C1 - Static Pressure : 82  
C2 - Residual Pressure: 80  
C2 - Residual Flow : 2576

Demand:  
D1 - Elevation : 3.357  
D2 - System Flow : 847.13  
D2 - System Pressure : 61.542  
Hose (Adj City) : 500  
Hose (Demand) : 1347.13  
D3 - System Demand : 19.855  
Safety Margin

