

John Ready
PO Box 17652
Portland, ME 04112

10/31/16

Department of Permitting & Inspections
389 Congress Street
Portland, ME 04101

To whom it may concern,

The attached site plan illustrates four new modular walk in coolers and three new HVAC air conditioners. The walk in coolers are made of modular cooler panels that attach together like Legos and can be seen on the diagram spec sheet attached.

The HVAC equipment consists of three air conditioner compressors located outside the building which connect to three air handlers placed on the floor inside the building. The air handlers will distribute cold air through "Duct SOX" as seen in the attached pdf.

Please see application and supporting documents A-E which are included in this packet. Thank you for your consideration.

Sincerely,

John Ready