

Protection Professionals

325 U.S. Route 1
 Falmouth, ME 04105
 Ph 207-775-5755
 Fax 207-781-2064

Device List

No. 10077

List Date
11/4/2016

Bill To Name / Address
R.M. Pearson, Inc. Attn: Rob Pearson 232 Ossipee Trail Gorham, ME 04038

Job Site
Smith House 899 Riverside Street Portland, ME 04103

CHANGING THIS DEVICE LIST DOES NOT ALTER THE ORIGINAL ESTIMATE
Attach copy to Purchase Order for accounting

Estimate No.

Item	Description	Qty To Order	Qty Ordered
	This estimate is for a renovation of the existing fire alarm system. Currently it is an Ademco 128FB with fire alarm devices and security devices connected to the panel. The system appears to be hybrid with some conventional devices and some addressable devices. The pull stations are Ademco brand and the horn/strobes are System Sensor brand. The approximate number of existing pertinent devices are: 1. Smoke detectors: 5 on lower level, 12 on 2nd floor, 2 on 3rd floor 2. AVs: 3 on lower level, 6 on 2nd floor, 1 on 3rd floor 3. Heat detectors: 2 on 2nd floor 4. Pull stations: 3 on lower level, 2 on 2nd floor, 2 on 3rd floor 5. Elevator controls of some kind		
Bat 12-7	12V 7AH Batteries SEC-1075 (update batteries)	3	
ELOCK-FA	Lockout kit with tag	1	
5193SD	Addressable Smoke Detectors	5	
4101SN	Vista 128FB addressable relay module (delayed egress doors and possible elevator additions)	5	
4193SN	Honeywell Multiplex addressable module (heat detector, pull stations, and sprinkler devices)	15	
BK-5602	Heat Detector, 194 degree, Rate of Rise, one circuit (elevator shaft if necessary)	1	
BK-P2R	Horn/strobe, wall mount, red, 15cd, 15/75cd, 30cd, 75cd, 95cd, 110cd, or 115cd	2	
BK-SR	Strobe, red, 15cd, 15/75cd, 30cd, 75cd, 95cd, 110cd, or 115cd	8	
5140MPS-2	Pull station for Ademco panels	3	
SSU00672	Fire Document box 12 inches wide X 13.1 inches high X 2.25 inches deep, CAT 30 keyed	1	
8085	Ademco cam lock assembly; composed of N6277V1 (cam, lock) and N6277-1 (clip)	1	
PSN-64-3006436	Potter PSN-64 Conventional NAC Power Supply 6amp with 4 NACs, 3 amp Aux power, Two Class A circuits max	1	

Ordered By: _____

Date: _____

Received By: _____

Date: _____

Protection Professionals

325 U.S. Route 1
Falmouth, ME 04105
Ph 207-775-5755
Fax 207-781-2064

Device List

No. 10077

List Date
11/4/2016

Bill To Name / Address
R.M. Pearson, Inc. Attn: Rob Pearson 232 Ossipee Trail Gorham, ME 04038

Job Site
Smith House 899 Riverside Street Portland, ME 04103

CHANGING THIS DEVICE LIST DOES NOT ALTER THE ORIGINAL ESTIMATE
Attach copy to Purchase Order for accounting

Estimate No.

Item	Description	Qty To Order	Qty Ordered
Bat 12-7	12V 7AH Batteries SEC-1075 5.5% Maine Sales Tax	2	

Ordered By: _____

Date: _____

Received By: _____

Date: _____