Vi

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 12/14/16

Quantity	Part #	Description				
1	V250	Fire Panel (maximu				
1	6160CR	Annunicator				
	4208SN	Expander				
1		Sprinkler				
11		Pull Station				
	2W	Smoke				
	4W	Smoke				
		heat				
10		Addressable smoke				
		Motion				
		Duct Detector	0.001	0.001	0.000	0.000
		Duct smoke	0.001	0.001	0.000	0.000
		Duct relay	0.001	0.001	0.000	0.000
		Duct Remote	0.001	0.001	0.000	0.000
		Remote light	0.001	0.001	0.000	0.000
			0.000	0.000	0.000	0.000
1		NAC Trigger only	0.000	0.001	0.001	0.001
		NAC power maximum (24V)	0.000	3.400	0.000	0.000
		NAC power maximum (12V)		2.300	0.000	0.000
					0.000	0.000
					0.000	0.000
		Miscellaneous			0.000	0.000
TOTAL			0.499	6.552	0.478	0.658

	Hours	Standby current			Total
	24	0.4780			11.472
Minutes		Alarm current			
5	0.08333333	0.6580			0.055
		Battery Capacity			
	10%	11.5268			**12.680**