



STATE FIRE MARSHAL

CALIFORNIA DEPARTMENT OF FORESTRY and FIRE PROTECTION
OFFICE OF THE STATE FIRE MARSHAL

REGISTERED FLAME RESISTANT PRODUCT

Product:

PRECONTRAIN 702 BLACKOUT

Registration No.

F-14408

Product Marketed By:

FERRARI SA
BX54,38352 LA TOUR DU PIN
LA TOUR DU PIN, FRANCE

This product meets the minimum requirements of flame resistance established by the California State Fire Marshal for products identified in Section 13115, California Health and Safety Code.

The scope of the approved use of this product is provided in the current edition of the CALIFORNIA APPROVED LIST OF FLAME RETARDANT CHEMICALS AND FABRICS, GENERAL AND LIMITED APPLICATIONS CONCERNS published by the California State Fire Marshal.

Pat Sanchez


Deputy State Fire Marshal

FR-8



PRINTED ON REGENESIS® POST CONSUMER RECYCLED PAPER





DIVERSIFIED

TESTING LABORATORIES, INC.

"We Test Per Your Request"

336 WEST FRONT STREET
P.O. BOX 4004
BURLINGTON, NORTH CAROLINA 27215
Phone (336) 227-7710 • Fax (336) 227-1175

Ms. Catherine MERILLON
FERRARI SA
BP 54
38352 La Tour Du Pin Cedex
La Mure, France

Reference: Laboratory Test Report
Lab Identification No. 5349
Invoice No. 8270 (Attached)

Dear Ms. MERILLON:

One (1) fabric sample, identified as PRECONTRAINTE 702, was received and tested in accordance with the National Fire Prevention Association No. 701, "Flame Propagation of Textiles and Films, 1999 Edition, (Test 2, Large Scale)". The results are as follows:

<u>Specimen Number</u>	<u>Afterflame</u> <u>(seconds)</u>	<u>Residual Flame</u> <u>(seconds)</u>	<u>Char Length</u> <u>(inches)</u>
Single 1	0.0	0.0	10.0
Flat 2	0.0	0.0	11.0
Specimen 3	0.0	0.0	11.0
4	0.0	0.0	10.0
5	0.0	0.0	10.0
6	0.0	0.0	10.0
7	0.0	0.0	12.0
8	0.0	0.0	7.0
9	0.0	0.0	10.0
10	0.0	0.0	8.0

The sample submitted meets the minimum requirements of the above standard. The length of char on the individual single flat specimens shall not exceed 17.1 inches. Additionally, no specimen shall continue flaming for more than two (2) seconds after the test flame is removed and no residues shall fall to the floor of the test chamber and continue flaming for more than two (2) seconds at any time during the test.

If there are any questions or when we can be of further assistance, please let us know.

Sincerely,


Karen S. Matkins

KSM/mr
Attachment

OUR LETTERS AND REPORTS ARE FOR THE EXCLUSIVE USE OF THE CLIENT TO WHOM THEY ARE ADDRESSED. ANY COMMUNICATION TO OTHERS OR THE USE OF OUR COMPANY NAME MUST RECEIVE PRIOR APPROVAL. OUR TEST RESULTS APPLY ONLY TO THE SAMPLE TESTED AND ARE NOT NECESSARILY INDICATIVE OF THE QUALITIES OF APPARENTLY IDENTICAL OR SIMILAR PRODUCTS. SAMPLES NOT DESTROYED IN TESTING ARE RETAINED A MAXIMUM OF THIRTY DAYS. THE LETTERS, REPORTS OR NAME OF DIVERSIFIED TESTING LABORATORIES, INC. MAY NOT BE USED IN ADVERTISING TO THE GENERAL PUBLIC.



PRINTED ON REGENESIS® POST CONSUMER RECYCLED PAPER

