NEW PARTIAL SECOND FLOOR PLAN

NEW PARTIAL FIRST FLOOR PLAN

1 PARTIAL CODE COMPLIANCE PLANS 1/4" = 1'-0"

DOOR SCHEDULE

2

ABBREVIATIONS

AL	ALUMINUM	T	TEMPERED
E	EXISTING	TH	THERMAL INSULATED
EMHO	ELECTRO MAGNETIC HOLD OPENER	V.C.V	VINYL
GL	GLASS	W	WIRE
HM	HOLLOW METAL	WD	WOOD
INSUL	INSULATED	W/	WITH
SS	STAINLESS STEEL		

DOORS										FRAMES					THRESHOLDS	
NO.	TYPE	SIZE (W X H)	THK	INSUL	HDWE	FR	GLASS TYPE	GLASS SIZE	REMARKS	TYPE	FR	PROFILE	DETAILS HEAD	DETAILS JAMB	MATERIAL	DETAILS SILL	DETAILS PIN
101	A	6070 PR	1 3/4"	YES	HW-1	NO	T/TH	FULL		A	NO	T-BREAK	4-A4.1	5-A5.1	ALUM	6-A4.1	-
102	A	6070 PR	1 3/4"	YES	HW-1	NO	T/TH	FULL		A	NO	T-BREAK	4-A4.1	5-A5.1	ALUM	6-A4.1	-
103	A	3070	1 3/4"	YES	HW-2	NO	T/TH	FULL		D	NO	T-BREAK	4-A4.1	5-A5.1	ALUM	6-A4.1	-
104	D	3070	1 3/4"	NO	HW-3	1 HR	1 HR	24X30		C	1 HR	DW	1-A4.1	1-A4.1	ALUM	2-A4.1	-
~~105~~	~~C~~	~~3070~~	~~1 3/4"~~	~~NO~~	~~HW-4~~	~~NO~~	~~NONE~~	~~NONE~~	~~NOT USED~~	~~C~~	~~NO~~	~~DW~~	~~1-A4.1~~	~~1-A4.1~~	~~NONE~~		~~GONG~~
106	C	3070	1 3/4"	NO	HW-5	NO	NONE	NONE		C	NO	DW	1-A4.1	1-A4.1	NONE	-	GONG
107	C	3070	1 3/4"	NO	HW-5	NO	NONE	NONE		C	NO	DW	1-A4.1	1-A4.1	NONE	-	GONG
108	C	3070	1 3/4"	NO	EXIST'G *	1 HR	NONE	NONE	* REUSE @ REMOVED DOOR	C	1 HR	DW	1-A4.1	1-A4.1	NONE	-	GONG
~~108~~	~~C~~	~~3070~~	~~1 3/4"~~	~~NO~~	~~HW-8~~	~~NO~~	~~NONE~~	~~NONE~~		~~C~~	~~NO~~	~~DW~~	~~1-A4.1~~	~~1-A4.1~~	~~NONE~~	~~-~~	
~~201~~	~~C~~	~~3070~~	~~1 3/4"~~	~~NO~~	~~HW-6~~	~~1 HR~~	~~NONE~~	~~NONE~~		~~C~~	~~1 HR~~	~~DW~~	~~1-A4.1~~	~~1-A4.1~~	~~ALUM~~	~~2-A4.1~~	~~-~~
202	C	3070	1 3/4"	NO	HW-7	NO	NONE	NONE		C	NO	DW	1-A4.1	1-A4.1	NONE	-	-
E/R	E	E	E	E	E	E	E	E	SEE PLAN	E	E	E	E	E	E	E	E

HW-1 EXTERIOR PAIR DOORS
- 6 BUTTS
- 2 CLOSERS
- 2 EXIT DEVICES WITH EXTERIOR PULLS & CONCEALED RODS
- 1 THRESHOLD
- 2 DOOR BOTTOMS
- 1 WEATHERSTRIPPING JAMB/HEAD SET

HW-2 EXTERIOR SINGLE DOOR
- 3 BUTTS
- 1 CLOSERS
- 1 EXIT DEVICES WITH EXTERIOR PULL
- 1 THRESHOLD
- 1 DOOR BOTTOM
- 1 WEATHERSTRIPPING JAMB/HEAD SET

HW-3 INTERIOR SINGLE RATED DOOR
- 3 BUTTS
- 1 CLOSERS
- 1 EXIT DEVICES WITH PULL
- 1 THRESHOLD
- 1 DOOR BOTTOM
- 1 WEATHERSTRIPPING JAMB/HEAD SET

HW-4 INTERIOR SINGLE DOOR
- 3 BUTTS
- 1 LEVERLOCKSET - STORE ROOM FUNCTION
- 2 FRAME SILENCERS

HW-5 INTERIOR SINGLE DOOR
- 3 BUTTS
- 1 CLOSER
- 1 PUSH PLATE WITH PULL
- 2 FRAME SILENCERS

HW-6 INTERIOR SINGLE RATED DOOR
- 3 BUTTS
- 1 CLOSER
- 1 LEVER LOCKSET - OFFICE FUNCTION
- 2 FRAME SILENCERS

HW-7 INTERIOR SINGLE DOOR
- 3 BUTTS
- 1 LEVER LOCKSET - OFFICE FUNCTION
- 2 FRAME SILENCERS
- 1 DOOR STOP

HW-8 INTERIOR SINGLE DOOR
- 3 BUTTS
- 1 LEVER LATCHSET - PASSAGE FUNCTION
- 2 FRAME SILENCERS
- 1 DOOR STOP

HARDWARE SETS NO SCALE

FINISH SCHEDULE

ABBREVIATIONS

C	CARPET	FRP	FIBERGLASS REINFORCED PANELS	QT	QUARRY TILE
CI	CONCRETE W/ HARDENER	FV	FIELD VERIFY	SS	STAINLESS STEEL
CMU	CONCRETE MASONRY UNIT	GL	GLASS	VBS	VINYL STRAIGHT BASE
CT	CERAMIC TILE	GWB	GYPSUM WALL BOARD	VCT	VINYL COMPOSITION TILE
E	EXISTING	P	PAINT	VWC	VINYL WALL COVERING
EP	EPOXY PAINT	PCS	PAINT COAT SYSTEM	WCW	WALL COVERING TYPE W
FCS	FLOOR COATINGS SYSTEM	RCB	RUBBER COVE BASE	WD	WOOD

NO.	NAME	WALLS N	WALLS E	WALLS S	WALLS W	FLOOR MATL	FLOOR BASE	MATL	BASE	CLG A TYPE	CLG A HT	CLG B TYPE	CLG B HT	REMARKS
106	EXISTING TOILET	E	E	P	P	E	E	E	WD *	E	E	-	-	* MATCH EXISTING
107	NEW RECEPTION	P	P	P	P	C	WD *	-	-	E	E	-	-	* MATCH EXISTING
108	EXIST. OPEN OFFICE AREA	P/E	E	E	P	E	E	E	WD *	E	E	-	-	* MATCH EXISTING
204	NEW HR RESOURCE	P	P	P	P	VCT	WD	-	-	SAT	8'-0"*	-	-	* F.V. W/ HVAC
205	NEW HR OFFICE	P	P	P	P	VCT	WD	-	-	SAT	8'-0"*	-	-	* F.V. W/ HVAC

NOTE: * WD = MATCH EXISTING WOOD BASE IN THE SAME ROOM
WD = MATCH WOOD BASE TYPE IN ADJACENT ROOM(S)

LIFE SAFETY SYMBOLS
- EXIT LIGHT
- FIRE EXTINGUISHER
- FIRE ALARM PULL MANUAL PULL STATION
- FACP FIRE ALARM PANEL
- EMERGENCY LIGHT
- FIRE ALARM HORN/STROBE UNIT
- FIRE ALARM STROBE UNIT
- HEAT DETECTOR
- SMOKE DETECTOR
- SMOKE DETECTOR W/ AUDIBLE ALARM
- "NOT AN EXIT" SIGN
- KNOX BOX
- EXISTING/RELOCATED (SHADED)
- EXISTING TO REMAIN (SHADED)

REPRODUCTION OF THIS DOCUMENT WITHOUT WRITTEN PERMISSION GRANT HAYS IS PROHIBITED

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 05/13/13
Planner: Benjamin Wallace

LICENSED MICHAEL F. HAYS No. 1724 STATE OF MAINE

REVISIONS

JOB TITLE
NEW ADDITION FOR ALLAGASH BREWING CO.
50 INDUSTRIAL WAY PORTLAND, MAINE

GRANT HAYS ASSOCIATES
ARCHITECTURE INTERIOR DESIGN
P.O. BOX 6179 FALMOUTH, MAINE 04105
telephone (207) 871-5900
facsimile (207) 871-8308

DRAWING TITLE
CODE COMPLIANCE PLANS, DOOR & FINISH SCHEDULES AT HR & WALK-IN COOLER

SCALE	AS NOTED
DATE	28 FEB. 13
DRAWN BY	SAM/MFH
JOB NO.	120701
DRAWING NO.	A8.2