SPLICE BOLT TABLE						
Mark	Qty Top	Bot	Int	Type	Dia	Length
SP-1	4	4	2	A325	1.000	2.75
SP-2	4	4	2	A325	0.750	2.25
SP-3	4	4	4	A325	1.000	2.75

FLANGE BRACES: Both Sides(U.N.)
FBxxB(1)
B – L20X3/16
A – L15X1/8
E – L30X1/4

MEMBER TABLE					
Mark	Web Depth Start/End	Web Plate Thick	Web Plate Length	Outside Flange W x Thk x Length	Inside Flange W x Thk x Length
RF2-1	14.0/32.0	0.188	195.1	6 x 1/4" x 192.4	6 x 1/4" x 60.3
				8 x 1/4" x 40.4	6 x 3/8" x 105.7
RF2-2	26.0/22.7	0.219	82.9	6 x 1/4" x 80.7	6 x 3/8" x 83.0
	22.7/18.0	0.188	120.0	6 x 5/16" x 120.0	6 x 1/4" x 120.1
RF2-3	18.0/21.9	0.149	120.0	6 x 1/2" x 120.0	6 x 1/4" x 300.1
	21.9/25.7	0.188	120.0	6 x 5/16" x 120.0	6 x 3/8" x 74.0
	25.7/27.6	0.219	60.0	6 x 1/4" x 136.5	
	27.6/30.0	0.250	76.5		
RF2-4	32.0/23.0	0.219	126.0	8 x 1/4" x 40.4	6 x 5/8" x 89.6
	23.0/11.0	0.188	120.0	6 x 1/4" x 246.0	6 x 1/2" x 120.6

Main Frame ELEVATION: FRAME LINE 4 5

GENERAL NOTES:

1. See Detail Sheets for Connection Information.
2. See Shipping List for Flange Brace Lengths.

CORLE BUILDING SYSTEMS
404 Sarah Furnace Road - Imler, PA 16655 (814) 276 - 9611

ALLAGASH BREWING WAREHOUSE
55'-0" x 180'-0" x 17'-0" x 21'-7"
DATE: 7/30/15 | REVIS
ENG: AJR | DWN: BJC

F.O. 19026

CITY OF PORTLAND, MAINE — RESURGAM
Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 10/15/15

ALLAGASH BREWING WAREHOUSE

REVISION HISTORY

REV.	DESCRIPTION	DATE
01	SEE CC-01	8-12-15

DRAWING STATUS

☐ FOR APPROVAL: THESE DRAWINGS, BEING FOR APPROVAL, ARE BY DEFINITION NOT FINAL, AND ARE FOR CONCEPTUAL REPRESENTATION ONLY. THEIR PURPOSE IS TO CONFIRM PROPER INTERPRETATION OF THE PROJECT DOCUMENTS. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.

☐ FOR PERMIT: THESE DRAWINGS, BEING FOR PERMIT, ARE BY DEFINITION NOT FINAL. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.

■ FOR CONSTRUCTION: FINAL DRAWINGS.

STATE OF MAINE
DENNIS L. ZONTS
No. 12885
LICENSED
PROFESSIONAL ENGINEER