MEMBER TABLE
FRAME LINE C

| QUAN | MARK | PART | LENGTH |
|---|---|---|---|
| 1 | G-16 | 8X25Z13 | 27'-1 1/2" |
| 1 | G-17 | 8X25Z14 | 27'-1 1/2" |
| 10 | G-18 | 8X25Z14 | 30'-3 1/2" |
| 1 | G-19 | 8X25Z13 | 27'-1 1/2" |
| 1 | G-20 | 8X25Z14 | 27'-1 1/2" |
| 4 | CB-4 | CABLE500 | 27'-2 3/4" |

SIDEWALL FRAMING: FRAME LINE C

SIDEWALL SHEETING & TRIM: FRAME LINE C

PANELS: 3" ECO-FICIENT SUMMIT 24Ga EXTERIOR & 26Ga INTERIOR – LIGHT STONE/IGLOO WHITE

TRIM COLORS

| | |
|---|---|
| EAVE TRIM = Ash Grey | CORNER TRIM = Ash Grey |
| BASE TRIM = Light Stone | GUTTER = |
| DOOR TRIM = Ash Grey | DOWNSPOUTS = |
| RAKE TRIM = Ash Grey | |

*LINER TRIM = Liner panel color
*SOFFIT TRIM = Soffit panel color
* ONLY APPLICABLE IF LINER TRIM OR SOFFIT PANEL IS INDICATED ON BUILDING ORDER.

GENERAL NOTES:
1. Use TEK5WW screws in place of SD150 panel screws at all 10 gage members.

CORLE BUILDING SYSTEMS
404 Sarah Furnace Road - Imler, PA 16655 (814) 276 - 9611

ALLAGASH BREWING WAREHOUSE
55'-0" x 180'-0" x 17'-0" x 21'-7"
DATE: 7/30/15
REVIS
ENG: AJR
DWN: BJC

F.O. 19026

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 10/15/15

ALLAGASH BREWING WAREHOUSE

REVISION HISTORY

| REV. | DESCRIPTION | DATE |
|---|---|---|
| 01 | SEE CO-01 | 8-12-15 |

DRAWING STATUS

☐ FOR APPROVAL: THESE DRAWINGS, BEING FOR APPROVAL, ARE BY DEFINITION NOT FINAL, AND ARE FOR CONCEPTUAL REPRESENTATION ONLY. THEIR PURPOSE IS TO CONFIRM PROPER INTERPRETATION OF THE PROJECT DOCUMENTS. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.

☐ FOR PERMIT: THESE DRAWINGS, BEING FOR PERMIT, ARE BY DEFINITION NOT FINAL. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.

■ FOR CONSTRUCTION: FINAL DRAWINGS.

STATE OF MAINE
DENNIS L. ZONTS
No. 12885
LICENSED
PROFESSIONAL ENGINEER