STANDARD GIRT BRACING DETAIL
FOR SIDEWALL GIRTS

BANDING REQUIREMENTS	
BAY WIDTH	RUNS REQ'D
AS SHOWN	AS SHOWN

MEMBER TABLE
FRAME LINE A

QUAN	MARK	PART	LENGTH
2	DJ-5	8X35C16	14'-4 3/4"
1	DH-1	8X35C16	10'-0"
2	JB-1	8X35C16	6'-1 3/4"
2	G-11	8X25Z13	28'-1 1/2"
7	G-12	8X25Z14	32'-3 1/2"
1	G-13	8X25Z13	34'-10"
1	G-14	8X25Z14	12'-10"
2	G-15	8X25Z13	28'-1 1/2"
1	G-21	8X25Z13	32'-3 1/2"
4	CB-3	CABLE500	29'-7 3/8"

CONNECTION PLATES
FRAME LINE A

ID	QUAN	MARK/PART
1	10	JC8
2	2	JC

SIDEWALL FRAMING: FRAME LINE A

SIDEWALL SHEETING & TRIM: FRAME LINE A
PANELS: 3" ECO-FICIENT SUMMIT 24Ga EXTERIOR & 26Ga INTERIOR - LIGHT STONE/IGLOO WHITE

TRIM COLORS

EAVE TRIM=Ash Grey	CORNER TRIM=Ash Grey
BASE TRIM=Light Stone	GUTTER =
DOOR TRIM=Ash Grey	DOWNSPOUTS =
RAKE TRIM=Ash Grey	

*LINER TRIM= Liner panel color
*SOFFIT TRIM= Soffit panel color
* ONLY APPLICABLE IF LINER TRIM OR SOFFIT PANEL IS INDICATED ON BUILDING ORDER.

GENERAL NOTES:
1. Use TEK5WW screws in place of SD150 panel screws at all 10 gage members.

CORE DESIGN & ENGINEERING
404 Sarah Furnace Road - Imler, PA 16655 (814) 276 - 9611

ALLAGASH BREWING WAREHOUSE

55'-0" x 180'-0" x 17'-0" x 21'-7"

DATE: 7/30/15 | REVIS
ENG: AJR | DWN: BJC

F.O. 19026

CITY OF PORTLAND, MAINE — RESURGAM
Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 10/15/15

ALLAGASH BREWING WAREHOUSE

REVISION HISTORY

REV.	DESCRIPTION	DATE
01	SEE CO 01	8-12-15

DRAWING STATUS

☐ FOR APPROVAL: THESE DRAWINGS, BEING FOR APPROVAL, ARE BY DEFINITION NOT FINAL, AND ARE FOR CONCEPTUAL REPRESENTATION ONLY. THE BUILDER MUST CONFIRM PROPER INTERPRETATION OF THE PROJECT DOCUMENTS. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.

☐ FOR PERMIT: THESE DRAWINGS, BEING FOR PERMIT, ARE BY DEFINITION NOT FINAL. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.

■ FOR CONSTRUCTION: FINAL DRAWINGS.

STATE OF MAINE
DENNIS ZONTS
No. 12885
LICENSED
PROFESSIONAL ENGINEER
AUG 1 4 2015