FRAME LINES: 2 3 4 5 6 7

RIGID FRAME: ANCHOR BOLTS & BASE PLATES

Frm Line	Col Line	Anc. Qty	Bolt Dia	Base Plate (in) Width	Length	Thick	Grout (in)
2*	C	4	0.750	8.000	14.50	0.500	0.0
2*	A	4	0.750	8.000	11.75	0.500	0.0

2* Frame lines: 2 3 6 7

RIGID FRAME: ANCHOR BOLTS & BASE PLATES

Frm Line	Col Line	Anc. Qty	Bolt Dia	Base Plate (in) Width	Length	Thick	Grout (in)
4*	C	4	0.750	8.000	14.50	0.500	0.0
4*	A	4	0.750	8.000	11.75	0.500	0.0

4* Frame lines: 4 5

RIGID FRAME: BASIC COLUMN REACTIONS (k)

Frame Line	Column Line	Dead Horiz	Dead Vert	Collateral Horiz	Collateral Vert	Live Horiz	Live Vert	Snow Horiz	Snow Vert	Wind_Left1 Horiz	Wind_Left1 Vert	Wind_Right1 Horiz	Wind_Right1 Vert
2*	C	1.3	3.0	1.3	2.4	7.0	14.2	14.7	29.8	−7.9	−10.6	1.7	−3.8
2*	A	−1.3	3.3	−1.3	2.9	−7.0	14.4	−14.7	30.2	0.1	−7.6	6.3	−7.7

Frame Line	Column Line	Wind_Left2 Horiz	Wind_Left2 Vert	Wind_Right2 Horiz	Wind_Right2 Vert	Wind_Long1 Horiz	Wind_Long1 Vert	Wind_Long2 Horiz	Wind_Long2 Vert	Seismic_Left Horiz	Seismic_Left Vert	Seismic_Right Horiz	Seismic_Right Vert
2*	C	−7.6	−6.8	2.4	0.0	−2.3	−10.6	−1.6	−6.9	−2.3	−1.4	2.3	1.4
2*	A	−0.2	−3.8	5.6	−3.9	2.7	−11.7	2.0	−8.0	−1.9	1.4	1.9	−1.4

Frame Line	Column Line	Seismic_Long Horiz	Seismic_Long Vert	LWIND1_L2E Horiz	LWIND1_L2E Vert	LWIND1_R2E Horiz	LWIND1_R2E Vert	LWIND2_L2E Horiz	LWIND2_L2E Vert	LWIND2_R2E Horiz	LWIND2_R2E Vert
2*	C	0.0	−5.2	−0.1	−1.4	−0.1	−0.1	−0.1	−1.4	−0.1	−0.1
2*	A	0.0	−6.9	0.2	−0.2	0.2	−1.5	0.2	−0.2	0.2	−1.5

Frame Line	Column Line	Dead Horiz	Dead Vert	Collateral Horiz	Collateral Vert	Live Horiz	Live Vert	Snow Horiz	Snow Vert	Wind_Left1 Horiz	Wind_Left1 Vert	Wind_Right1 Horiz	Wind_Right1 Vert
4*	C	1.3	3.0	1.1	2.1	7.0	14.2	14.7	29.8	−6.7	−9.9	0.5	−4.5
4*	A	−1.3	3.3	−1.1	2.2	−7.0	14.4	−14.7	30.2	1.1	−8.3	5.3	−7.0

Frame Line	Column Line	Wind_Left2 Horiz	Wind_Left2 Vert	Wind_Right2 Horiz	Wind_Right2 Vert	Wind_Long1 Horiz	Wind_Long1 Vert	Wind_Long2 Horiz	Wind_Long2 Vert	Seismic_Left Horiz	Seismic_Left Vert	Seismic_Right Horiz	Seismic_Right Vert
4*	C	−6.4	−6.1	1.2	−0.8	−2.3	−8.9	−1.6	−5.2	−1.4	−0.9	1.4	0.9
4*	A	0.8	−4.6	4.6	−3.2	2.7	−9.3	2.0	−5.5	−1.2	0.9	1.2	−0.9

Frame Line	Column Line	LWIND1_L2E Horiz	LWIND1_L2E Vert	LWIND1_R2E Horiz	LWIND1_R2E Vert	LWIND2_L2E Horiz	LWIND2_L2E Vert	LWIND2_R2E Horiz	LWIND2_R2E Vert
4*	C	−0.1	−1.4	−0.1	−0.1	−0.1	−1.4	−0.1	−0.1
4*	A	0.2	−0.2	0.2	−1.5	0.2	−0.2	0.2	−1.5

2* Frame lines: 2 3 6 7
4* Frame lines: 4 5

CORE BUILDING SYSTEMS
404 Sarah Furnace Road - Imler, PA 16655 (814) 276 - 9611

ALLAGASH BREWING WAREHOUSE

55'-0" x 180'-0" x 17'-0" x 21'-7"

DATE: 7/30/15 | REVISI

ENG: AJR | DWN: BJC

F.O. 19026

CITY OF PORTLAND MAINE — RESURGAM
Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 10/15/15

ALLAGASH BREWING WAREHOUSE

REVISION HISTORY

REV.	DESCRIPTION	DATE
01	SEE CO-01	8-12-15

DRAWING STATUS

☐ FOR APPROVAL: THESE DRAWINGS, BEING FOR APPROVAL, ARE BY DEFINITION NOT FINAL, AND ARE FOR CONCEPTUAL REPRESENTATION ONLY. THEIR PURPOSE IS TO CONFIRM PROPER INTERPRETATION OF THE PROJECT DOCUMENTS. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.

☐ FOR PERMIT: THESE DRAWINGS, BEING FOR PERMIT, ARE BY DEFINITION NOT FINAL. ONLY DRAWINGS ISSUED "FOR CONSTRUCTION" CAN BE CONSIDERED AS COMPLETE.

■ FOR CONSTRUCTION: FINAL DRAWINGS.

STATE OF MAINE
DENNIS L. ZONTS
No. 12885
LICENSED
PROFESSIONAL ENGINEER