

DOOR SCHEDULE

ID	LOCATION	HEIGHT	WIDTH	THICKNESS	DOOR MATERIAL	DOOR FINISH	DOOR TYPE	GLAZING	FRAME MATERIAL	FRAME FINISH	FRAME TYPE	HEAD DTL	JAMB DTL	HARDWARE SET	FIRE LABEL	NOTES
101	HEAD START 102 TO VESTIBULE 101	6'-8"	3'-0"	0'-1 3/4"	HM	PAINT	B	YES	HM	PAINT	1	3/A-501	4/A-501	#3	45 MIN	
102	BATHROOM 104 TO HEAD START 102	6'-8"	3'-0"	0'-1 3/4"	WOOD	PAINT	C	-	HM	PAINT	1	4/A-501	4/A-501	#2A	-	DUTCH DOOR
103	ADA BATHROOM 107	6'-8"	3'-0"	0'-1 3/4"	WOOD	PAINT	A	-	HM	PAINT	1	3/A-501	4/A-501	#2B	-	
104	HEAD START 102 TO VESTIBULE 108	6'-8"	3'-0"	0'-1 3/4"	HM	PAINT	B	YES	HM	PAINT	1	3/A-501	4/A-501	#1	45 MIN	HALF GLAZED DOOR, INSTALLED WITHIN EXISTING OPENING
105A	ADA LIFT DOOR - FIRST LANDING	-	-	-	-	-	-	-	-	-	-	-	-	-	45 MIN	INCLUDED AS PART OF ADA LIFT ASSEMBLY, SEE A-101 KEYS NOTE 7
105B	ADA LIFT DOOR - UPPER LANDING	-	-	-	-	-	-	-	-	-	-	-	-	-	45 MIN	INCLUDED AS PART OF ADA LIFT ASSEMBLY, SEE A-101 KEYS NOTE 7
106	FOOD PREP 103 TO EXTERIOR	-	-	-	-	-	-	-	-	-	-	-	-	-	-	MODIFICATIONS TO EXISTING HARDWARE COORDINATE WITH ELECTRICAL
107	HEAD START 102 TO EXTERIOR	-	-	-	-	-	-	-	-	-	-	-	-	-	-	MODIFICATIONS TO EXISTING HARDWARE COORDINATE WITH ELECTRICAL
108	VESTIBULE 101 TO EXTERIOR	-	-	-	-	-	-	-	-	-	-	-	-	-	-	MODIFICATIONS TO EXISTING HARDWARE
109	VESTIBULE 108 TO EXTERIOR	-	-	-	-	-	-	-	-	-	-	-	-	-	-	MODIFICATIONS TO EXISTING HARDWARE
201	HEAD START 201 TO STAIRWELL 109	6'-8"	3'-0"	0'-1 3/4"	HM	PAINT	A	-	HM	PAINT	1	3/A-501	4/A-501	#3	45 MIN	VF EXISTING FRAMED OPENING
202	HEAD START 201 TO ADJACENT CORRIDOR	6'-8"	3'-0"	0'-1 3/4"	HM	PAINT	A	-	HM	PAINT	1	3/A-501	4/A-501	#1	45 MIN	VF EXISTING FRAMED OPENING
203	ADJACENT CORRIDOR TO LAUNDRY / OFFICE	-	-	-	-	-	-	-	-	-	-	-	-	-	-	VF EXISTING FRAMED OPENING

ROOM FINISH SCHEDULE

ROOM NUMBER	ROOM NAME	FLOOR MATERIAL	BASE	HEIGHT	NORTH WALL	SOUTH WALL	FINISH	EAST WALL	WEST WALL	FINISH	FINISH	CEILING MATERIAL	CEILING HEIGHT	FINISH	REMARKS
101	VESTIBULE	VCT-1	WD-1	4"	GYP	EXST	PT-1	GYP	PT-1	GYP	PT-1	GYP	8'-0"	PT-1	ENLARGED VESTIBULE WILL REQUIRE EXPANDED HARD CEILING PLANE TO FINISH FACES OF 1-HR RATED WALL
102	HEAD START	VCT-1	WD-1	4"	EXST	GYP	PT-1	EXST	PT-1	EXST	PT-1	ACT-1	9'-0"	PT-1	COORDINATE WITH ELECTRICAL, MATCH EXISTING ACT.
103	FOOD PREP	VCT-2	RB-1	4"	EXST	GYP	PT-2	EXST	PT-2	EXST	PT-2	ACT-1	7'-6"	PT-1	COORDINATE WITH ELECTRICAL, MATCH EXISTING ACT.
104	BATHROOM	VCT-2	RB-1	4"	EXST	GYP	PT-3	EXST	PT-3	EXST	PT-3	GYP	7'-6"	PT-1	
109	STAIRWELL	RUBBER TREADS VCT-1 @ LANDINGS	RB-1	4"	GYP	EXST	PT-1	EXST/GYP	PT-1	EXST	PT-1	EXST	EXST	PT-2	
201	HEAD START	VCT-1	WD-1	4"	EXST	EXST	PT-1	EXST	PT-1	EXST/GYP	PT-1	EXST	EXST	PT-3	
202	LAUNDRY/OFFICE	EXST	EXST	EXST	EXST	EXST	PT-1	GYP	PT-1	GYP	PT-1	EXST	EXST	PT-3	

1 FRAME TYPES (1/4" = 1'-0")

2 DOOR TYPES (1/4" = 1'-0")

3 DETAIL - DOOR HEAD (1/2" = 1'-0")

4 DETAIL - DOOR JAMB (1/2" = 1'-0")

5 PHOTO - EXISTING VCT (1/2" = 1'-0")

6 DETAIL - TYP STAIR TREAD AND RISER (1/2" = 1'-0")

7 DETAIL - DOOR JAMB (1/2" = 1'-0")

8 WALL TYPE 1 (1/2" = 1'-0")

9 WALL TYPE 2 (1/2" = 1'-0")

10 WALL TYPE 3 (1/2" = 1'-0")

11 WALL TYPE 4 (1/2" = 1'-0")

EXISTING WALL TO BE STRIPPED TO STUDS AND REFINISHED BOTH SIDES WITH 5/8" TYPE X GYP/UM PANELS. WALL TYPE 1 IS PARTITION OF 1-HR RATED ENCLOSURE AROUND STAIRWELL 109.

- FINISH NOTES:**
- ALL SUB-SURFACES TO BE ROUGHED & SANDED TO PROVIDE AN EVEN SURFACE AS NEEDED, CLEANED AND WIPED OFF TO RECEIVE SPECIFIED FINISHES IN ACCORDANCE WITH MFR. INSTRUCTIONS.
 - ALL FLOORING MATERIALS TO COVER ENTIRE FLOOR AREA TO WALL WITHIN ROOM. SEE A-101 FOR FLOOR FINISH LIMITS.
 - CONTRACTOR TO PROVIDE TRANSITION STRIPS AS REQUIRED AT FLOOR AND DOOR TRANSITIONS. INSTALL PER MANUFACTURER'S DETAILED INSTRUCTIONS. UNLESS STATED OTHERWISE, ALL FINISHES ARE TO REQUIRE SAMPLES THAT ARE TO BE APPROVED BY PHA AND/OR HEAD START.
 - ALL VCT AND PAINT TO BE PROVIDED BY OWNER.
 - CONTRACTOR TO FIELD VERIFY ALL DOOR HEIGHTS PRIOR TO COMMENCING WORK.

- FINISH LEGEND:**
- VCT-1 VINYL COMPOSITION TILE 01 (EXISTING HEAD START AREA)
 - VCT-2 VINYL COMPOSITION TILE 02 (EXISTING KITCHEN AREA)
 - RB-1 4" RUBBER BASE (ROPPE 700 SERIES, COLOR BY OWNER)
 - WD-1 1/2" WOOD BASE (MATCH EXISTING)
 - PT-1 PAINT, COLOR 1 (BY OWNER)
 - PT-2 PAINT, COLOR 2 (BY OWNER)
 - PT-3 PAINT, COLOR 3 (BY OWNER)
 - ACT-1 ACOUSTIC CEILING TILE (MATCH EXISTING)

PORTLAND HOUSING AUTHORITY
PORTLAND, MAINE

PHA RIVERTON HEAD START
BUILDING 14, UNITS 102 AND 104

PROJECT NO: 218.02.001
DATE: 02/29/17
DRAWN BY: GUN
CHECKED BY: BLS
DATE: 02/29/17
DRAWN BY: GUN
CHECKED BY: BLS

ARCHITECTURAL DETAILS

DRAWING NO: A-501

SHEET 11 OF 16