08/31/2004 03:04:43 PM

STORE EQUIPMENT - BAKERY DEPARTMENT

EQUIPMENT IDENTIFICATION				ELECTRICAL REQUIREMENTS				
TAG	MFGR.	ITEM	MODEL	KVA	VOLT/PH	FLA	CONN.	REMARKS
BK-1	BAXTER HOBART	PROOFER	P0101 M40 A HP1-63/HPI-2	5.0 0.5 7.5	208V/1 120V/1 208V/1	23.0 4.6 36.0	HW . HW	HEATING CIRCUIT CONTROL CIRCUIT
BK-2	???	30 QT. MIXER	.	.	.	.	.	.
BK-3	???	DOUGH DIVIDER	.	.	.	.	.	.
BK-4	BAXTER HOBART HOBART	2 RACK GAS OVEN W/HOOD 2 RACK GAS OVEN W/HOOD 2 RACK GAS OVEN W/HOOD	OV2100 M2B A C-V H0210G2 C-V HBA2G C-V	2.30 0.86 1.58 0.86 1.75 1.58 0.02	208V/3 120V/1 208V/3 120V/1 480V/3 208V/3 120V/1	6.6 7.2 4.4 7.2 2.1 4.4 .2	HW . HW . HW HW .	PWR IMPACT MOTORS AND CONTROL CIRCUIT PWR IMPACT MOTORS AND CONTROL CIRCUIT PWR IMPACT MOTORS PWR IMPACT MOTORS AND CONTROL CIRCUIT
BK-5	???	FOOD PROCESSOR	.	.	.	.	.	.
BK-6	FAB-X	DONUT FINISH TABLE	BG-2					NO POWER REQUIRED
BK-7	BUNN	COFFEE GRINDER	G2	1.08	120V/1	9.0	CP	.
BK-8	BERKEL	BREAD SLICER	GMB MB	0.9 0.7	120V/1 120V/1	7.5 6.2	CP	FURNISHED WITH 8A CIRCUIT BREAKER
BK-9	WILBUR CURTIS FILTER FRESH	COFFEE BREWER	C1000 AP ?	5.0 1.2	208V/1 120V/1	25.4 10 *	⊘ CP	.
BK-10	EDHARD	POWER DONUT FILLER	EDH	0.12	120V/1	1	CP	
BK-11	HOBART	SCALE/LABEL	SP1500 QUANTUM	0.15 0.18	120V/1 .	1.25 1.5	CP .	
BK-12	HOBART GLOBE	20 QT. MIXER 8 QT. MIXER	A-200 SP8	0.86 0.6	120V/1 120V/1	7.2 5.0	CP CP	.
BK-13	ICL	LINEAR POWER SUPPLY	18526/001	0.09	120V/1	0.75	CP	
BK-14	ICL	TERMINAL	9520/150 TP5K	0.03	30VDC	1.2	.	POWER CABLE/FED FROM PWR SUPPLY
BK-15	ICL	COMPACT SCANNER	CCD	0.12	120V/1	1.0	CP	
BK-16	ICL	PRINTER	10883/001	0.12	120V/1	1.0	CP	
BK-17	S.C.JOHNSON GILBERT GILBERT	INSECT CONTROL UNIT	PRISM FLYING VENUS STICK TIGER 219GT	0.2 0.03 0.03	120V/1 115V/1 120V/1	0.8 0.26 0.26	CP	
BK-18	LORING, SHORT & HARMON	TIME CLOCK STATION	PTI-PTR-4000	0.02	120V/1	0.13	CP	
BK-19	.	CAKE DECORATOR	K1000	0.5	120V/1	4.3	CP	
BK-20	BAKERY CRAFTS	PHOTO CAKE SCANNER	BCC-1000	0.02	120V/1	0.8	CP	
BK-21	BAKERY CRAFTS	PHOTO CAKE PRINTER	BCC-4000	0.03	120V/1	0.25	CP	

STORE EQUIPMENT - BOTTLE RETURN DEPARTMENT

EQUIPMENT IDENTIFICATION				ELECTRICAL REQUIREMENTS				
TAG	MFGR.	ITEM	MODEL	KVA	VOLT/PH	FLA	CONN.	REMARKS
BR-1	GILBERT	INSECT TRAP LIGHT	601T	0.1	115V/1	0.84	CP	.
BR-2	HALTEK ICL	COMPUTER REGISTER	. TP10	0.5 0.5	120V/1 120V/1	4.0 4.0 *	CP .	
BR-3	TOMRA	PLASTIC CRUSHER	22	1.4	208V/3	4	⊘I	NEMA L15-20R
BR-4	TOMRA	CAN CRUSHER	42	1.4	208V/3	4	⊘I	NEMA L15-20R
BR-5	ROTARY PRODEVA ENVIPCO/TOMRA METRO	GLASS CRUSHER	1403 95-2 1405-2	2.3 1.18 2.3	125V/1 120V/1 120V/1	18.0 9.8 18.0	⊘J CP ⊘I	.
BR-6	ENVIPCO	PLASTIC CRUSHER	200L CFP1500	5.1 5.1	208V/3 208V/3	14.0 14.0	⊘I	NEMA L15-20R
BR-7	ENVIPCO	CAN CRUSHER	200L CFM1500	0.9 2.5	120V 208V/3	7 7	CP ⊘I	NEMA L15-20R
BR-8	ENVIPCO	GLASS CRUSHER	200L CFC1500	0.9 2.5	120V 208V/3	7 7	CP ⊘I	NEMA L15-20R
BR-9	TOMRA	GLASS CRUSHER	32	1.4	208V/3	4	⊘I	NEMA L15-20R

STORE EQUIPMENT - CHEESE DEPARTMENT

EQUIPMENT IDENTIFICATION				ELECTRICAL REQUIREMENTS				
TAG	MFGR.	ITEM	MODEL	KVA	VOLT/PH	FLA	CONN.	REMARKS
CH-1	HOBART	SCALE/WRAP/STATION	SP1500/HWS2	1.2	120V/1	9.75	CP	
CH-2	GENERAL SERVICES	CHEESE GRATER	CG-150	2.4	120V/1	20.0	.	VERIFY CONNECTION
CH-3	.	INSECT CONTROL UNIT	PRISM	0.2	120V/1	0.8	CP	.

STORE EQUIPMENT - CHECKOUT (P.O.S.) AREA

EQUIPMENT IDENTIFICATION				ELECTRICAL REQUIREMENTS				
TAG	MFGR.	ITEM	MODEL	KVA	VOLT/PH	FLA	CONN.	REMARKS
CO-1	PERMASTEEL LOAD KING	ORION CHECKOUT (88" BELT)	OTE96 LHPTA55 OTE1880	0.48 0.51	120V/1 115V/1	4.0 4.4	CP	REQ PWR CONN FOR 3/4" REAR BELT
CO-2	PERMASTEEL LOAD KING	ORION EXPRESS CHECKOUT	OTE41 NR OTE1832	0.7 0.29	120V/1 115V/1	5.0 2.5	CP	
CO-3	HYPERCOM	CUSTOMER POS TERMINAL	ICE 5500M	0.24	120V/1	0.2		
CO-4	FUJITSU	CASH DRAWER	TP10	0.001	24VDC	1.2 *		POWER CABLE FED FROM POWER SUPPLY
CO-5	EPSON	REMOTE DISPLAY	DM-D110	0.01	30VDC	0.42 *		POWER CABLE FED FROM POWER SUPPLY
CO-6	SYMBOL	SCANNER	LS 4000	0.001	14VDC	.95		POWER CABLE FED FROM POWER SUPPLY
CO-7	EPSON	PRINTER	TM-H6000II	0.12	24VDC	1.9		POWER CABLE FED FROM POWER SUPPLY
CO-8	NCR	SCANNER / SCALE	7875	.1	120V/1	1 *	CP	
CO-9	WINCOR/NIXDORF	12.1" LCD FLAT SCREEN	BA72A	.003	120V/1	0.02	CP	
CO-10	ACER	15" CRT MONITOR	AC501	0.09	120V/1	.75	CP	
CO-11	LORING SHORT HARM VERFONE	TIME CLOCK STATION	PTI PTR 4000 OMNI-550	0.02	120V/1 120V/1	0.13	CP	
CO-12	VERIFONE	E.P.S. TERMINAL	490	.	120V/1	.	CP	
CO-13	VERIFONE	E.P.S. PRINTER	150	.	120V/1	.	CP	
CO-14	.	INSTANT LOTTERY MACH	.	0.2	120V/1	1.66	CP	.
CO-15	ACM	SELF SCANNING CHECKOUTS	700-58	1.2	115V/1	10 *	CP	POWER INCLUDES BELT DRIVE
CO-16	ACM	SELF SCANNING CHECKOUTS	502	0.7	115V/1	6.0 *	CP	POWER INCLUDES BELT DRIVE

STORE EQUIPMENT - CUSTOMER SERVICE/CASH OFFICE

EQUIPMENT IDENTIFICATION				ELECTRICAL REQUIREMENTS				
TAG	MFGR.	ITEM	MODEL	KVA	VOLT/PH	FLA	CONN.	REMARKS COND
CS-1	ICL	LINEAR POWER SUPPLY	.	0.09	120V/1	0.75	CP	
CS-2	ICL	TERMINAL	9520/150	0.03	30VDC	1.2	.	POWER CABLE/FED FROM PWR SUPPLY
CS-3	ICL SYMBOL	COMPACT SCANNER Y HAND SCANNER	CCD LS4007	0.12	120V/1	1.0	CP	
CS-4	ICL	PRINTER	10883/001	0.12	120V/1	1.0	CP	
CS-5	FDC/WESTERN UNION	TERMINAL	.	0.2	120V/1	0.8	CP	.
CS-6	.	.	.	.	.	.	.	.
CS-7	.	PHONE FIND TERM.	HDS-5	0..2	120V/1	2.0	CP	
CS-8	IBM	STORE SETTLE TERM	HDS-1	0.2	120V/1	2.0	CP	
CS-9	IBM	STORE SETTLE PRINTER	PRU-7070	0.09	120V/1	0.8	CP	
CS-10	.	ELECT.FUNDS TRSFR.	772015	0.5	120V/1	4.0	CP	
CS-11	PANASONIC SENSORMATIC	MONITOR	. AD9414	0.2 0.06	120V/1 120V/1	0.8 0.5	CP CP	.
CS-12	REPUBLIC TRAVELERS EXP	MONEY ORDER DISPENSER	. .	N/A N/A	120V/1 120V/1	. .	CP .	PLUGS INTO GENERAL PURPOSE OUTLET
CS-13	SCIENTIFIC GAMES	LOTTERY	.	.2	120V/1	1	CP	& TEL
CS-14	STANDARD REGSTR.	CHECK ENCODER	TE-1807 TE-1916	0.5 0.12	120V/1 120V/1	4.0 1.0	CP	FILTERED PWR REQUIRED
CS-15	BELL ATLANTIC/ CMP	BILL PROCESSOR	LNX-C	0.12	120V/1	1.0	CP	REQUIRES PWR CONN. FOR MODEM & CONN. FOR TELEPHONE
CS-16	COMPAQ	CPU (EPS SYS))	PS-3/35	.	120/1	.	CP	
CS-17	COMPAQ	MONITOR (EPS SYS)	8503	.	120/1	.	CP	
CS-18	OKIDATA LEXMARK	PRINTER (EPS SYS)	LX-810 T522	. .2	120/1	. 2.0 *	CP	
CS-19	VERIFONE	EPS TERMINAL	490	.	120/1	.	CP	PLUGS INTO GENERAL PURPOSE OUTLET
CS-20	VERIFONE	E.P.S. PRINTER	150	.	120/1	.	CP	PLUGS INTO GENERAL PURPOSE OUTLET
CS-21	VERIFONE	CHECK READER	CR600	.1	120/1	.0008	CP	PLUGS INTO GENERAL PURPOSE OUTLET
CS-22	IBM	CHIP TERMINAL (CRT)	3153	0.1	120V/1	1.0	CP	
CS-23	WINCOR/NIXDORF	12.1" LCD FLAT SCREEN	BA72A	.003	120V/1	0.02	CP	

STORE EQUIPMENT - DELI DEPARTMENT

EQUIPMENT IDENTIFICATION				ELECTRICAL REQUIREMENTS				
TAG	MFGR.	ITEM	MODEL	KVA	VOLT/PH	FLA	CONN.	REMARKS
DE-1	LORING, SHORT & HARMON	TIME CLOCK STATION	PTI-PTR-4000	.02	120V/1	0.13	CP	
DE-2	LOAD KING	HOT FOODS UNIT	HST-5	10.4	208V/1	35	HW	.
DE-3	McCALL	SANDWICH/PIZZA PREP	PTS-2D P-10-12	1.4 0.92	120V/1 115V/1	12 8.0	CP	.
DE-4	BLODGETT	GAS OVEN	DFG-100	1.1	120V/1	9.0	CP	.
DE-9	HEAT SEAL	FILM WRAP	625A	0.8	120V/1	6.5	CP	.
DE-10	HENNY PENNY	GAS PRESSURE FRYER	600 PFG-600	1.2 1.2	120V/1 120V/1	10 9.6	HW	FOR CONTROL CIRCUIT
DE-11	HOBART	SCALE/LABELER	SP1500 QUANTUM	0.15 0.18	120V/1 .	1.25 1.5	CP	
DE-12	HOBART	AUTO SLICER	1712E 2912	0.86 0.72	120/1 120/1	7.2 6	CP	.
DE-13	HOBART	MANUAL SLICER	1612E 2812	0.7 0.6	120V/1 120V/1	5.8 5	CP	.
DE-14	CLEVELAND	WARMING CABINET	CR-334	2.58	120V/1	21.5	CP	REQUIRES NEMA L5-30R ⊘J
DE-15	LANG MFG CO	PANINI GRILLE	USA-24-6	3.32	208V/1	16	⊘G	
DE-16	AMERICAN PERM WARE	SOUP WARMER	CW-2A	1.2	120V/1	10	CP	.
DE-17	HOBART	FOOD PROCESSOR	FP-100	0.42	120V/1	3.5	CP	.
DE-18	NATIONAL	RICE COOKER	RICE-O-MATIC	1.6	120V/1	12.9	CP	.
DE-19	AMANA	MICROWAVE	RC/6D	0.7	120/1	5.8	CP	.
DE-20	GILBERT	INSECT CONTROL UNIT	STICK TIGER 219GT FLYING VENUS	0.03 0.03	120V/1 115V/1	0.26 0.26	CP	.
DE-21	TURN-O-MATIC	TAKE-A-NO. SYSTEM	.	1.0	120V/1	0.8	CP	TRANSF/BUTTONS/WIRE SUPPLIED WITH UNIT- INSTALLED BY E.C.
DE-22	THERMACO	GREASE INTERCEPTOR	W-200-IS	.36	120V/1	3	HW	.
DE-23	DCS	DECK OVEN	DCS-FSCO	1.1	120V/1	9	CP	.
DE-24	HOBART	HAND-WRAP STATION	HWS-2 HWS-4	1.02	120V/1	8.5	CP	MAY BE USED WITH SP1500
DE-25	CLEVELAND HOBART HOBART HARDT	ROTISSERIE OVEN	CR-32 HCFR HR-7 INFERNO 35	1.1 .4 8.9 0.9	120V/1 120V/1 208V/3 120V/1	9 3 24.7 7.5	CP CP HW	. . .
DE-26	BKI	MOBILE CHICKEN	MM-4 MM-6	2.2 3.0	208V/1 208V/1	10.5 14.4	⊘M ⊘P	

STORE EQUIPMENT - OFFICES

EQUIPMENT IDENTIFICATION				ELECTRICAL REQUIREMENTS				
TAG	MFGR.	ITEM	MODEL	KVA	VOLT/PH	FLA	CONN.	REMARKS
EL-1	AMANA PANASONIC	MICROWAVE OVEN	RC/6D NM-S541WF	0.7 1.2	120V/1 120V/1	5.8 10 *	CP	.
EL-2	FRIGIDAIRE	REFRIGERATOR	FRT18DRHW FRT18HS6A	1.0 1.0	120V/1 120V/1	8.3 * 8.3 *	CP	.
EL-3	CRANE NATIONAL	VENDING MACHINE	SNACKCENTER1	0.36	120V/1	3.0	CP	.
EL-4	CRANE NATIONAL	VENDING MACHINE	HOTTRON	1.6	120V/1	13.25	CP	.
EL-5	NATIONAL WHEEL-O-VATOR	CHAIR LIFT	BC-144	1.9	120V/1	16	HW	.
EL-6		VENDING MACHINE	SODA	1.44	120V/1	12.0	CP	.
PO-1	COMPAQ	PC	.	.	120/1	.	CP	
PO-2	.	MONITOR	.	.	120/1	.	CP	
PO-3	HEWLETT-PACKARD	LASER PRINTER	.	.	120/1	.	CP	
CR-1	ICL	CPU CONTROLLER	1800 . ALPHA IV ALPHA IV	1.8	120V/1	15.0	CP	L5-15P PLUG SUPPLIED- PROVIDE L5-15R RECEP
CR-2	IBM	PC	.	.	120/1	.	CP	
CR-3	ICL	MODEM	. ALPHA IV	0.4	120V/1	3.3	CP	
CR-4	.	MONITOR	.	.	120/1	.	CP	
CR-5	.	PRINTER	.	.	120/1	.	CP	
TA-1	CANNON PITNEY BOISE	PHOTO COPIER	NP1820 OL185	1.5	120V/1 120V/1	12	CP	
TA-2	COMPAQ	PC	.	.	120/1	.	CP	
TA-3	.	MONITOR	.	.	120/1	.	CP	
TA-4	HEWLETT-PACKARD	LASER PRINTER	.	.	120/1	.	CP	
MO-1	COMPAQ	PC	.	.	120/1	.	CP	
MO-2	COMPAQ	MONITOR	.	.	120/1	.	CP	
MO-3	HEWLETT PACKARD	LASER PRINTER	.	.	120/1	.	CP	

STORE EQUIPMENT - GENERAL SALES AREA

EQUIPMENT IDENTIFICATION				ELECTRICAL REQUIREMENTS				
TAG	MFGR.	ITEM	MODEL	KVA	VOLT/PH	FLA	CONN.	REMARKS
GS-1	ARIZONA WATER VENDORS	WATER VENDING MACHINE	AWV-100	1.4	120/1	12	CP	.
GS-2	PANASONIC SENSORMATIC	SECURITY MONITOR	CT-2004 AD9421A	. 0.06	120V/1 120V/1	. .5	CP	.
GS-3	SAGE INDUSTRIES MART SHOPPER	MART CART CHARGER	02002	0.24 0.08	120V/1 120V/1	2.0 0.66	CP	.
GS-4	CRANE NATIONAL	VENDING MACHINE	-	1.2	120V/1	10.0	CP	.
GS-5	LEER	ICE MERCHANDISER	40	0.8	120V/1	6.5	CP	.
GS-6	.	STAMP MACHINE	.	0.6	120V/1	5	CP	.

STORE EQUIPMENT - ONE HOUR PHOTO DEPARTMENT

EQUIPMENT IDENTIFICATION				ELECTRICAL REQUIREMENTS				
TAG	MFGR.	ITEM	MODEL	KVA	VOLT/PH	FLA	CONN.	REMARKS
HP-1	ICL	LINEAR PWR SUPPLY	-	0.09	120V/1	0.75	CP	
HP-2	ICL	TERMINAL	TP5K	0.03	30VDC	1.2	.	POWER CABLE-FED FROM POWER SUPPLY
HP-3	ICL	REMOTE DISPLAY	18526/001	0.01	30VDC	0.42	.	POWER CABLE-FED FROM POWER SUPPLY
HP-4	ICL	COMPACT SCANNER	CCD	0.12	120V/1	1.0	CP	
HP-5	ICL	PRINTER	10883/001	0.12	120V/1	1.0	CP	
HP-6	VERIFONE	EPS STATION	490	.	120V/1	.	CP	
HP-7	VERIFONE	EPS PRINTER	150	.	120V/1	.	CP	
HP-8	AGFA MINILAB BUSINESS SYSTEM	FILM PROCESSOR	MSC101	6.48	208V/3	18.0	HW	.
HP-9	SAFETY CLEAN	SILVER RECOVERY UNIT	OMNI 16	1.9	120V/1	16.0	CP	.
HP-10	KODAK	DIGITAL PROCESSOR	1000	.	120V/1	.	CP	
HP-11	KODAK	PRINT SCANNER	2000	.	120V/1	.	CP	.
HP-12	KODAK	DIGITAL PRINTER	3000	.	120V/1	.	CP	.
HP-13	SUMMIT	REFRIGERATOR	61RF	1.0	120V/1	8.3	CP	.
HP-14	LOGAN	LIGHT BOX	LB810	.01	120V/1	.10	HW	.
HP-15	AGFA	KODAK PROCESSOR/ SCANNER/PRINTER	MSC101	6.2	208V/1	30	.	.

STORE EQUIPMENT - MEAL/ENTREE CENTER

EQUIPMENT IDENTIFICATION				ELECTRICAL REQUIREMENTS				
TAG	MFGR.	ITEM	MODEL	KVA	VOLT/PH	FLA	CONN.	REMARKS
MC-1	.	SIDE BY SIDE REFRIG.	TXF242R	0.2	120/1	1.5	CP	.
MC-2	.	MEAL CENTER WRAP	54004	0.84	120/1	7	CP	.
MC-3	.	MICROWAVE/OVEN	JKP76GP	2.4	208V/1	20.0	CP	.
MC-4	SUPERMARKET KIOSKS INC.	COMPUTER/RECEIPE KOISKS	RCPC22	0.8	120/1	6.0	CP	.

STORE EQUIPMENT - MEAT DEPARTMENT

EQUIPMENT IDENTIFICATION				ELECTRICAL REQUIREMENTS				
TAG	MFGR.	ITEM	MODEL	KVA	VOLT/PH	FLA	CONN.	REMARKS
MT-1	HOBART	NSW COMPACT SEMI-AUTO WRAP SYSTEM	UWS	2.1 .06 .94	208V/1 120V/1 120V/1	10 .5 7.8	. . .	PROVIDE SINGLE CORD DROP TO SYSTEM- SEE OVERHEAD ELECTRICAL DROPS DETAIL
MT-2	HOBART BIRO	MEAT SAW	5701 6614 6801 3340-4003	4.2 2.0 2.4 4.0 3.8 3.3	480V/3 480V/3 208V/3 460V/3 208V/3 208V/3	5 3.4 6.8 4.8 * 10.6 * 9.16	⊘H ⊘K ⊘H ⊘K	
MT-3	HOBART	SCALE/LABELER	SP1500 QUANTUM	0.15 0.18	120V/1 .	1.25 1.5	.	
MT-4	???	HUMIDIFIER	.	1.8	120V/1	15	.	
MT-5	HOBART	SCALE/WRAP/STATION	SP1500/HWS-2 QUANTUM/HWS-4	1.2 1.2	120V/1 120V/1	9.02 10	CP	
MT-6	KASCO	KNIFE SHARPNER	HKY100	.06	120V/1	.5	CP	
MT-7	S.C. JOHNSON GILBERT	INSECT CONTROL UNIT	PRISM STICK TIGER 219GT	0.2 0.03	120V/1 120V/1	0.8 0.26	CP	
MT-8	BIRO HOBART	MEAT TENDERIZER	PRO 9 SD 403	1.18 1.0	120V/1 120V/1	9.8 8.1	CP	
MT-9	BIRO HOBART	AUTOMATIC FEED MIXER/GRINDER	EMG 32 MG1532	6.3 12.5 10.8	480/3 208/3 480/3 208/3	7.6 17.5 15 30	⊘H ⊘K ⊘H ⊘K	

STORE EQUIPMENT - PHARMACY DEPARTMENT

EQUIPMENT IDENTIFICATION				ELECTRICAL REQUIREMENTS				
TAG	MFGR.	ITEM	MODEL	KVA	VOLT/PH	FLA	CONN.	REMARKS
PH-1	COMPAQ	PC	EN	0.5	120V/1	4.2	CP	
PH-2	ICL	LINEAR PWR SUPPLY	-	0.09	120V/1	0.75	CP	
PH-3	WINCOR/NIXDORF	12.1" LCD FLAT SCREEN	BA72A	.003	120V/1	0.02	CP	
PH-4	ICL	REMOTE DISPLAY	18526/001	0.01	30VDC	0.42	.	POWER CABLE-FED FROM POWER SUPPLY
PH-5	ICL	COMPACT SCANNER	CCD	0.12	120V/1	1.0	CP	
PH-6	EPSON	PRINTER	TM-H6000II	0.12	24VDC	1.9		POWER CABLE FED FROM POWER SUPPLY
PH-7	.	MODEM	-	0.2	120V/1	1.7	CP	
PH-8	IBM	CHIP TERMINAL (CRT)	3153	0.1	120V/1	1.0	CP	
PH-9	.	CHIP CPU	-	0.25	120V/1	1.8	CP	
PH-10	LEXMARK	PRINTER	1865S T616N	.32 .32	120V/1 120V/1	2.7 2.7 *	CP	
PH-11	VITA-STAT	BLOOD PRESS. MACH.	8000-C 90550	0.3 0.3	120V/1 120V/1	2.5 2.5	CP	
PH-12	SUMMIT FRIGIDAIRE AMANA	REFRIGERATOR	CT 70 CT 70J FRT18DRHW DRT1700B	.2 .2 1.0 1.7	120V/1 120V/1 120V/1 115V/1	1.3 1.3* 8.3 * 15	CP	
PH-13	VERIFONE	EPS STATION	490	,	120V/1	.	CP	
PH-14	VERIFONE	EPS PRINTER	150	,	120V/1	.	CP	
PH-15	AMANA PANASONIC	MICROWAVE OVEN	RC/6D NM-S541WF	0.7 1.6	120V/1 120V/1	5.8 13.5	CP	

STORE EQUIPMENT - PRODUCE DEPARTMENT

EQUIPMENT IDENTIFICATION				ELECTRICAL REQUIREMENTS				
TAG	MFGR.	ITEM	MODEL	KVA	VOLT/PH	FLA	CONN.	REMARKS
PR-1	HEAT SEAL	FILM WRAP	625A	0.8	120V/1	6.5	CP	
PR-2	HOBART	SCALE/LABELER	SP1500 QUANTUM	0.15 0.18	120V/1 .	1.3 1.5	CP	
PR-3	.	ICE BIN	.	.	.	.	.	
PR-4	KESS MIATECK	MISTER SPRAY	AVIOA 150	0.3 0.18	120V/1 120V/1	2.3 1.5 *	CP	SUPPLIED WITH FUSE
PR-5	S.C. JOHNSON GILBERT	INSECT CONTROL UNIT	PRISM FLYING VENUS	0.2 0.03	120V/1 115V/1	0.8 0.26	CP	

STORE EQUIPMENT - RECEIVING/STORAGE AREAS

EQUIPMENT IDENTIFICATION				ELECTRICAL REQUIREMENTS				
TAG	MFGR.	ITEM	MODEL	KVA	VOLT/PH	FLA	CONN.	REMARKS
RS-1	PHILADELPHIA	TRASH COMPACTOR	PT-350	11.6 10.4	480V/3 208V/3	14 29	. .	UNFUSED DISC. SWITCH REQ CONN FROM
RS-2	GNB	ELECT. FORKL. CHRGR.	FOR CROWN 30SCTF	1.5	120V/1	12	CP	VERIFY CP CONNECTION
RS-3	CLARK	PALLET JACK CHRGR.	P40	1.5	120V/1	12.0	CP	VERIFY CP CONNECTION
RS-4	GILBERT	INSECT LIGHT TRAP	601T	0.2	120V/1	0.8	CP	.
RS-5	HONEYWELL	TERMINAL	HDS-1	0.2	120V/1	0.8	CP	
RS-6	OKIDATA	PRINTER	320	0.2	120V/1	0.8	CP	
RS-7	NSS	AUTOMATIC SCRUBBER	33	1.1	120V/1	9.2	CP	.
RS-8	LORING, SHORT & HARMON	TIME CLOCK STATION	PTI-PTR-4000	0.02	120V/1	0.13	CP	
RS-9	LOAD KING TRAMRAIL	BAILER	HB6030 2300HD	8.5 10.4 11.6	208V/3 208V/3 460V/3	23.5 29 14		UNFUSED DISC SWITCH TIME DELAY FUSED DISCONNECT SWITCH
RS-10	RITE-HITE	DOCK LEVELER	HD-1700	3.4 3.4	480V/3 208V/3	4.14 9.4		UNFUSED DISC SWITCH REQ CONN FROM CONTROL UNIT TO MOTOR
RS-11	TASKI	FLOOR CLEANER	MONO 42	1.5	120V/1	12.0	CP	USES GEN. PURPOSE OUTLET
RS-12	TENNANT-TREND	BURNISHER	S-2500	1.8	120V/1	15.0	CP	.
RS-13	CULLIGAN	WATER FILTRATION	PV-12	0.5	120V/1	4.2	CP	WATER SYSTEM REQUIRES 3 RECPTS

STORE EQUIPMENT - SEAFOOD DEPARTMENT

EQUIPMENT IDENTIFICATION				ELECTRICAL REQUIREMENTS				
TAG	MFGR.	ITEM	MODEL	KVA	VOLT/PH	FLA	CONN.	REMARKS
SF-1	.	MICROWAVE	.	2.7	208V/1	13	CP	.
SF-2	GILBERT	INSECT CONTROL UNIT	STICK TIGER 219GT FLYING VENUS	0.03 0.03	120V/1 115V/1	0.26 0.26	CP	.
SF-3	HOBART	SCALE/LABELER	SP1500 QUANTUM	0.15 0.18	120V/1 .	1.3 1.5	CP .	
SF-4	.	SHRIMP TANK	ELCS-9	0.9	120V/1	7.2	CP	.
SF-5	LIVING WATERS	LOBSTER TANK	24' X 36"	1.2	120V/1	10.0	CP	.
SF-6	PANASONIC	TOASTER OVEN	.	1.2	120V/1	10	.	.
SF-7	HOBART	STEAMER	HSF3	7.5	208V/1 208V/3	36.1 20.8	HW	
SF-8	SCOTSMAN	ICE MACHINE (E)	FM 2400 RHE 32A	0.6	208V/1	2.7	.	UNFUSED DISC SWITCH HACR CKT BREAKER
SF-8	.	CUSTOM CHOWDER		.72	120V/1	6	.	.

GENERAL NOTES

1. HBC TO PROVIDE LINE CONDITIONERS AS INDICATED ON EQUIPMENT SCHEDULES.
2. BRACKETS ("[" & "]") SURROUNDING EQUIPMENT NUMBERS IN THE ONEAC CONDITIONERS MODEL# COLUMN INDICATE DEVICE IS CONNECTED TO SAME CONDITIONER AS INDICATED EQUIPMENT NUMBER. EXAMPLE: [PH-9] INDICATES DEVICE IS CONNECTED TO SAME CONDITIONER USED FOR PH-9.
3. * = ESTIMATED ELECTRICAL LOAD

CONNECTION KEY

CP = CORD AND PLUG FURNISHED WITH EQUIPMENT
CPE = CORD AND PLUG FURNISHED BY ELECTRICAL CONTRACTOR
HW = HARD WIRED

Hannaford Bros. Co.
PO Box 1000
Portland, ME 04104
(207) 883-2911
Engineering Design Services

NO	REVISIONS	DATE	BY
0	ISSUED FOR CONSTRUCTION	8/30/04	RAC

PROJECT TITLE
Hannaford
Riverside Street
Portland, Maine

SHEET TITLE
EQIPMENT SCHEDULE

scale	1/8" = 1'-0"
design	R. BUTEAU
drawn	R. CYR
checked	Dept
proj mgr	BCM
date	AUGUST, 2004

© 2004 Hannaford Bros Co

SHEET
E14
proj no. PRSSA

p:\maine\portland-riversidest-000\dgns\ep-equipscheds.dgn
MODEL NAME: Default