

**TABLE I
SUMMARY OF SUBSURFACE EXPLORATIONS
PROPOSED FOOD STORE
RIVERSIDE STREET AND FOREST AVENUE
PORTLAND, MAINE**

Explor. No.	Ground Surface El. (ft) ¹	Expl. Depth (ft)	Depth to Water (ft)	Strata Thickness (ft)						
				Topsoil	Fill	Former Topsoil	Sand	Marine Silt and Clay	Marine Sand	Glacial Stream Deposit
B101(OW)	77.3	50.0	43.5	1.0	2.0	1.0	--	21.0	25.0*	--
B102	80.1	12.0	10.5	--	5.0	--	--	7.0*	--	--
B103	78.8	12.0	NE	--	2.5	--	2.0	7.5*	--	--
B104	77.5	12.0	NE	--	5.0	--	3.5	3.5*	--	--
B105	80.8	17.5	NE	1.0	12.5	--	--	4.0*	--	--
B105A	80.8	10.1	NE	1.0	9.1	--	--	--	--	--
B106	76.8	32.5	NE	--	28.5	--	--	--	--	4.0*
B107	54.9	22.0	21.0	--	13.8	--	--	--	--	8.2*
B108	81.4	52.0	51.4	2.0	--	--	3.5	46.5*	--	--
B109	47.1	22.0	13.1	--	6.0	--	--	--	--	16.0*
B110(OW)	78.8	53.0	45.0	--	0.5	--	--	52.5*	--	--
B111(OW)	43.2	21.5	9.6	--	5.0	2.0	--	--	--	14.5*
B112	61.7	31.0	NE	--	25.0	--	--	--	--	6.0*
B113	63.6	25.7	NE	--	14.5	--	--	--	--	10.2*
B114	64.2	16.0	NE	--	16.0*	--	--	--	--	--
B115	83.9	12.0	NE	1.0	--	--	2.5	8.5*	--	--
B116	77.6	12.0	9.5	1.0	--	--	2.0	9.0*	--	--
B117(OW)	46.0	20.0	NE	--	2.5	--	--	--	--	17.5*
TP101	77.6	8.2	NE	--	4.6	1.0	--	2.6*	--	--
TP102	79.0	10.0	NE	--	10.0	--	--	--	--	--
TP103	81.7	4.5	NE	0.1	--	--	3.3	1.1*	--	--
TP104	81.2	5.3	NE	--	3.1	0.6	0.8	0.8*	--	--
TP105	77.2	9.5	NE	--	6.5	1.0	--	2.0*	--	--
TP106	46.3	11.0	NE	--	8.5	--	--	--	--	2.5*
TP107	44.4	8.5	NE	--	8.5	--	--	--	--	--

Notes:

- Deposit not encountered in exploration
- NE Water not encountered in exploration
- * Depth of penetration into stratum in exploration (does not necessarily represent full depth of deposit)
- 1. Elevations referenced to National Geodetic Vertical Datum (NGVD)

HALEY & ALDRICH, INC.

G:\PROJECTS\29761\001\TABLE1.DOC

27 May 03