

PERFORMANCE SPECIFICATION - CONT.

SECTION IV TANK INSTALLATION - CONTINUED

PART 3 - INSTALLATION - CONTINUED

- 3.5 PLUGS: ALL UNUSED PLUGS SHALL BE REMOVED. APPLY COMPATIBLE NON-HARDENING PIPE SEALANT TO INTERNAL BUSHING THREADS. PERMANENT METAL PLUGS SHALL BE INSTALLED AT ALL UNUSED OPENINGS.
- 3.6 THE PLUGS IN TANK OPENINGS WHICH ARE TO BE USED SHALL NOT BE OVER TIGHTENED AS THIS MAY CAUSE THE BUSHING TO UNSCREW WITH THE PLUG. CARE SHALL BE TAKEN NOT TO CROSS THREAD OR DAMAGE THE NON- METALLIC BUSHINGS WHEN REPLACING PLUGS OR INSTALLING REQUIRED TANK PIPING.
- 3.7 WET HOLE INSTALLATION: SHOULD GROUND WATER BE PRESENT IN TANK EXCAVATIONS, 7-ELEVEN'S LOCAL CONSTRUCTION ENGINEER MUST BE NOTIFIED.
 - 3.7.1 WELL POINT: WATER SHALL BE KEPT AT LOWEST POSSIBLE POINT BY WELL POINT SYSTEM(S) AND PROPERLY SIZED PUMP(S).
 - 3.7.2 ANCHORS: DEAD MAN AS PER TANK MANUFACTURER'S RECOMMENDATIONS. PLACE 6" FROM OUTSIDE VERTICAL LINE OF TANK(S) AS DENOTED ON DRAWINGS.
 - 3.7.3 TIE DOWNS: SUPPLIED BY TANK MANUFACTURER.
 - 3.7.4 TAKE-UP FIXTURE & TURNBUCKLE: TO REMOVE CABLE SLACK, UTILIZE THE TAKE-UP FIXTURE FOR 8" DIA. TANK: MIN SIZE 26" MAX SIZE 43". WEIGHT 16 LB.
 - 3.7.5 STRAP PLACEMENT: AS PER TANK MANUFACTURER'S SPECIFICATIONS.
 - 3.7.6 COATING: COVER ALL NON-GALVANIZED HARDWARE WITH TWO (2) COATS OF ASPHALT IMPREGNATED WITH WATERPROOFING PRIOR TO PLACEMENT OF BACKFILL.
- 3.8 LIFTING: TANKS SHALL BE LIFTED ONLY AS PER MANUFACTURER'S RECOMMENDATIONS, UTILIZING LIFTING LUGS PROVIDED ON TANKS. TANKS SHALL NOT BE ROLLED, DROPPED OR WRAPPED WITH CHAINS. EQUIPMENT OF SUFFICIENT SIZE, DESIGN AND LIFT CAPACITY SHALL BE UTILIZED FOR SETTING OF TANKS. SHOULD TANKS BE BUMPED, DENTED, DROPPED OR MISHANDLED IN ANY WAY, INSTALLATION SHALL BE HALTED AND TANK MANUFACTURER'S REPRESENTATIVE IMMEDIATELY CONTACTED FOR RE-CERTIFICATION OF TANKS. CONTACT LOCAL CONSTRUCTION OFFICE OR SITE MANAGER IMMEDIATELY UPON NOTICE OF QUESTIONABLE HANDLING OF TANKS OR NOTABLE DAMAGE THERETO.
- 3.9 BACK FILL PLACEMENT: ONCE TANKS ARE PROPERLY SET IN PLACE, CAREFULLY BACK FILL ENTIRE EXCAVATION, HAND SHOVELING AND TAMPING ALONG BOTTOM OF TANK(S) SO THEY ARE EVENLY SUPPORTED AROUND BOTTOM. SPECIAL ATTENTION SHALL BE PAID TO BOTTOM QUARTER POINTS ELIMINATING ANY VOIDS IN FILL AT THESE POINTS. DO NOT DROP BACK FILL FROM HIGH DISTANCE ONTO TANKS. TAMP AS REQUIRED TO ACHIEVE ACCEPTABLE DENSITY.
- 3.10 BALLASTING: IF GROUND WATER IS PRESENT, TANKS SHALL BE FILLED WITH BALLAST (WATER) TO AVOID SHIFTING MOVEMENT. COST OF WATER AND REMOVAL SHALL BE CONTRACTOR COST. DO NOT INSTALL SUBMERGIBLE PUMPS IN TANKS FILLED WITH WATER. DO NOT BALLAST TANKS ABOVE LEVEL OF BACKFILL.
- 3.11 PROTECTION: CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ADEQUATE PROTECTION FOR TANK EXCAVATION FROM SURFACE WATERS WITH DAMS, BERMS, OR OTHER MEANS PENDING COMPLETION OF INSTALLATION. EXCAVATION SHALL BE MARKED AT ALL TIMES WITH LIGHTED BARRICADES UNTIL INSTALLATION IS COMPLETE. WATER SHALL NOT BE ALLOWED TO ACCUMULATE IN EXCAVATION. DE-WATER AS REQUIRED TO MAINTAIN EXCAVATION AS DRY AS POSSIBLE.

SECTION V CONCRETE

PART 1 - GENERAL

- 1.1 SCOPE: THIS SECTION COVERS THE FURNISHING OF ALL LABOR, MATERIALS, SERVICES, EQUIPMENT AND APPLIANCES REQUIRED IN CONJUNCTION WITH OR PROPERLY INCIDENTAL TO CONCRETE.

PART 2 - PRODUCTS

- 2.1 MATERIALS:
 - 2.1.1 AIR ENTRAINING AGENT: ASTM C 260-60-T. "PROTEX" MANUFACTURED BY PROTEX INDUSTRIES OR APPROVED EQUAL.
 - 2.1.2 PORTLAND CEMENT: CONFORM TO ASTM C-150 TYPE I; TYPE II WHERE WATER SOLUBLE SULFATES ARE PRESENT.
 - 2.1.3 AGGREGATES: CONFORM TO ASTM C-33.
 - 2.1.4 WATER: SHALL BE CLEAN AND POTABLE.
 - 2.1.5 SAND: CONFORM TO ASTM C-144.
 - 2.1.6 STEEL REINFORCING: CONFORM TO ASTM A-615, GRADE 60 (EXCEPT WHERE NOTED OTHERWISE) YIELD STRENGTH 60,000 PSI.
 - 2.1.7 ACCESSORIES INCLUDING BAR SUPPORTS, CHAIR SPACES, ETC., SHALL BE COLD DRAWN WIRE WITH HEIGHTS REQUIRED. BAR SUPPORTS FOR CONCRETE RESTING ON EARTH OR GRAVEL SHALL BE PRE CAST BRIQUETTES OR INDIVIDUAL HIGH CHAIRS NO. HCP WITH WELDED PLATES ON BOTTOM AS MANUFACTURED BY HOHMANN & BERNARD, INC.
 - 2.1.8 FORMS: CLEAN, STRAIGHT LUMBER OF MOISTURE RESISTANT PLYWOOD. KNOT HOLES, DEFORMATIONS, ETC., SHALL NOT BE ALLOWED.
 - 2.1.9 EXPANSION JOINT FILLERS: ASPHALT IMPREGNATED FIBERBOARD CONFORMING TO ASTM D-60-T. USE 1/2" THICK OR AS INDICATED ON DRAWINGS. TOP OF JOINT MATERIAL SHALL BE SET 1/2" BELOW TOP SURFACE OF SLAB. FILL VOID WITH GASOLINE RESISTANT SEALER.
 - 2.1.10 CALCIUM CHLORIDE: NOT PERMITTED.
- 2.2 CONCRETE PROPORTIONS: CONCRETE SUPPLIER SHALL DESIGN CONCRETE MIX AND SHALL GUARANTEE CONCRETE STRENGTH. ALL CONCRETE, UNLESS NOTED OTHERWISE ON DRAWINGS, OR REQUIRED OTHERWISE BY CODES, SHALL BE DESIGNED FOR 4,000 PSI STRENGTH AT 28 DAYS WITH NOT LESS THAN 5 1/2 BAGS OF CEMENT PER CUBIC YARD OF CONCRETE. NOT MORE THAN 6 1/2 GALLONS OF WATER PER BAG OF CEMENT AND NOT MORE THAN A 4" SLUMP. AIR CONTENTS SHALL RANGE BETWEEN 4% AND 7%.

SECTION V CONCRETE - CONTINUED

PART 3 - EXECUTION

- 3.1 GRADE CONTROL: ESTABLISH AND MAINTAIN LINES AND GRADES FOR CONCRETE ITEMS BY MEANS OF LINE AND GRADE STAKES AND SCREEDS.
- 3.2 FORM WORK: BUILD FORMS TO CONFORM TO SHAPE, LINES AND DIMENSIONS OF CONCRETE MEMBERS. BRACE AND SECURE TO WITHSTAND PLACING OF CONCRETE AND MAINTAIN THEIR SHAPES AND POSITIONS. MAKE FORMS SUFFICIENTLY TIGHT AND SUBSTANTIALLY ASSEMBLED TO PREVENT BULGING OR LEAKAGE. ASSEMBLE FORMS IN SUCH A MANNER TO FACILITATE THEIR REMOVAL WITHOUT DAMAGE TO CONCRETE. FORMS SHALL BE IN OR NEAR NEW CONDITION; CLEAN, SMOOTH AND WITHOUT INDENTATIONS OR BENDS. INSTALL SLEEVES, MANHOLES, CAPS, BOXES AND POSTS IN PROPER LOCATIONS AND HEIGHTS. EXPANSION JOINTS SHALL CONSIST OF FILLER STRIPS INSTALLED WITH TOP AT ELEVATIONS OF FINISHED CONCRETE. NEATLY FINISH EDGES OF EXPOSED CONCRETE ALONG JOINTS WITH A SLIGHTLY ROUNDED EDGING TOOL.
- 3.3 REINFORCEMENT: FURNISH AND INSTALL ALL REINFORCING STEEL INDICATED ON DRAWING METAL REINFORCEMENT AT THE TIME CONCRETE IS PLACED, SHALL BE FREE FROM COATINGS WHICH WILL DESTROY OR REDUCE THE BOND. METAL REINFORCEMENT SHALL BE STORED SO AS TO PREVENT FREEZING FOR A MINIMUM OF 48 HOURS PRIOR TO PLACEMENT ALL REINFORCEMENT SHALL BE FABRICATED AND PLACED IN ACCORDANCE WITH STANDARDS OF ACI. METAL REINFORCEMENT SHALL BE ACCURATELY PLACED AND ADEQUATELY SECURED IN POSITION. SPLICES IN ADJACENT BARS SHALL BE LAPPED 36 DIAMETERS AT CORNERS AND SPLICES, AS REQUIRED.
- 3.4 MIXING AND TRANSPORTING CONCRETE: CONCRETE SHALL BE READY MIXED AND SHALL MEET REQUIREMENTS OF ASTM C-94 FOR MIXING AND DELIVERY. FURNISH DUPLICATE DELIVERY TICKETS OF EACH TRUCK LOAD TO OWNER'S LOCAL CONSTRUCTION OFFICE WHEN REQUIRED. TICKETS SHALL SPECIFY STRENGTH, SLUMP, AGGREGATE SIZES, AIR ENTRAINMENT (IF ANY) AND BRAND OF CEMENT. NOTE AMOUNT OF WATER ADDED AT JOB.
- 3.5 PLACING CONCRETE:
 - 3.5.1 NOTIFICATION: THE CONTRACTOR SHALL NOTIFY THE OWNER'S LOCAL CONSTRUCTION OFFICE AT LEAST 48 HOURS BEFORE PLACING ANY CONCRETE. THE CONTRACTOR SHALL NOTIFY ALL TRADES AFFECTED BY CONCRETE PLACEMENT AT LEAST 24 HOURS BEFORE PLACING ANY CONCRETE IN ORDER THAT TRADES AFFECTED MAY INSTALL REQUIRED BLOCKING, SLEEVED, POCKETS, ETC.
 - 3.5.2 PROTECTION: PROTECT ALL WORK OF OTHER TRADES AS REQUIRED.
 - 3.5.3 WETTING: THOROUGHLY WET FORMS AND DAMPEN SAND CUSHIONS BEFORE PLACING CONCRETE.
 - 3.5.4 PLACING: PLACE ALL CONCRETE IN ACCORDANCE WITH ACI 614. MINIMUM CONCRETE COVER OVER REINFORCEMENT SHALL CONFORM TO ACI 318; USE HANDLING EQUIPMENT AND METHODS TO INSURE A CONTINUOUS FLOW FROM MIXER TO PLACE OF DEPOSIT SPACE, TAMP AND MECHANICALLY VIBRATE FRESHLY PLACED CONCRETE TO COMPACT THOROUGHLY AND ELIMINATE VOIDS. DO NOT ALLOW FREE FALL OF CONCRETE TO EXCEED 5'.
- 3.6 FINISHING CONCRETE:
 - 3.6.1 SLABS SHALL BE A TRUE PLANE SURFACE WITH NO DEVIATION IN EXCESS OF 1/4" WHEN TESTED WITH A 10' STRAIGHTEDGE AT 3' INTERVALS IN BOTH DIRECTIONS. SCREED AND FLOAT CONCRETE FOR SLAB WITH STRAIGHT EDGES TO BRING SURFACE TO REQUIRED FINISHED LEVEL. WOOD FLOAT CONCRETE WHILE STILL GREEN TO A TRUE, EVEN SURFACE WITH NO COARSE AGGREGATE VISIBLE. AFTER SURFACE MOISTURE HAS DISAPPEARED, STEEL TROWEL SURFACE TO A SMOOTH, EVEN FINISH, FREE FROM BLEMISHES AND TROWEL MARKS. AFTER TROWELING, BRUSH SURFACE OF CONCRETE WITH BRISTLE BROOM TO RESULT IN A MEDIUM, UNIFORM, NON-SLIP TEXTURED SURFACE. STROKE CROSSWISE TO LENGTH.
- 3.7 CURING: UTMOST CARE SHALL BE TAKEN TO ACHIEVE A UNIFORM, PROTECTIVE CURE FOR ALL SLABS. DO NOT USE CALCIUM CHLORIDE. CURING METHODS SHALL CONFORM TO ACI STANDARD 605-99 AND ACI STANDARD 306-66.
- 3.8 REMOVAL OF FORMS: DOT NOT REMOVE FORMS UNTIL CONCRETE HAS ATTAINED SUFFICIENT STRENGTH TO SUPPORT ANY SUPERIMPOSED LOADS.
- 3.9 PATCHING: NO PATCHING SHALL OCCUR UNTIL APPROVED BY OWNER.
- 3.10 TEMPERATURE:
 - 3.10.1 COLD WEATHER: WHEN MEAN DAILY TEMPERATURE OF THE ATMOSPHERE IS LESS THAN 40 DEGREES FAHRENHEIT, MAINTAIN TEMPERATURE OF CONCRETE BETWEEN 50 AND 70 DEGREES FAHRENHEIT FOR MINIMUM OF 72 HOURS.
 - 3.10.2 HOT WEATHER: MAKE ARRANGEMENTS FOR INSTALLATION OF WINDBREAKS, SHADING, FOG SPRAY, SPRINKLING, PONDING OR WET COVERING IN ADVANCE OF PLACEMENT. TAKE SUCH PROTECTIVE MEASURES AS QUICKLY AS CONCRETE HARDENING AND FINISHING OPERATIONS WILL ALLOW.
- 3.11 TESTING: CONCRETE TESTS SHALL BE ORDERED AT THE DISCRETION OF THE OWNER'S CONSTRUCTION MANAGER. THE OWNER SHALL PAY FOR ALL CONCRETE TESTING. COMPACTION TESTS SHALL BE REQUIRED PRIOR TO PLACEMENT OF ANY CONCRETE ON GRADE. CONTRACT OWNER'S ENGINEERING SERVICES FOR COMPACTION TESTING TESTS. TESTS WILL BE PAID FOR BY OWNER.
- 3.12 THICKNESS:
 - 3.12.1 SLAB OVER TANKS SHALL BE 8" CONCRETE SLAB WITH #3 REINFORCING BARS AT 12" OC EACH WAY ON 3" SADDLES (CHAIRS). ADDITIONAL REINFORCING AROUND MANHOLES IN UPPER PORTION OF THE TANK SLAB SHALL BE ON 5" SADDLES (CHAIRS).
 - 3.12.2 CANOPY SLABS SHALL BE 6" CONCRETE. REINFORCEMENT SHALL BE #3'S AT 18" OC EACH WAY. REINFORCEMENT SHALL BE ON 2" SADDLES (CHAIRS).
- 3.13 CANOPY FOOTINGS: CANOPY FOOTINGS SHALL BE INSTALLED BY GENERAL GASOLINE CONTRACTOR AS PER SHOP DRAWINGS SUPPLIED BY THE CANOPY COMPANY. ALL MATERIALS SHALL BE EQUAL TO OR BETTER THAN SPECIFIED ELSEWHERE IN THIS SECTION.
- 3.14 PROTECTION OF ALL CONCRETE SURFACES: IT IS THE RESPONSIBILITY OF THE GENERAL CONTRACTOR TO PROTECT ALL CONCRETE SURFACES AGAINST ANY DAMAGE WHATSOEVER, INCLUDING EXCESSIVE LOADING, SHIPPING, CRACKING, STAINING, PAINT SPLATTERS, ETC. THE OWNER EXPECTS EXPOSED CONCRETE SURFACES TO BE CLEAN AND OF UNIFORM COLOR AND TEXTURE AT COMPLETION OF THE PROJECT. REPLACE ANY CONCRETE DAMAGE DURING CONSTRUCTION.
- 3.15 GRADE CONTROL: ESTABLISH AND MAINTAIN LINES AND GRADES FOR CONCRETE ITEMS.

SECTION VI PIPING

PART 1 - GENERAL



- 1.1 SCOPE: THIS SECTION COVERS THE FURNISHING OF ALL LABOR, MATERIALS, SERVICES, EQUIPMENT AND RELATED APPLIANCES REQUIRED IN CONJUNCTION WITH OR INCIDENTAL TO A COMPLETE PLUMBING SYSTEM FOR A GASOLINE INSTALLATION.

PART 2 - PRODUCTS

- 2.1 PRODUCT PIPING: PRODUCT PIPING AND FITTINGS SHALL BE DOUBLE WALL RIGID FIBERGLASS PIPING AS SPECIFIED BY 7-ELEVEN. PIPING MUST SLOPE 1/8" PER FOOT MINIMUM FROM DISPENSER ISLAND TO STP SUMP.
- 2.2 VENT PIPING: PIPING SHALL BE FIBERGLASS PIPE. VENT LINE RISERS SHALL BE GALVANIZED PIPE AND EXTEND 4' ABOVE ADJACENT STRUCTURE OR 12'-0" ABOVE FINISHED GRADE. VENT LINE RISERS SHALL NOT BE INSTALLED ON BUILDING UNLESS APPROVED IN WRITING.
- 2.3 STAGE II VAPOR RECOVER PIPING: PIPING SHALL BE FIBERGLASS. PIPING MUST SLOPE 1/8" PER FOOT MINIMUM FROM DISPENSER ISLAND TO TANK.
- 2.5 BACK FILL: ALL MATERIAL SHALL COMPLY WITH SPECIFICATIONS FOR APPROVED MATERIAL AND AS PER MANUFACTURER'S SPECIFICATIONS.


PART 3 - INSTALLATION

- 3.1 ALL PRODUCT PIPING AND SPECIALTIES SHALL BE INSTALLED IN STRICT ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS AND STATE AND LOCAL CODES.
- 3.2 THE DRAWINGS ARE DIAGRAMMATIC AND THE FINAL ARRANGEMENT OF THE WORK SHALL SUIT FIELD CONDITIONS, THE CHARACTERISTICS OF THE MATERIALS USED, AND THE INSTRUCTIONS OF THE CONSTRUCTION MANAGER. VERIFY ALL DIMENSIONS IN THE FIELD. ACCESS AND CLEARANCES MUST BE PROVIDED AND MAINTAINED FOR THE PROPER OPERATION, MAINTENANCE, SERVICE AND REPAIR OF THE WORK.
- 3.3 LOCATE, IDENTIFY AND MARK EXISTING UNDERGROUND UTILITIES IN THE AREA OF WORK BEFORE STARTING EARTHWORK OPERATIONS. IF UTILITIES ARE TO REMAIN IN PLACE PROVIDE ADEQUATE MEANS OF PROTECTION DURING EARTHWORK PROCEDURES.
- 3.4 SHOULD UNCHARTED OR INCORRECTLY CHARTED PIPING OR OTHER UTILITIES BE ENCOUNTERED DURING EXCAVATION, CONSULT THE CONSTRUCTION MANAGER IMMEDIATELY FOR DIRECTIONS AS TO PROCEDURE. COOPERATE WITH THE OWNER AND PUBLIC AND PRIVATE UTILITY COMPANIES IN KEEPING THEIR RESPECTIVE SERVICES IN SATISFACTORY CONDITION.
- 3.5 VERTICAL RISERS FROM TANKS FOR ALL FILL PIPES, VAPOR RECOVERY ADAPTERS AND AUTO GAUGING ADAPTATIONS SHALL BE A 4" DIAMETER PIPE.
- 3.6 DO NOT INTERRUPT EXISTING UTILITIES SERVING FACILITIES OCCUPIED AND USED BY THE OWNER OR OTHERS, EXCEPT WHEN PERMITTED IN WRITING BY THE CONSTRUCTION MANAGER, AND THE ONLY AFTER ACCEPTABLE TEMPORARY UTILITY SERVICE HAS BEEN PROVIDED.
- 3.7 CONVEY WATER REMOVED FROM EXCAVATIONS AND RAIN WATER TO COLLECTING OR RUN-OFF AREA. DO NOT USE TRENCH EXCAVATIONS FOR SITE UTILITIES AS TEMPORARY DRAINAGE DITCHES. REMOVE ALL TRASH, DEBRIS AND FOREIGN MATERIAL FROM TRENCHES PRIOR TO PLACING PIPING MATERIAL.
- 3.8 ALL PRODUCT, VAPOR RECOVERY AND VENT LINES SHALL SLOPE UP FROM TANKS. A MINIMUM OF 2' IN 8' (1/8" /FT) WITH NO SAG OR TRAPS. LINES SHALL BE IN TRENCHES WITH A MINIMUM OF 6" OF BACK FILL MATERIAL BELOW AND ON EITHER SIDE AND A MINIMUM OF 18" OF BACK FILL MATERIAL ABOVE.
- 3.9 SUBMERGED PUMP, FILL PIPE, AUTO GAUGING ADAPTERS AND VAPOR RECOVERY ADAPTER SHALL BE LOCATED AT TANK OPENINGS AS SHOWN ON DRAWINGS.
- 3.10 FILL PIPE SHALL HAVE OVER SPILL CONTAINMENT SYSTEM INSTALLED AS SHOWN ON DRAWINGS.
- 3.11 FILL PIPE SHALL HAVE SUBMERGED FILL TUBE. FILL PIPE AND VAPOR RECOVERY RISER SHALL BE CUT TO THE PROPER LENGTH SO THAT FINISHED HUB HEIGHT WILL BE WITHIN 5' (+ OR - 1") OF THE TOP OF THE MANHOLE.
- 3.12 OVERFILL PREVENTION DEVICES SHALL BE INSTALLED AS SHOWN IN DRAWINGS.
- 3.13 REMOTE PUMP SHEAR VALVES SHALL BE INSTALLED ON THE PRODUCT LINES UNDER EACH DISPENSER AND SECURED TO THE DISPENSER BOX. THESE VALVES MUST BE INSTALLED WITH THE SHEAR SECTION FLUSH AT THE TOP OF THE DISPENSER SUMP, AS DENOTED ON PLANS.
- 3.14 AFTER ALL PIPING IS COMPLETE AND PRIOR TO BACK FILLING, ALL PIPING INCLUDING VENT LINES SHALL BE ISOLATED FROM THE TANK AND TESTED PER MANUFACTURER'S TESTING INSTRUCTIONS.
- 3.15 IF SUBMERGED, PUMP RISER IS TO BE LENGTHENED, THE PROPER 4" THIN WALL RISER AS PRODUCED BY MANUFACTURER SHALL BE USED.
- 3.16 ALL VALVES AND PRODUCT HANDLING EQUIPMENT SHALL BE AS SHOWN ON EQUIPMENT LIST. REFER TO LIST OF MATERIALS SUPPLIED BY OWNER.
- 3.17 OBSERVATION WELLS WHEN REQUIRED SHALL BE INSTALLED. WELLS ARE TO BE POSITIONED IN EXCAVATION HOLE PRIOR TO PLACING BEDDING MATERIAL AND SUPPORTED TO REMAIN VERTICAL DURING BACK FILL OPERATIONS. BOTTOM OF OBSERVATION WELL(S) SHALL BE 12" MINIMUM BELOW THE BOTTOM OF TANK EXCAVATION PIT. TOP OF PIPE TO TERMINATE IN 12" DIAMETER OBSERVATION BOX. SLOTTED SAMPLE WELL MATERIAL SHALL BE FURNISHED BY CONTRACTOR. LOCKING CAPS AND KEYED ALIKE LOCKS PROVIDED TO 7-ELEVEN, INC. REPRESENTATIVE.
- 3.18 CODES: THE NFPA 30 FLAMMABLE AND COMBUSTIBLE LIQUIDS CODE, & NFPA 30A AUTOMOBILE AND MARINE SERVICE STATION CODE. IS BY REFERENCE MADE A PART OF THIS SPECIFICATION. SAID CODE SHALL DICTATE MINIMUM ACCEPTABLE STANDARDS. CODE SHALL BE ADHERED TO UNLESS LOCAL GOVERNING AUTHORITIES DICTATE HIGHER OR MORE STRINGENT REQUIREMENTS WHICH
- 3.19 STARTUP: PRIOR TO STARTUP AND CHECK-OUT OF SYSTEM, PRODUCT LINES SHALL PASS HYDROSTATIC LINE TEST. ALL SITE IMPROVEMENTS, INCLUDING PAVEMENTS AND UTILITIES, SHALL BE COMPLETED PRIOR TO THIS TEST.
- 3.20 INSPECTIONS: PLUMBING INSPECTION SHALL BE PERFORMED BY 7-ELEVEN, INC.'S APPOINTED REPRESENTATIVE.
- 3.21 CLEANUP: CLEANUP ALL DEBRIS CAUSED BY THE WORK OF THIS SECTION, KEEPING THE PREMISES CLEAN AND NEAT AT ALL TIMES.



Job#: SEI-16380.0222
Scale: AS NOTED
Date: 01/21/16
Drawn By: JMR
Checked By: CPS

Documents prepared by Core States Group are to be used for specific use for which they are intended. Any extension of use to other projects, by owner or expressed, written consent of Core States Group is required. No other use than specifically intended, user will hold Core States Group harmless from all claims and losses.



SHEET:
G15
FUELING - USA