



**MANUAL RELEASE STATION WIRING DETAIL**

**CAUSE AND EFFECT MATRIX**

INPUTS/EVENT	Panel Alarm Tone & LED	Panel Trouble Tone & LED	Agent Release	Onboard Relay 1	Onboard Relay 2	Onboard Relay 3
Manual Pull Station - Canopy	X		X		X	X
Heat Sensor - Canopy	X		X		X	X
System Fault		X		X		

**ELECTRICAL EQUIPMENT INSTALLATION NOTES**

1. A RPS-E2 REMOTE ELECTRICAL PULL STATION SHALL BE LOCATED AT THE POINT OF SALE, WITH FULL VIEW OF THE PROTECTED GASOLINE DISPENSERS.

**WIRING NOTES**

1. THE POWER SOURCE FOR THE Z-10 RELEASING PANEL CONTROLLED GAS ISLAND FIRE SYSTEM MUST BE A DEDICATED 120 VAC CIRCUIT USED ONLY FOR THIS PURPOSE. THE BREAKER SHALL BE LABELED.
2. ALL SYSTEM WIRING SHALL BE 14 AWG MINIMUM.
3. THE DISPENSER SHUT DOWNS SHALL BE A SHUNT TRIP BREAKER OR LATCHING STYLE RELAY.

**PANEL INSTALLATION NOTES**

1. THE AUTOPULSE Z-10 PANEL SHALL BE INSTALLED IN AN ENVIRONMENT WITH NOMINAL ROOM TEMPERATURES OF 15° - 27° C/ 60° - 80° F AND A RELATIVE HUMIDITY OF NO MORE THAN 85%.
2. POWER-LIMITED AND NON-POWER-LIMITED CONDUCTORS SHALL BE SEPARATED AS DETAILED IN THESE DRAWINGS. BUNDLE, LACE, AND TRAIN CONDUCTORS TO THE PANEL TERMINAL POINTS WITH NO EXCESS.
3. ALL CONDUCTORS SHALL BE COLOR CODED AND NUMBERED AT THE TERMINATION POINTS AS SHOWN ON THE PANEL WIRING DETAIL ON THIS SHEET. SEE WIRING NOTES FOR CONDUCTOR SIZE.
4. ALL PENETRATIONS THROUGH WALLS FOR CONDUITS, ETC. SHALL BE SEALED WITH APPROVED FIRE-STOPPING MATERIAL.
5. THE AUTOPULSE Z-10 SYSTEM CONTROL ALARM PANEL SHALL BEAR A LABEL STATING: "GAS ISLAND FIRE SYSTEM CONTROL PANEL".
6. PROGRAMMING OF THE AUTOPULSE Z-10 PANEL SHALL BE PERFORMED BY A FACTORY AUTHORIZED DISTRIBUTOR AND INSTALLER OF PYRO-CHEM, INC. PRODUCTS.
7. UPON COMPLETION OF INSTALLATION EACH INPUT DEVICE AND OUTPUT DEVICE SHALL BE TESTED IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS TO VERIFY PROPER OPERATION.

SELF-SERVE EXTINGUISHING SYSTEM SHALL BE INSTALLED FROM AND IN ACCORDANCE WITH STATE FIRE MARSHALL APPROVED PLANS. ALL EXTINGUISHING SYSTEMS, DISPENSING SYSTEMS AND CONTROL EQUIPMENT SHALL BE UNDERWRITERS LABORATORY LISTED (UL).

- NOTES:**
1. THE INFORMATION AND GRAPHIC DEPICTIONS ON THIS DRAWING ARE DERIVED FROM PYRO-CHEM, INC. DOCUMENT NUMBER 430545 TITLED "AUTOPULSE Z-10 AGENT RELEASE CONTROL SYSTEM INSTALLATION MANUAL" PART NUMBER 579-357, REV. G.
  2. THE AUTOPULSE Z-10 CONTROL PANEL PROGRAMMING SHALL BE FULLY TESTED.

**System Information:**  
 PYRO-CHEM ATTENDANT II UL 1254 DRY CHEMICAL FIRE SUPPRESSION SYSTEM PROTECTING A SELF-SERVICE GASOLINE FUELING FACILITY

**Owner/Site:**  
 7-ELEVEN INC.  
 7-ELEVEN #32541  
 1917 FOREST AVENUE  
 PORTLAND, ME 04101

**Interstate FIRE PROTECTION**  
 P.O. BOX 1005  
 NORTH CONWAY, NH 03860  
 P.O. BOX 187  
 GARDINER, ME 04345

**PYRO-CHEM GAS ISLAND FIRE SUPPRESSION SYSTEM ELECTRICAL PLAN**

Proj. no.:  
 CAD File:7-11ForestAvePortME.dwg  
 Drawn By:M. STEWARD  
 Created on:02/16/2016  
 Designed by:M. STEWARD  
 Checked by:B. TWOMBLY  
 Approved by:B. TWOMBLY  
 Project Lead:J. MOONEY  
 Scale:AS NOTED

Revisions: Date:  
 ii 02/16/2016

SHEET :  
 03