

OFFICE OF  
  
STATE FIRE MARSHAL

CALIFORNIA DEPARTMENT OF FORESTRY and FIRE PROTECTION  
OFFICE OF THE STATE FIRE MARSHAL

**REGISTERED FLAME RESISTANT PRODUCT**

Product:

PRECONTRAIINT 702 BLACKOUT

Registration No.

F-11408

Product Marketed By:

FERRARI SA  
BX54, 38352 LA TOUR DU PIN  
LA TOUR DU PIN, FRANCE

This product meets the minimum requirements of flame resistance established by the California State Fire Marshal for products identified in Section 13115, California Health and Safety Code.

The scope of the approved use of this product is provided in the current edition of the CALIFORNIA APPROVED LIST OF FLAME RETARDANT CHEMICALS AND FABRICS, GENERAL AND LIMITED APPLICATIONS CONCERNS published by the California State Fire Marshal.

*Pat Sweeney*


Deputy State Fire Marshal

FR-8



PRINTED ON REGENESIS® POST CONSUMER RECYCLED PAPER





**DIVERSIFIED**  
**TESTING LABORATORIES, INC.**

"We Test Per Your Request"

336 WEST FRONT STREET  
P.O. BOX 4004  
BURLINGTON, NORTH CAROLINA 27215  
Phone (336) 227-7710 • Fax (336) 227-1175

Ms. Catherine MERILLON  
FERRARI SA  
BP 54  
38352 La Tour Du Pin Cedex  
La Mure, France

Reference: Laboratory Test Report  
Lab Identification No. 5349  
Invoice No. 8270 (Attached)

Dear Ms. MERILLON:

One (1) fabric sample, identified as PRECONTRAINMENT 702, was received and tested in accordance with the National Fire Prevention Association No. 701, "Flame Propagation of Textiles and Films, 1999 Edition, (Test 2, Large Scale)". The results are as follows:

<u>Specimen Number</u>	<u>Afterflame (seconds)</u>	<u>Residual Flame (seconds)</u>	<u>Char Length (inches)</u>
Single 1	0.0	0.0	10.0
Flat 2	0.0	0.0	11.0
Specimen 3	0.0	0.0	11.0
4	0.0	0.0	10.0
5	0.0	0.0	10.0
6	0.0	0.0	10.0
7	0.0	0.0	12.0
8	0.0	0.0	7.0
9	0.0	0.0	10.0
10	0.0	0.0	8.0

The sample submitted meets the minimum requirements of the above standard. The length of char on the individual single flat specimens shall not exceed 17.1 inches. Additionally, no specimen shall continue flaming for more than two (2) seconds after the test flame is removed and no residues shall fall to the floor of the test chamber and continue flaming for more than two (2) seconds at any time during the test.

If there are any questions or when we can be of further assistance, please let us know.

Sincerely,  
  
Karen S. Matkins

KSM/mr  
Attachment

OUR LETTERS AND REPORTS ARE FOR THE EXCLUSIVE USE OF THE CLIENT TO WHOM THEY ARE ADDRESSED. ANY COMMUNICATION TO OTHERS OR THE USE OF OUR COMPANY NAME MUST RECEIVE PRIOR APPROVAL. OUR TEST RESULTS APPLY ONLY TO THE SAMPLE TESTED AND ARE NOT NECESSARILY INDICATIVE OF THE QUALITIES OF APPARENTLY IDENTICAL OR SIMILAR PRODUCTS. SAMPLES NOT DESTROYED IN TESTING ARE RETAINED A MAXIMUM OF THIRTY DAYS. THE LETTERS, REPORTS OR NAME OF DIVERSIFIED TESTING LABORATORIES, INC. MAY NOT BE USED IN ADVERTISING TO THE GENERAL PUBLIC.