

Form # P 04

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK CITY OF PORTLAND

Please Read Application And Notes, if Any, Attached

BUILDING PERMIT

PERMIT ISSUED
Permit Number: 100461
MAY 24 2010
CITY OF PORTLAND

This is to certify that WOODWORKING & CABINETS LLC / Grinnell

has permission to install a water-based fire suppression system

AT 225 INDUSTRIAL WAY

CB# 329 A007001

provided that the person or persons, firm or corporation accounting for this permit shall comply with all of the provisions of the Statutes of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of buildings and structures, and of the application on file in this department.

Apply to Public Works for street line and grade if nature of work requires such information.

Notification of inspection must be given and written permission procured before this building or part thereof is lathed or otherwise finished-in. 24 HOUR NOTICE IS REQUIRED.

A certificate of occupancy must be procured by owner before this building or part thereof is occupied.

OTHER REQUIRED APPROVALS

Fire Dept. CAPT. R. Sawhear

Health Dept. _____

Appeal Board _____

Other _____
Department Name

[Handwritten Signature]
Director - Building & Inspection Services

PENALTY FOR REMOVING THIS CARD


City of Portland, Maine - Building or Use Permit Application
 389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716

Permit No: 10-0461	Issue Date:	CBL: 329 A007001
-----------------------	-------------	---------------------

Location of Construction: 225 INDUSTRIAL WAY	Owner Name: WOODWORKING & CABINETRY	Owner Address: 40 PORTLAND PIER # 11	Phone:
Business Name:	Contractor Name: Simplex / Grinnell	Contractor Address: 20 Thomas Drive Westbrook	Phone: 2078426440
Lessee/Buyer's Name	Phone:	Permit Type: Fire Suppression System	<i>Zoning</i> <i>2-1M</i>

Past Use: Commercial	Proposed Use: Commercial - install a water-based fire suppression system	Permit Fee: \$320.00	Cost of Work: \$30,000.00	CEO District: 5
Proposed Project Description: install a water-based fire suppression system <i>legal use: light manufacturing</i>		FIRE DEPT: <input checked="" type="checkbox"/> Approved <input type="checkbox"/> Denied <i>* See Conditions</i>	INSPECTION: Use Group: <i>U</i> Type: <i>Fire Supp.</i>	
		Signature: <i>(KC)</i>	Signature: <i>[Signature]</i>	
PEDESTRIAN ACTIVITIES DISTRICT (P.A.D.)				
Action: <input type="checkbox"/> Approved <input type="checkbox"/> Approved w/Conditions <input type="checkbox"/> Denied				
Signature: _____ Date: _____				

Permit Taken By: ldobson	Date Applied For: 05/03/2010 <i>5/5/10</i>	Zoning Approval		
1. This permit application does not preclude the Applicant(s) from meeting applicable State and Federal Rules. 2. Building permits do not include plumbing, septic or electrical work. 3. Building permits are void if work is not started within six (6) months of the date of issuance. False information may invalidate a building permit and stop all work..		Special Zone or Reviews <input type="checkbox"/> Shoreland <input type="checkbox"/> Wetland <input type="checkbox"/> Flood Zone <input type="checkbox"/> Subdivision <input type="checkbox"/> Site Plan Maj <input checked="" type="checkbox"/> Minor <input type="checkbox"/> MM <input type="checkbox"/> Date: <i>5/5/10</i>	Zoning Appeal <input type="checkbox"/> Variance <input type="checkbox"/> Miscellaneous <input type="checkbox"/> Conditional Use <input type="checkbox"/> Interpretation <input type="checkbox"/> Approved <input type="checkbox"/> Denied Date: _____	Historic Preservation <input checked="" type="checkbox"/> Not in District or Landmark <input type="checkbox"/> Does Not Require Review <input type="checkbox"/> Requires Review <input type="checkbox"/> Approved <input type="checkbox"/> Approved w/Conditions <input type="checkbox"/> Denied Date: _____



CERTIFICATION

I hereby certify that I am the owner of record of the named property, or that the proposed work is authorized by the owner of record and that I have been authorized by the owner to make this application as his authorized agent and I agree to conform to all applicable laws of this jurisdiction. In addition, if a permit for work described in the application is issued, I certify that the code official's authorized representative shall have the authority to enter all areas covered by such permit at any reasonable hour to enforce the provision of the code(s) applicable to such permit.

SIGNATURE OF APPLICANT	ADDRESS	DATE	PHONE
RESPONSIBLE PERSON IN CHARGE OF WORK, TITLE		DATE	PHONE

City of Portland, Maine - Building or Use Permit

389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716

Permit No: 10-0461	Date Applied For: 04/30/2010	CBL: 329 A007001
------------------------------	--	----------------------------

Location of Construction: 225 INDUSTRIAL WAY	Owner Name: WOODWORKING & CABINETRY	Owner Address: 40 PORTLAND PIER # 11	Phone:
Business Name:	Contractor Name: Simplex / Grinnell	Contractor Address: 20 Thomas Drive Westbrook	Phone (207) 842-6440
Lessee/Buyer's Name	Phone:	Permit Type: Fire Suppression System	

Proposed Use: Commercial -light manufacturing - install a water-based fire suppression system	Proposed Project Description: install a water-based fire suppression system
---	---

Dept: Zoning **Status:** Approved **Reviewer:** Marge Schmuckal **Approval Date:** 05/05/2010
Note: **Ok to Issue:** ✓

Dept: Building **Status:** Approved **Reviewer:** Tammy Munson **Approval Date:** 05/20/2010
Note: **Ok to Issue:** ✓

Dept: Fire **Status:** Approved with Conditions **Reviewer:** Capt Keith Gautreau **Approval Date:** 05/11/2010
Note: **Ok to Issue:** ✓

- 1) The Fire Department will require knock locking caps on all Fire Department Connections on the exterior of the building.
- 2) Sprinkler protection shall be maintained.
Where the system is to be shut down for maintenance or repair, the system shall be checked at the end of each day to insure the system has been placed back in service.
- 3) The Fire alarm and Sprinkler systems shall be reviewed by a licensed contractor[s] for code compliance.
Compliance letters are required.
- 4) The sprinkler system shall be installed in accordance with NFPA 13.
- 5) Application requires State Fire Marshal approval.
- 6) Fire department connection type and location shall be approved in writing by fire prevention bureau.
- 7) System acceptance and commissioning must be co-ordinated with alarm and suppression system contractors and the Fire Department. Call 874-8703 to schedule.

BUILDING PERMIT INSPECTION PROCEDURES

Please call 874-8703 or 874-8693 (ONLY)

or email: buildinginspections@portlandmaine.gov

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the City of Portland Inspection Services for the following inspections. Appointments must be requested 48 to 72 hours in advance of the required inspection. The inspection date will need to be confirmed by this office.

- **Please read the conditions of approval that is attached to this permit!! Contact this office if you have any questions.**
- **Permits expire in 6 months, if the project is not started or ceases for 6 months.**
- **If the inspection requirements are not followed as stated below additional fees may be incurred due to the issuance of a “Stop Work Order” and subsequent release to continue with construction.**

 X **Final inspection required at by the fire department upon completion of work.**

The project cannot move to the next phase prior to the required inspection and approval to continue, REGARDLESS OF THE NOTICE OR CIRCUMSTANCES.

IF THE PERMIT REQUIRES A CERTIFICATE OF OCCUPANCY, IT MUST BE PAID FOR AND ISSUED TO THE OWNER OR DESIGNEE BEFORE THE SPACE MAY BE OCCUPIED.



CITY OF PORTLAND, MAINE
 Department of Building Inspections

Original Receipt

5.3 20 10

Received from Jennifer Dowd

Location of Work 225 Industrial

Cost of Construction \$ _____ Building Fee: _____

Permit Fee \$ _____ Site Fee: _____

Certificate of Occupancy Fee: _____

Total: 320

Building (IL) _____ Plumbing (IS) _____ Electrical (I2) _____ Site Plan (U2) _____

Other: Fire

CBL: 326 A-7

Check #: CC Total Collected \$ 320

**No work is to be started until permit issued.
 Please keep original receipt for your records.**

Taken by: S. J. D.

WHITE - Applicant's Copy
 YELLOW - Office Copy
 PINK - Permit Copy



Water-Based Fire Suppression System Permit

If you or the property owner owes real estate or property taxes or user charges on any property within the city, payment arrangements must be made before permits of any kind are accepted.

Installation address: 225 INDUSTRIAL WAY CBL: 329-A-7

Exact location: (within structure) NEW ADDITION ONLY

Type of occupancy(s) (NFPA & ICC): WOOD WORKING / RETAIL

Building owner: WALT DEKKO

Managing Supervisor (RMS): TOD PRAY License No: 389

Supervisor phone: 842-6440 E-mail: PDOUGHTY@SIMPLEXGRINNELL.COM

Installing contractor: SIMPLEXGRINNELL License No: 398

Contractor phone: _____ E-mail: SAME AS ABOVE

The suppression work to be done will be: New: Renovation: Addition to existing system:

This is an amendment to an existing permit: Yes: NO: Permit no: _____

NFPA Standard this system is designed to: 13 Edition: 2007

*Non-NFPA systems are not approved for use within the City of Portland.

Download a new copy of this document from www.portlandmaine.gov/fire for every submittal. Attach all working documents and complete approved submittals as may be required by the State Fire Marshal's Office on electronic PDF's in addition to full sized plans.

Contractor shall verify location and type of all FDCs shall be approved in writing by the Fire Prevention Bureau.

<p>COST OF WORK: <u>30,000.00</u></p> <p>PERMIT FEE: <u>300.00</u></p> <p>(\$10 PER \$1,000 + \$30 FOR THE FIRST \$1,000)</p> <p>RECEIVED</p> <p>APR 30 2010</p> <p>Dept. of Building Inspections City of Portland Maine</p>

Submit all information to the Building Inspections Department, 389 Congress Street, Room 315, Portland, Maine 04101.

Prior to acceptance of any fire protection system, a complete commissioning and acceptance test must be coordinated with all fire system contractors and the Fire Department, and proper documentation of such test(s) provided.

All installation(s) must comply with NFPA and the Fire Department Technical Standard(s).

Applicant signature: [Signature] Date: 4/29/10



State of Maine
Department of Public Safety



Fire Sprinkler System Permit

8379

Dekko LLC

Located at: 225 Industrial Way
In the Town of: Portland
Occupancy/Use: Wood working/ Retail
Type of System: NFPA 13

Permission is hereby given to:

Simplex Grinnell
20 Thomas Drive
Westbrook, ME 04092
Contractor License # 398

according to plans submittal filed with the Licensing and Inspections Unit and are now approved. This application form/plans are filed under log # 2081449 , and no departure from application form/plans shall be made without prior approval in writing. This permit is issued under the provisions of Title 32, Chapter 20, Section 12004-I. Nothing herein shall excuse the holder of this permit for failure to comply with local ordinances, zoning laws, or other pertinent legal restrictions. Each permit issued shall be displayed/available at the site of construction.

This permit was issued on 11/6/2008 for a fee paid of \$100.00

This permit will expire at midnight on Tuesday, May 05, 2009

Anne H. Jordan
Commissioner

Fire Department Connection Location/Type per Local Fire Department

Within 30 days of the completion of a new fire sprinkler system or an addition to an existing fire sprinkler system, a fire sprinkler system contractor shall provide to the Licensing and Inspections Unit a copy of this permit signed and dated by the certified responsible managing supervisor representing that the fire sprinkler system has been installed according to specifications of the approved plan to the best of the supervisor's knowledge, information, and belief. This requirement is part of the sprinkler law, and neglect of this duty is grounds to not renew the contractor's license to do work in the State of Maine. All sprinkler licenses expire June 30th every year.

Job completed, tested and verified on date of

4/13/09

RMS for this job: Pray Tod P.

RMS Signature:

SimplexGrinnell BE SAFE.

A Tyco International Company

SimplexGrinnell LP
20 Thomas Drive
Westbrook, ME 04092

P: 207-842-6440
F: 207-482-2358
www.simplexgrinnell.com

Date: 4/23/10

To: Capt. Keith Gaudreau
Portland Fire Department


Re: 225 Industrial Way
Portland, Me.04101

Compliance Letter

The dry type sprinkler system at 225 Industrial Way, Portland Maine was designed, installed and tested in accordance with NFPA 13, 2007 edition. We received approval from the "Office of State Fire Marshal" and they issued the permit on 11/6/2008 (Permit #8379).

Regards,

Tod Pray
Designer/NICET III
District 147



... Fire Protection by Computer Design

Simplex Grinnell
Col. Westbrook Exec. Park
20 Thomas Drive
Westbrook, Me. 04092
207-842-6440

Job Name : DEKKO, LLC
Building : METAL BUTLER BLDG
Location : SPACE #3
System : DRY
Contract : 939361501
Data File : DEKKO LLC- DRY-GROUP II.WXF

Hydraulic Design Information Sheet

Name - DEKKO LLC Date - 10/23/08
 Location - SPACE #3
 Building - METAL BUTLER BLDG System No. - DRY
 Contractor - SIMPLEXGRINNELL LP Contract No. - 939361501
 Calculated By - T. PRAY Drawing No. - 1 OF 1
 Construction: () Combustible (X) Non-Combustible Ceiling Height - VARIES
 Occupancy - MISC. ORDINARY GROUP II USAGE (WOOD SHOP/RETAIL)

S (XX) NFPA 13 () Lt. Haz. Ord.Haz.Gp. () 1 (X) 2 () 3 () Ex.Haz.
 Y () NFPA 231 () NFPA 231C (X) Figure 11.2.3.1.1 Curve ORDINARY 1

S Other
 T Specific Ruling Made By Date

M	Area of Sprinkler Operation	- 2031	System Type	Sprinkler/Nozzle
	Density	- .2	() Wet	Make TYCO
D	Area Per Sprinkler	- 110	(X) Dry	Model TY-FRB
E	Elevation at Highest Outlet	- 120.33	() Deluge	Size 1/2"
S	Hose Allowance - Inside	-	() Preaction	K-Factor 5.6
I	Rack Sprinkler Allowance	-	() Other	Temp.Rat.155
G	Hose Allowance - Outside	- 250		

N
 Note

Calculation Flow Required - 737.78 Press Required - 78.76 AT TEST
 Summary C-Factor Used: 100 Overhead 140 Underground

W	Water Flow Test:	Pump Data:	Tank or Reservoir:
A	Date of Test - 9/25/08		Cap. -
T	Time of Test - N/A	Rated Cap.-	Elev.-
E	Static Press - 86	@ Press -	
R	Residual Press - 78	Elev. -	Well
	Flow - 2250		Proof Flow
S	Elevation - 101.0'		

U
 P Location - FLOW HYD. (HYD #1713) LOCATED ON EVERGREEN DR. IN FRONT OF BLDG AND
 P TEST HYD (HYD #1714) IS LOCATED NORTH OF BLDG ON EVERGREEN DR.
 L Source of Information - PORTLAND WATER DISTRICT
 Y

C	Commodity	Class	Location
O	Storage Ht.	Area	Aisle W.
M	Storage Method: Solid Piled	%	Palletized % Rack
M	() Single Row	() Conven. Pallet	() Auto. Storage () Encap.
S	() Double Row	() Slave Pallet	() Solid Shelf () Non
T	() Mult. Row		() Open Shelf

R K Flue Spacing Clearance: Storage to Ceiling
 A Longitudinal Transverse

G
 E Horizontal Barriers Provided:


Water Supply Curve (C)

Simplex Grinnell
DEKKO, LLC

Page 2
Date 9/22/08

City Water Supply:
C1 - Static Pressure : 86
C2 - Residual Pressure: 78
C2 - Residual Flow : 2250

Demand:
D1 - Elevation : 8.372
D2 - System Flow : 487.775
D2 - System Pressure : 78.762
Hose (Adj City) :
Hose (Demand) : 250
D3 - System Demand : 737.775
Safety Margin : 6.221



Fitting Legend
Abbrev. Name

D	Generic Dry Pipe Valve	0	0	0	0	0	0	9.5	17	0	28	0	47	0	0	0	0	0	0	0	0
G	Generic Gate Valve	0	0	0	0	0	1	1	1	1	2	2	3	4	5	6	7	8	10	11	13
I	90° Grvd-Vic Elbow #10	0	0	2	3	4	3.5	6	5	8	7	8.5	10	13	17	20	23	25	33	36	40
L	Long Turn Elbow	1	1	2	2	2	3	4	5	5	6	8	9	13	16	18	24	27	30	34	40
T	90° Flow thru Tee	3	4	5	6	8	10	12	15	17	20	25	30	35	50	60	71	81	91	101	121
W	Generic Wafer Check Valve	0	0	0	0	0	0	0	0	0	10.3	0	13.1	31.8	35.8	27.4	0	0	0	0	0

Pressure / Flow Summary - STANDARD

Simplex Grinnell
DEKKO, LLC

Page 4
Date 9/22/08

Node No.	Elevation	K-Fact	Pt Actual	Pn	Flow Actual	Density	Area	Press Req.
1	120.33	8	7.56	na	22.0	0.2	110	7.56
2	120.33	8	7.75	na	22.28	0.2	110	7.56
3	120.33	8	8.45	na	23.25	0.2	110	7.56
4	120.33	8	9.97	na	25.26	0.2	110	7.56
5	120.33	8	12.71	na	28.52	0.2	110	7.56
6	120.33	8	7.67	na	22.16	0.2	110	7.56
7	120.33	8	7.87	na	22.44	0.2	110	7.56
8	120.33	8	8.57	na	23.42	0.2	110	7.56
9	120.33	8	10.11	na	25.44	0.2	110	7.56
10	120.33	8	12.89	na	28.72	0.2	110	7.56
11	120.33	8	8.07	na	22.73	0.2	110	7.56
12	120.33	8	8.28	na	23.01	0.2	110	7.56
13	120.33	8	9.02	na	24.02	0.2	110	7.56
14	120.33	8	10.63	na	26.08	0.2	110	7.56
15	120.33	8	13.54	na	29.43	0.2	110	7.56
16	120.33	8	12.49	na	28.27	0.2	110	7.56
17	120.33	8	12.79	na	28.61	0.2	110	7.56
18	120.33	8	13.9	na	29.82	0.2	110	7.56
19	120.33	8	16.31	na	32.31	0.2	110	7.56
30	116.83		21.04	na				
31	116.83		21.31	na				
32	116.83		22.29	na				
33	116.83		24.4	na				
TOR	105.0		72.25	na				
DPV	101.0		76.93	na				
CON	101.0		78.05	na				
TEST	101.0		78.76	na	250.0			

The maximum velocity is 19.46 and it occurs in the pipe between nodes 33 and TOR

Final Calculations - Hazen-Williams

Simplex Grinnell
DEKKO, LLC

Page 5
Date 9/22/08

Hyd. Ref. Point	Qa Qt	Dia. "C" Pf/Ft	Fitting or Eqv.	Ln.	Pipe Ftng's Total	Pt Pe Pf	Pt Pv Pn	*****	Notes	*****
1	22.00	1.682		0.0	8.750	7.562			K Factor = 8.00	
to		100		0.0	0.0	0.0				
2	22.0	0.0218		0.0	8.750	0.191			Vel = 3.18	
2	22.28	1.682		0.0	8.750	7.753			K Factor = 8.00	
to		100		0.0	0.0	0.0				
3	44.28	0.0797		0.0	8.750	0.697			Vel = 6.39	
3	23.25	1.682		0.0	8.750	8.450			K Factor = 8.00	
to		100		0.0	0.0	0.0				
4	67.53	0.1737		0.0	8.750	1.520			Vel = 9.75	
4	25.26	1.682		0.0	8.750	9.970			K Factor = 8.00	
to		100		0.0	0.0	0.0				
5	92.79	0.3128		0.0	8.750	2.737			Vel = 13.40	
5	28.52	1.682	1I	3.533	2.670	12.707			K Factor = 8.00	
to		100	1T	7.065	10.599	1.516				
30	121.31	0.5135		0.0	13.269	6.814			Vel = 17.52	
	0.0									
	121.31					21.037			K Factor = 26.45	
6	22.16	1.682		0.0	8.750	7.673			K Factor = 8.00	
to		100		0.0	0.0	0.0				
7	22.16	0.0221		0.0	8.750	0.193			Vel = 3.20	
7	22.44	1.682		0.0	8.750	7.866			K Factor = 8.00	
to		100		0.0	0.0	0.0				
8	44.6	0.0807		0.0	8.750	0.706			Vel = 6.44	
8	23.42	1.682		0.0	8.750	8.572			K Factor = 8.00	
to		100		0.0	0.0	0.0				
9	68.02	0.1761		0.0	8.750	1.541			Vel = 9.82	
9	25.44	1.682		0.0	8.750	10.113			K Factor = 8.00	
to		100		0.0	0.0	0.0				
10	93.46	0.3169		0.0	8.750	2.773			Vel = 13.49	
10	28.72	1.682	1I	3.533	2.670	12.886			K Factor = 8.00	
to		100	1T	7.065	10.599	1.516				
31	122.18	0.5203		0.0	13.269	6.904			Vel = 17.64	
	0.0									
	122.18					21.306			K Factor = 26.47	
11	22.73	1.682		0.0	8.750	8.073			K Factor = 8.00	
to		100		0.0	0.0	0.0				
12	22.73	0.0232		0.0	8.750	0.203			Vel = 3.28	
12	23.02	1.682		0.0	8.750	8.276			K Factor = 8.00	
to		100		0.0	0.0	0.0				
13	45.75	0.0846		0.0	8.750	0.740			Vel = 6.61	
13	24.02	1.682		0.0	8.750	9.016			K Factor = 8.00	
to		100		0.0	0.0	0.0				
14	69.77	0.1845		0.0	8.750	1.614			Vel = 10.07	
14	26.08	1.682		0.0	8.750	10.630			K Factor = 8.00	
to		100		0.0	0.0	0.0				
15	95.85	0.3322		0.0	8.750	2.907			Vel = 13.84	
15	29.43	1.682	1I	3.533	2.670	13.537			K Factor = 8.00	
to		100	1T	7.065	10.599	1.516				
32	125.28	0.5450		0.0	13.269	7.232			Vel = 18.09	

Final Calculations - Standard

Simplex Grinnell
DEKKO, LLC

Page 6
Date 9/22/08

Hyd. Ref. Point	Qa Qt	Dia. "C" Pf/Ft	Fitting or Eqv. Ln.	Pipe Ftng's Total	Pt Pe Pf	Pt Pv Pn	*****	Notes	*****
	0.0 125.28					22.285		K Factor = 26.54	
16 to 17	28.27 28.27	1.682 100 0.0347	0.0 0.0 0.0	8.750 0.0 8.750	12.485 0.0 0.304			K Factor = 8.00 Vel = 4.08	
17 to 18	28.61 56.88	1.682 100 0.1265	0.0 0.0 0.0	8.750 0.0 8.750	12.789 0.0 1.107			K Factor = 8.00 Vel = 8.21	
18 to 19	29.82 86.7	1.682 100 0.2758	0.0 0.0 0.0	8.750 0.0 8.750	13.896 0.0 2.413			K Factor = 8.00 Vel = 12.52	
19 to 33	32.31 119.01	1.682 100 0.4957	1I 1T 0.0	3.533 7.065 13.269	2.670 10.599 6.577	16.309 1.516		K Factor = 8.00 Vel = 17.18	
	0.0 119.01					24.402		K Factor = 24.09	
30 to 31	121.31 121.31	3.2 100 0.0223	0.0 0.0 0.0	12.040 0.0 12.040	21.037 0.0 0.269			Vel = 4.84	
31 to 32	122.18 243.49	3.2 100 0.0813	0.0 0.0 0.0	12.040 0.0 12.040	21.306 0.0 0.979			Vel = 9.71	
32 to 33	125.28 368.77	3.2 100 0.1752	0.0 0.0 0.0	12.080 0.0 12.080	22.285 0.0 2.117			Vel = 14.71	
33 to TOR	119.01 487.78	3.2 100 0.2939	1I 1T 0.0	4.381 13.143 145.363	127.840 17.523 42.728	24.402 5.124		Vel = 19.46	
TOR to DPV	0.0 487.78	4.26 100 0.0730	1D 0.0 0.0	26.313 26.313 40.313	14.000 1.732 2.942	72.254		Vel = 10.98	
DPV to CON	0.0 487.78	4.026 120 0.0686	1W 1G 0.0	10.3 2.0 16.300	4.000 12.300 1.118	76.928 0.0		Vel = 12.29	
CON to TEST	0.0 487.78	6.16 140 0.0065	1L 1G 1T	12.911 4.304 43.037	50.000 60.252 110.252	78.046 0.0 0.716		Vel = 5.25	
	250.00 737.78					78.762		Qa = 250.00 K Factor = 83.13	

CONTRACTOR'S MATERIAL & TEST CERTIFICATE FOR A ABOVEGROUND PIPING

Additional copies of this form are available to insureds from:

Corporate Communications - Training Resource Center
FM Global, 1151 Boston-Providence Turnpike, P.O. Box 9102, Norwood MA 02062

PROCEDURE:

Upon completion of work, inspection and tests shall be made by the contractor's representative and witnessed by an owner's representative. All defects shall be corrected and system left in service before contractor's personnel finally leave the job.

A certificate shall be filled out and signed by both representatives. Copies shall be prepared for approving authorities, owners and contractor. It is understood the owner's representative's signature in no way prejudices any claim against the contractor for faulty material, poor workmanship, or failure to comply with approving authority's requirements or local ordinances.

PROPERTY NAME	DEKKO LLC					DATE	4-26-10				
PROPERTY ADDRESS	225 Industrial way Portland me 04101										
PLANS	ACCEPTED BY APPROVING AUTHORITY(S) NAMES STATE FIRE MARSHALS OFFICE										
	ADDRESS 45 COMMERCE DRIVE, SUITE 1, AUGUSTA, ME 04333										
	INSTALLATION CONFORMS TO ACCEPTED PLANS <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO										
	EQUIPMENT USED IS APPROVED IF NO. STATE DEVIATIONS BELOW <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO										
INSTRUCTIONS	HAS PERSON IN CHARGE OF FIRE EQUIPMENT BEEN INSTRUCTED AS TO LOCATION OF CONTROL VALVES AND THE CARE AND MAINTENANCE OF THIS NEW EQUIPMENT? <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO IF NO, EXPLAIN:										
	HAVE COPIES OF APPROPRIATE INSTRUCTIONS AND CARE AND MAINTENANCE CHARTS BEEN LEFT ON PREMISES? <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO IF NO, EXPLAIN:										
LOCATION OF SYSTEM	SUPPLIES BUILDINGS 6" D.I.C.L ENTERS SOUTH-EAST SIDE OF BLDG, SUPPLIES ENTIRE BLDG										
SPRINKLERS	MAKE		MODEL		YEAR OF MANUFACTURE		ORIFICE SIZE		QUANTITY		TEMPERATURE RATING
	TYCO		TY-FRB		2007		3/4"		70		155
	TYCO		TY-FRB		2007		2"		3		155
PIPE AND FITTINGS	PIPE CONFORMS TO <u>NFPA 13</u> STANDARD <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO										
	FITTINGS CONFORM TO <u>NFPA 13</u> STANDARD <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO IF NO, EXPLAIN:										
ALARM VALVE OR FLOW INDICATOR	ALARM DEVICE					MAXIMUM TIME TO OPERATE THROUGH TEST PIPE					
	TYPE		MAKE		MODEL		MIN.		SEC.		
	PRESSURE		POTTER		PS-10				50		
DRY PIPE OPERATING TEST	DRY VALVE					Q.O.D.					
	MAKE		MODEL		SERIAL NUMBER		MAKE		MODEL		SERIAL NUMBER
	TYCO		DPV-1								
	TIME TO TRIP THRU TEST PIPE		WATER PRESSURE		AIR PRESSURE		TRIP POINT AIR PRESSURE		Time Water Reached Test Outlet		Alarm Operated Properly
	MIN. SEC.		PSI		PSI		PSI		MIN. SEC.		MIN. SEC.
WITHOUT Q.O.D.		30		83		41		12		50 50	
WITH Q.O.D.											
IF NO, EXPLAIN:											

OPERATION: PNEUMATIC ELECTRIC HYDRAULIC

PIPING SUPERVISED YES NO DETECTING MEDIA SUPERVISED? YES NO

DOES THE VALVE OPERATE FROM THE MANUAL TRIP AND/OR REMOTE CONTROL? YES NO

~~DRUGS & PRESCRIPTION VALVES~~

IS THERE AN ACCESSIBLE FACILITY IN EACH CIRCUIT FOR TESTING? YES NO
IF NO, EXPLAIN:

MAKE	MODEL	Does each circuit operate supervision loss alarm?		Does each circuit operate valve release?		Maximum time to operate release	
		YES	NO	YES	NO	MIN.	SEC.

TEST DESCRIPTION

HYDROSTATIC: Hydrostatic tests shall be made at not less than 200 psi (13.6 bars) for two hours or 60 psi (3.4 bars) above static pressure in excess of 150 psi (10.3 bars) for two hours. Differential dry-pipe valve clappers shall be left open during test to prevent damage. All aboveground piping leakage shall be stopped.
PNEUMATIC: Establish 40 psi (2.7 bars) air pressure and measure drop which shall not exceed 1-1/2 psi (0.1 bars) in 24 hours. Test pressure tanks at normal water level and air pressure and measure air pressure drop which shall not exceed 1-1/2 psi (0.1 bars) in 24 hours.

ALL PIPING HYDROSTATICALLY TESTED AT 200 PSI FOR 2 Hrs. IF NO, STATE REASON
DRY PIPING PNEUMATICALLY TESTED? YES NO
EQUIPMENT OPERATES PROPERLY? YES NO

TESTS

DRAIN TEST 83 PSI READING OF GAUGE LOCATED NEAR WATER SUPPLY TEST PIPE. RESIDUAL PRESSURE WITH VALVE IN TEST PIPE OPEN WIDE 77 PSI

Underground mains and lead-in connections to system risers shall be flushed before connection made to sprinkler piping.
VERIFIED BY COPY OF THE FORM NUMBER 85B? YES NO OTHER EXPLAIN
FLUSHED BY INSTALLER OF UNDERGROUND SPRINKLER PIPING? YES NO

~~BLANK TESTING GASKETS~~

NUMBER USED LOCATIONS NUMBER REMOVED

WELDING

WELDED PIPING? YES NO IF YES.....
DO YOU CERTIFY AS THE SPRINKLER CONTRACTOR THAT WELDING PROCEDURES COMPLY WITH THE REQUIREMENTS OF AT LEAST AWS D10.9, LEVEL AR-3? YES NO
DO YOU CERTIFY THAT THE WELDING WAS PERFORMED BY WELDERS QUALIFIED IN COMPLIANCE WITH THE REQUIREMENTS OF AT LEAST AWS D10.8, LEVEL AR-3? YES NO
DO YOU CERTIFY THAT WELDING WAS CARRIED OUT IN COMPLIANCE WITH A DOCUMENTED QUALITY CONTROL PROCEDURE TO INSURE THAT ALL DISCS ARE RETRIEVED, THAT OPENINGS IN PIPING ARE SMOOTH, THAT SLAG AND OTHER WELDING RESIDUE ARE REMOVED, AND THAT INTERNAL DIAMETERS OF PIPING ARE NOT PENETRATED? YES NO

HYDRAULIC DATA NAMEPLATE

NAMEPLATE PROVIDED? YES NO
IF NO, EXPLAIN:

REMARKS

DATE LEFT IN SERVICE WITH ALL CONTROL VALVES OPEN:
4-26-10

NAME OF INSTALLING CONTRACTOR SIMPLEXGRINNELL

SIGNATURES

FOR PROPERTY OWNER (Signed) [Signature] TITLE OWNER DATE 4-26-10
FOR INSTALLING CONTRACTOR (Signed) [Signature] TITLE Installation DATE 4-26-10

ADDITIONAL EXPLANATION AND NOTES:

Lannie Dobson - Chiang Mai restaurant, 50 Washington Ave

From: "Hinman, Tim" <thinman@simplexgrinnell.com>
To: <ldobson@portlandmaine.gov>
Date: 7/16/2010 9:06 AM
Subject: Chiang Mai restaurant, 50 Washington Ave
CC: "Doughty, Paul" <PDoughty@simplexgrinnell.com>

Hi Lannie,

Our Paul Doughty said he's been in communication with you about some permits that the City believes were applied for by SimplexGrinnell, including the Chiang Mai restaurant at 50 Washington Ave (?). SimplexGrinnell did not apply for a permit as this particular location.

As you may recall from about a month ago, 3 permits were mailed twice to SimplexGrinnell. I mailed them back the first time and hand delivered them the second time. Since they were not our permits, I did not keep any records/copies of them, but I believe that the Chiang Mai location was one of those permits. Don't know what party applied for this permit, but my suggestion would be to contact someone at the Chiang Mai location. If the permit was for a kitchen hood fire suppression system, the installer should have an inspection tag with their name on it attached to the fire suppression system cylinder and emergency actuation station for that system. Whosever name is on that inspection tag is likely the party that applied for the permit.

Hope this helps.

Tim Hinman

Fire Suppression Sales Rep

SimplexGrinnell District #147

20 Thomas Drive

Westbrook, ME 04092

tel: 207-482-2335

cell: 207-415-7475

