



| NFPA 2009: CODE DATA | |
|---|---|
| PORTLAND FENCING CENTER | |
| OVERALL BUILDING - UNSEPARATED MIXED USE | F-1 |
| USE GROUP CLASSIFICATION - TENANT SPACE | EXISTING BUSINESS GROUP B |
| OCCUPANT LOAD: Existing Business Ground Floor | 33 |
| TYPE OF CONSTRUCTION | V (000) |
| SUITE AREA (Portland Fencing Center) | 3,300 sf |
| TOTAL BUILDING AREA | 10,000 sf |
| BUILDING HEIGHT | 35'-0" |
| FIRE SUPPRESSION: | NO SPRINKLER SYSTEM |
| FIRE WALLS AND PARTY WALLS | 1 HOURS with 45 min. DOORS |
| STAIR ENCLOSURES | 1 HOURS with 45 min. DOORS |
| SHAFTS | NONE USED |
| EXIT ACCESS CORRIDORS | NONE USED |
| INTERIOR LOAD BEARING WALLS | 0 HOURS |
| STRUCTURAL MEMBER SUPPORTING WALL | 0 HOURS |
| FLOOR CONSTRUCTION | 0 HOURS |
| ROOF CONSTRUCTION | 0 HOURS |
| FIRE EXTINGUISHERS | LOCATIONS TO BE FIELD VERIFIED BY FIRE CHIEF PRIOR TO INSTALLATION |
| FLAME SPREAD RATINGS: | |
| INTERIOR FINISH REQUIREMENTS | |
| REQUIRED VERTICAL EXITS | CLASS A OR CLASS B |
| CORRIDORS PROVIDING EXIT ACCESS | CLASS A OR CLASS B |
| ROOMS OR ENCLOSED SPACES | CLASS A OR CLASS B |
| INTERIOR FLOOR FINISH REQUIREMENTS | |
| EXISTS | CLASS A OR CLASS B |
| EXIT ACCESS CORRIDORS | CLASS A OR CLASS B |
| OTHER SPACES | CLASS A OR CLASS B OR CLASS C |
| GENERAL NOTES | 1. ALL PENETRATIONS OF FIRE RATED WALLS AND FLOORS SHALL BE SEALED WITH PROPER APPROVED MATERIALS 2. ALL WORK SHALL CONFORM TO LOCAL AND STATE CODES, ORDINANCES, AND REQUIREMENTS, ACCESSIBILITY PER A.D.A.G. |

| REVISIONS | | |
|-----------|------------|--|
| # | DATE | DESCRIPTION |
| 1 | 07.26.2013 | ISSUED FOR CITY OF PORTLAND FIRE PREVENTION REVIEW |
| 2 | 07.30.2013 | ISSUED FOR CITY OF PORTLAND FIRE PREVENTION REVIEW - REVISED |

| | |
|----------------|----------|
| DATE: | 07.30.13 |
| PROJECT #: | 070413 |
| DRAWN BY: | |
| CHECKED BY: | |
| DRAWING SCALE: | |

SHEET TITLE