

Tim Hill Fine Woodworking, LLC

11 Little Wing Lane  
 Gorham, Maine  
 04038

# Estimate

DATE	ESTIMATE #
6/6/2013	426

NAME / ADDRESS
Portland Fencing

P.O. NO.	REP	PROJECT

ITEM	DESCRIPTION	QTY	COST	TOTAL
Build	Building of new raised floor at Riverside drive, Portland Maine location. 2388 sq ft total. Sub floor type constructed with 3/4" T and G plywood. Net height		0.00	0.00
Materials	seam tape	1	42.99	42.99
Materials	#6 1 1/2 fasteners	1	122.85	122.85
Materials	3/4 x 4 x 8 T and G plywood.	80	46.63	3,730.40
Materials	2 x 3 x 8' Fir under structure	262	2.93	767.66
Materials	Bits	12	1.05	12.60
Materials	Polyurethane	6	45.00	270.00
Materials	Roller for applying poly	5	6.25	31.25
Materials	Sanding materials, and lg sander rental	1	130.00	130.00
Labor	Labor associated with the build	1	4,000.00	4,000.00
Delivery	allocation for delivery of all materials	1	300.00	300.00
			<b>Sales Tax (5.0%)</b>	\$0.00
			<b>TOTAL</b>	\$9,407.75