

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK



CITY OF PORTLAND BUILDING PERMIT

This is to certify that

YOUNG MARY E ETALS TRUSTEES /Tim Hill Fine
Woodworking

Located at

987 RIVERSIDE ST

PERMIT ID: 2013-01308

ISSUE DATE: 08/05/2013

CBL: 329 B011001

has permission to **Change of use to add a recreational fencing use with installation of flooring and lighting within the building**

provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statues of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of the buildings and structures, and of the application on file in the department.

Notification of inspection and written permission procured before this building or part thereof is lathed or otherwise clsoed-in. 48 HOUR NOTICE IS REQUIRED.

A final inspection must be completed by owner before this building or part thereof is occupied. If a certificate of occupancy is required, it must be procured prior to occupancy.

/s/ Chris Pirone

/s/ Jon Rioux

Fire Official

Building Official

**THIS CARD MUST BE POSTED ON THE STREET SIDE OF THE PROPERTY
THERE IS A PENALTY FOR REMOVING THIS CARD**

Approved Property Use - Zoning

Commercial bakery (Izzy's) & Recreational
use (fencing

Building Inspections

Fire Department

Classification:

Business

ENTIRE

2009 Business

BUILDING PERMIT INSPECTION PROCEDURES
Please call 874-8703 (ONLY)
or email: buildinginspections@portlandmaine.gov

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the city of Portland Inspections Services for the following inspections. Appointments must be requested 48 to 72 hours in advance of the required inspection. The inspection date will need to be confirmed by this office.

- **Please read the conditions of approval that is attached to this permit!! Contact this office if you have any questions.**
- **Permits expire in 6 months. If the project is not started or ceases for 6 months.**
- **If the inspection requirements are not followed as stated below additional fees may be incurred due to the issuance of a "Stop Work Order" and subsequent release to continue.**
- **Per Section 107.3.1 of the Maine Uniform Building and Energy Code (MUBEC). One set of printed approved stamped construction documents shall be kept at the site of work and shall be open to inspection by building officials.**

REQUIRED INSPECTIONS:

Close-in Plumbing/Framing

Electrical - Commercial

Certificate of Occupancy/Final

The project cannot move to the next phase prior to the required inspection and approval to continue, REGARDLESS OF THE NOTICE OF CIRCUMSTANCES.

IF THE PERMIT REQUIRES A CERTIFICATE OF OCCUPANCY, IT MUST BE PAID FOR AND ISSUED TO THE OWNER OR DESIGNEE BEFORE THE SPACE MAY BE OCCUPIED.

City of Portland, Maine - Building or Use Permit		Permit No: 2013-01308	Date Applied For: 06/24/2013	CBL: 329 B011001
389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716				
Proposed Use: Change the use from one unit within the building for a Sport Fencing Program	Proposed Project Description: Change of use to add a recreational fencing use with installation of flooring and lighting within the building			
Dept: Zoning Status: Approved w/Conditions Reviewer: Marge Schmuckal Approval Date: 06/25/2013				
Note:				Ok to Issue: <input checked="" type="checkbox"/>
Conditions:				
1) This permit is being approved on the basis of plans submitted. Any deviations shall require a separate approval before starting that work.				
2) Separate permits shall be required for any new signage.				
Dept: Building Status: Approved w/Conditions Reviewer: Jon Rioux Approval Date: 07/29/2013				
Note: Training and skill development not within a school or academic program.				Ok to Issue: <input checked="" type="checkbox"/>
Conditions:				
1) 602.4.4 Floors. Floors shall be without concealed spaces.				
Floors shall not extend closer than 0.5 inch to walls. Such 0.5-inch space shall be covered by a molding fastened to the wall and so arranged that it will not obstruct the swelling or shrinkage movements of the floor.				
2) Flooring must comply with Section 1003.5 Elevation change. Field modification(s) may be required (plans do not indicate the proposed floor transition and existing elevation).				
3) Floor elevation shall comply with Section 1008.1.5. There shall be a floor or landing on each side of a door. Such floor or landing shall be at the same elevation on each side of the door. Landings shall be level except for exterior landings, which are permitted to have a slope not to exceed 0.25 unit vertical in 12 units horizontal (2-percent slope).				
4) Permit approved based upon information provided by the design professional. Any deviation from the final approved plans requires separate review and approval prior to work.				
5) 713.3 Fire-resistance-rated walls. Penetrations into or through fire walls, fire barriers, smoke barrier walls and fire partitions shall comply with Sections 713.3.1 through 713.3.3. Penetrations in smoke barrier walls shall also comply with Section 713.5.				
6) Separate permits are required for any electrical: plumbing, sprinkler, fire alarm, HVAC systems, commercial hood exhaust systems and fuel tanks. Separate plans may need to be submitted for approval as a part of this process.				
7) A State Fire Marshal permit may be required for this project, contact at 207-626-3880 or http://www.maine.gov/dps/fmo/plans/about_permits.html				
Dept: Fire Status: Approved w/Conditions Reviewer: Chris Pirone Approval Date: 08/02/2013				
Note:				Ok to Issue: <input checked="" type="checkbox"/>
Conditions:				
1) A separate Suppression System Permit is required for all new suppression systems, including standpipe systems, and sprinkler work effecting more than 20 heads. This review does not include approval of system design or installation.				
2) Construction or installation shall comply with City Code Chapter 10.				
3) Application requires State Fire Marshal approval.				
4) A separate Fire Alarm Permit is required for new systems; or for work effecting more than 5 fire alarm devices; or replacement of a fire alarm panel with a different model. This review does not include approval of fire alarm system design or installation.				
5) Shall comply with 2009 NFPA 101 Chapter 39 Existing Business Occupancy				
6) A firefighter Building Marking Sign is required.				
7) Fire extinguishers are required per NFPA 1.				

- 8) All means of egress to remain accessible at all times.
- 9) Emergency lights and exit signs are required. Emergency lights and exit signs are required to be labeled in relation to the panel and circuit and on the same circuit as the lighting for the area they serve.
- 10 Any cutting and welding done will require a Hot Work Permit from Fire Department.
- 11 Fire walls, fire barriers, fire partitions, smoke barriers and smoke partitions or any other wall required to have protected openings or penetrations shall be effectively and permanently identified with signs or stenciling in accessible concealed floor, floor-ceiling or attic spaces at intervals not exceeding 30 feet with lettering not less than 0.5 inches in height.
- 12 Notice: The first scheduled final inspection fee is at no charge. Additional inspections shall be billed at \$75 for each inspector.
- 13 Through-penetrations and membrane penetrations in fire walls, fire barrier walls, and fire resistance rated horizontal assemblies shall be protected by firestop systems or devices in conformance with NFPA 101:8.3.5 (ASTM E 814 or ANSI/UL 1479). Providing firestop labels at each firestop system or device and an onsite manual containing the detail for each firestop system or device used for the project will streamline final inspection approvals.
- 14 **The fire alarm system design shall be evaluated for the renovated areas by an NICET IV certified interior fire alarm designer or a licensed engineer for compliance with the code. A compliance letter is required prior to the final inspection.**
A current inspection sticker from an approved fire alarm inspection company is required prior to the final inspection.
- 15 The approved plans with the Building Department Approved stamp shall be maintained on site for inspection.
- 16 Street addresses shall be marked on the structure and shall be as approved by the City E-911 Addressing Officer. Contact Michelle Sweeney at 874-8682 for further information.