


PROVIDE ADDITIONAL #5 REBAR

TYPICAL VERTICAL WALL CONSTRUCTION JOINT 1" = 1'-0"

2

5





1. COORDINATE WITH ARCHITECT THE TYPE AND THICKNESS OF VAPOR BARRIER, IF APPLICABLE. 2. CONTRACTOR SHALL COORDINATE CONSTRUCTION JOINT LOCATION SUCH THAT THEY COINCIDE WITH CONTRACTION JOINT LOCATIONS SHOWN ON PLAN.

3. APPLY LIQUID BONDBREAKER TO FULL DEPTH OF CONSTRUCTION JOINT.

	t: 207.553	design group, inc. Unit 206, Portland, Maine 04103 5.2070 - f: 207.553.2072 basedesigngroup.com
Key Pl	an	
Sheet Issue / Revision		
No. 1	Date 04/27/17	Description Permit Set
Seal/Signature MIGUEL MIGUEL BETANCOURT No. 14038 SONAL ENGLINE Project		
UNIT 5 - LOADING DOCK 1039 RIVERSIDE STREET PORTLAND, MAINE		
Client HardyPond Construction Portland, Maine		
Title TYPICAL FOUNDATION DETAILS		
Project Drawn	t Number By	17068-0 MB
Checko	ed By	MB
S-300		
Scale As indicated		