Package Steel Systems, Inc. Manufacturer of the *Package Steel Buildi*

15 Harback Road
Sutton, MA 01590

Tel 800.225.7242 | Tel 508.865.5871
Fax 508.865.9130

sales@pac
packagesteel.com

CITY OF PORTLAND, MAINE — RESURGAM
Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 02/29/16

Customer:	Project:	
Biskup Construction Inc.	Moongate Properties	Date: 12/18/15
16 Danielle Drive	1039 Riverside Street	Project ID: 1511-038
Windham, ME 04062	Portland, ME 04103	

Width:	Length:	Lt. Eave:	Rt. Eave:	Pitch:
95.00 ft.	115.00 ft.	20.00 ft.	21.98 ft.	0.25:12

To Whom It May Concern,

The building is designed and fabricated in accordance with the order documentation; The 13th Edition of The American Institute of Steel Construction (AISC) "Manual of Steel Construction"; the 2007 Edition of the North American United States Manual (NAUS); the MBMA Low Rise Building Systems Manual and any applicable sections of the American Welding Society (AWS D1.1) specifications for the loads indicated.

The criteria for application of design loads are as follows:

GOVERNING CODE: IBC 09 BUILDING CLASS: II - Normal

Dead Load:	5.00 psf	Ground Snow,Pg:	60.00 psf
Collateral Load:	5.00 psf	Flat Roof Snow,Pf:	42.00 psf
Live Load:	20.00 psf	Snow Exp. Factor,Ce:	1.00
Live Load Reduction:	No	Snow Therm. Factor,Ct:	1.00
Basic Wind Speed:	100.00 mph	Snow Imp. Factor,Is:	1.00
Wind Exposure:	B	Seis.Imp. Factor,Ie:	1.00
Enclosure Type:	Closed	Seis.Design Cat.,SDC:	C
Wind Imp. Factor,Iw:	1.00	Site Class:	E
Int.Pres.Coef.,GCpi:	+/-0.18	Spec.Resp.Coef.,Sds:	0.486
Auxiliary Load:	(4)400# Unit Heaters Suspended off Purlins	Spec.Resp.Coef.,Sd1:	0.182

Note:
Additional components, such as panel and trims, may be fabricated and provided for use in a Package Steel Systems, Inc. (PSS) building by other manufacturers. This Letter of Certification applies solely to the building frames and components as supplied by PSS and specifically excludes any foundation, masonry, general contract work, and materials not furnished by PSS. It also excludes any unauthorized modification to the PSS framing systems. The Buyer is responsible for verifying that the loads, specified above, are in compliance with those required by the local regulatory authorities.

Sincerely,

STATE OF MAINE
ZACK R. McCAIN, III
6669
REGISTERED PROFESSIONAL ENGINEER

Zack R McCain III, P
Engineering Manager