FOOTING & PIER SCHEDULE

LOCATION	FOOTING SIZE	FOOTING REBAR	PIER SIZE	PIER REBAR	ANCHOR BOLTS
1A, 1B, 1C, 1D, 1E	3'-6" X 3'-6" X 1'-0"	4 #5 E.W BOTT.	12" X 12"	2 #5 "U" BARS, 15" X 48" X 12"	3/4" X 18"
2A, 5A	5'-0" X 5'-0" X 1'-0"	6 #5 E.W BOTT.	16" X 16"	4 #5 "U" BARS, 15" X 48" X 12"	3/4" X 18"
3A, 4A	6'-6" X 6'-6" X 1'-0"	7 #5 E.W. BOTT.	33" X 16"	6 #5 "U" BARS, 15" X 48" X 12"	3/4" X 18"
6A, 6B, 6C, 6D, 6E	3'-6" X 3'-6" X 1'-0"	4 #5 E.W. BOTT.	12" X 12"	2 #5 "U" BARS, 15" X 48" X 12"	3/4" X 18"
2C, 3C, 4C, 5C	7'-0" X 7'-0" X 1'-2"	8 #5 E.W. BOTT.	24" X 24"	6 #5 "U" BARS, 15" X 48" X 12"	3/4" X 18"
2E, 3E, 4E, 5E	6'-6" X 6'-6" X 1'-0"	7 #5 E.W. BOTT.	16" X 16"	4 #5 "U" BARS, 15" X 48" X 12"	3/4" X 18"

"U" BARS

GENERAL NOTES:

ALL FOOTINGS TO BEAR ON 6" OF 3/4" STONE ATOP UNDISTURBED SOIL, WITH MIN. ALLOWABLE NET, BEARING CAPACITY OF 2,000 PSF.

MINIMUM COMPRESSIVE STRENGTH OF CONCRETE, 28 DAYS = 3,000 PSI.

MINIMUM YIELD STRENGTH OF REINF. STEEL = 60,000 PSI.

REINF. STEEL SHALL BE FABRICATED AND INSTALLED IN ACCORDANCE WITH THE CRSI MANUAL OF STANDARD PRACTICE, LATEST EDITION

HEADED ANCHOR BOLTS TO BE A 307

CONCRETE WORKMANSHIP SHALL CONFORM TO THE REQUIREMENTS OF ACI 318 AND "SPECIFICATIONS FOR STRUCTURAL CONCRETE FOR BUILDINGS" ACI 301, LATEST EDITION

BACKFILL BOTH SIDES OF ALL WALLS SIMULTANEOUSLY

BISKUP CONSTRUCTION, INC.
16 DANIELLE DRIVE
WINDHAM, MAINE 04062
TEL. (207) 892-9800
FAX. (207) 892-9895
WWW.BISKUPCONSTRUCTION.COM

CONSULATANT
ASSOCIATED DESIGN PARTNERS INC.
80 Leighton Road
Falmouth, Maine 04105
Office: (207) 878-1756
Fax: (207) 878-1788
E-Mail: adp@adpengineering.com

STAMP

STATE OF MAINE
AARON S. WILSON
NO. 10428
LICENSED
PROFESSIONAL ENGINEER

PROJECT:
MOONGATE PROPERTIES LLC
1039 RIVERSIDE STREET
UNIT #9
PORTLAND, MAINE

REVISIONS

DATE	DESCRIPTION

DATE: 12/28/2015
SCALE: 1/8" = 1'-0"
DESIGNER: AW
CHECKED BY: JB

© COPYRIGHT
BISKUP CONSTRUCTION, INC.

SHEET TITLE

FOUNDATION PLAN

SHEET NUMBER

S-1

SHEET 1 OF 3

Reviewed for Code Compliance
Inspection Division
Portland, Maine
Date: 02/29/16