SPLICE BOLT TABLE						
Mark	Qty Top	Bot	Int	Type	Dia	Length
SP-1	4	4	0	A325	0.625	2.00
SP-2	2	2	0	A325	0.625	1.75

CAP PLATE BOLTS				
Mark	Qty	Type	Dia	Length
EC-8	4	A325	0.625	1.50
EC-7	4	A325	0.625	1.50
EC-6	4	A325	0.625	1.50

FLANGE BRACE TABLE			
∇ ID	MARK	LENGTH (in)	SIDES
1	FB25.6A	25.630	1
2	FB23.4A	23.380	1
3	FB25.1A	25.130	1

FBxA - 1-1/2'x1-1/2'x1/8'
FBxB - 2'x2'x1/8'
FBxC - 2-1/2'x2-1/2'x3/16'

MEMBER TABLE						
Mark	Weight	Web Depth Start/End	Web Plate Thick	Web Plate Length	Outside Flange W x Thk x Length	Inside F W x Thk
RF2-1	323	8.5/19.0	0.125	230.0	5 x 1/4' x 229.6 5 x 1/4' x 28.3	5 x 1/4
RF2-2	431	12.0/12.0 12.0/12.0	0.125 0.125	101.0 240.0	5 x 1/4' x 340.7	5 x 1/4
RF2-3	497	12.0/12.0 12.0/12.0	0.125 0.125	164.3 240.0	5 x 1/4' x 404.3	5 x 1/4
RF2-4	422	12.0/12.0 12.0/12.0	0.125 0.125	95.2 240.0	5 x 1/4' x 335.2	5 x 1/4
RF2-5	386	19.0/ 9.0 9.0/ 8.3	0.125 0.125	236.9 16.0	5 x 1/4' x 27.9 5 x 1/4' x 252.9	5 x 5/16' x 236.6
EC-8	206	W8X10				
EC-7	211	W8X10				
EC-6	216	W8X10				

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 02/29/16

FRAME CROSS SECTION: FRAME LINE 6

REV.	DESCRIPTION:	DATE:	DRAFT	ENG.
3				
2				
1				
0	PRELIMINARY DRAWING: NOT FOR CONSTRUCTION / FOR PERMIT ONLY	CURRENT REVISION: 0		

PACKAGE STEEL SYSTEMS, INC.		Biskup Construction Inc.	
PROJECT	Moongate Properties	RIGID FRAME X-SECTION	
ID	1511-038	DESIGN: ZRM	DESIGN CHECK:
PROJECT	1039 Riverside Street	DRAFT: TMZ	DRAFT CHECK:
ADDRESS	Portland, ME 04103	DATE: 12/07/15	DRAWING: FRXS-2

PACKAGE