



Quantity: 1
RO Size: 30.5" X 54.5"
Unit Size: 30" X 54"



Row 1 1556 Double Hung - Vent - 1 Units - 30W x 54H
*** DIMENSIONS ***
30W x 54H
*** FRAME ***
East, Vinyl, Frame Type - Fin, Exterior Color - White
*** GLASS ***
Glazing Type - Insulated, Glass Tint - Clear, Low-E, Argon Gas, Glass Strength - DSB
*** SCREEN ***
Screen - Rollform Full, Screen Mesh Type - Charcoal Fiber, Screens Packed Separately - Yes
*** WRAPPING ***
Extension Jamb - 6 9/16 Wood, Extension Jamb Type - Primed Finger Jointed, Number of Jamb Sides - Four Sides, J-Channel - Integral
*** NFRC ***
Series 1556::DoubleHung, U-Factor::0.27, SHGC::0.28, VT::0.51
*** Performance ***
Series 1556::DoubleHung, Calculated Positive DP Rating::50.13, Calculated Negative DP Rating::50.13, DP Rule ID::1556 DH, Rating Type::DesignPressure, Structural Rating::R-PG30°, Water Rating::4.60, FL ID::N/A

1556 Double Hung - Vent - CustomCustom


Quantity: 2
RO Size: 60.125" X 54.5"
Unit Size: 59.625" X 54"



Row 1 1556 Double Hung - Vent / Vent - 2 Units - 59.625W x 54H
*** DIMENSIONS ***
Unit 1 30W x 54H
Unit 2 29.5W x 54H
*** FRAME ***
East, Vinyl, Frame Type - Fin, Exterior Color - White
*** GLASS ***
Glazing Type - Insulated, Glass Tint - Clear, Low-E, Argon Gas, Glass Strength - DSB
*** SCREEN ***
Screen - Rollform Full, Screen Mesh Type - Charcoal Fiber, Screens Packed Separately - Yes
*** WRAPPING ***
Wrapping Group 1 Extension Jamb - 6 9/16 Wood, Extension Jamb Type - Primed Finger Jointed, Number of Jamb Sides - Four Sides, J-Channel - IntegralWrapping Group 0
*** MULLS ***
Vertical CommonFrame 0.125" thick, 54" in length
*** NFRC ***
NFRC 1 Series 1556::DoubleHung, U-Factor::0.27, SHGC::0.28, VT::0.51
NFRC 2 Series 1556::DoubleHung, U-Factor::0.27, SHGC::0.28, VT::0.51
*** Performance ***
Performance 1 Series 1556::DoubleHung, Calculated Positive DP Rating::50.13, Calculated Negative DP Rating::50.13, DP Rule ID::1556 DH, Rating Type::DesignPressure, Structural Rating::R-PG30°, Water Rating::4.60, FL ID::N/A
Performance 2 Series 1556::DoubleHung, Calculated Positive DP Rating::50.13, Calculated Negative DP Rating::50.13, DP Rule ID::1556 DH, Rating Type::DesignPressure, Structural Rating::R-PG30°, Water Rating::4.60, FL ID::N/A

1556 Double Hung - Vent - CustomCustom

Quantity: 1
RO Size: 71.375" X 80"
Unit Size: 70.875" X 79.5"



Row 1 1615 Two Panel Setup Patio Door - XO - 1 Units - 70.875W x 79.5H
*** DIMENSIONS ***
70.875W x 79.5H
*** FRAME ***
East, Vinyl, Frame Type - Fin, Groove Cover, Jamb Cover, Exterior Color - White
*** GLASS ***
Glazing Type - Insulated, Dual, Glass Tint - Clear, Low-E, Argon Gas, Tempered Location - Full, Glass Strength - DSB
*** SCREEN ***
Screen - Silencia, Screens Packed Separately - No
*** HARDWARE ***
2-Point Non-Keyed, Hardware Color - White, Foot Lock
*** NFRC ***
Series 1615::DoubleSlidingDoor, U-Factor::0.28, SHGC::0.28, VT::0.51
*** Performance ***
Series 1615::DoubleSlidingDoor, Calculated Positive DP Rating::-1, Calculated Negative DP Rating::-1, DP Rule ID::1615-2 PD, Rating Type::DesignPressure, Structural Rating::, Water Rating::, FL ID::

1615 Two Panel Setup Patio Door - XO - 6068