

Walls

- 2x4 studs @ 16" o.c.
- R-13 insulation (future)
- 7/16 sheathing
- vinyl siding
- typer-Norpat barrier
- Floor system

- 14" clear span I joists @ 16" o.c.
- 1 1/2" Rim Joist
- Hangers on joists to Rim
- 5/8 sheetrock ceiling
- 3/4" T & G Decking
- R-30 insulation



Roof

- 2x6 ceiling joists - R-30 Attic insulation (future)
- 2x8 Rafters @ 16" o.c.
- 2x10 Ridge
- 7/16 OSB Sheathing
- 30 year architectural shingles
- 2x4 collarties