Inspections Division
Date: 06/27/14

# 1 - Pass Through Section ~ 3/4 in = 1 ft

| DOOR SCHEDULE | | | | | | |
|---|---|---|---|---|---|---|
| NUMBER | QTY | FLOOR | SIZE | WIDTH | HEIGHT | COMMENTS |
| D01 | 1 | 1 | 2668 R IN | 30 " | 80 " | LEAF RELOCATED FROM FRONT CLOSET |
| D02 | 1 | 1 | 3068 L EX | 36 " | 80 " | WITH INTEGRAL BLINDS |
| D03 | 1 | 2 | 1468 L IN | 16 " | 80 " | |
| D04 | 1 | 2 | 2666 L IN | 30 " | 78 " | |
| D05 | 2 | 2 | 2668 R IN | 30 " | 80 " | |

| WINDOW SCHEDULE | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| NUMBER | QTY | FLOOR | WIDTH | HEIGHT | EGRESS | TEMPERED | DESCRIPTION | CODE | MANUFACTURER |
| W01 | 3 | 1 | 29 1/2 " | 59 1/2 " | | | DOUBLE HUNG | IFDH2650 | INTEGRITY |
| W02 | 3 | 1 | 31 1/2 " | 53 1/2 " | | | DOUBLE HUNG | IFDH2846 | INTEGRITY |
| W03 | 1 | 2 | 23 1/2 " | 41 1/2 " | | YES | DOUBLE HUNG | IFDH2036 | INTEGRITY |
| W04 | 3 | 2 | 35 3/4 " | 59 1/2 " | YES | | DOUBLE HUNG | IFDH3050 | INTEGRITY |

WINDOWS: MARVIN INTEGRITY, WHITE, NO SDL, WHITE HARDWARE, FACTORY APPLIED 3 1/2" FLAT CASING AND HISTORIC SILL

LICENSED ARCHITECT
KEVIN J. MOQUIN
ARC3016
STATE OF MAINE

0 1' 2' 4'
Graphic Scale 1/4" = 1'-0"


*Kevin Moquin Architect*
*Maine Licensed Architect*
*Portland, ME*
*www.km-a.me*
*kevin@km-a.me | (207) 615-6421*


***Nancy & Hugh Hill***
***Proposed Renovation***
*Eastlawn Road, Portland, ME*
**PERMIT SET**
**6-4-2014 REV**

**SCHEDULES**
**I1**