

Sequence of Operations

1519 Forest Ave	Audio/visual activation	Activate audible/visual signal at FACP & Annunciator	Device Description at FACP & Annunciator	Shutdown of HVAC equipment	Log event in system history	Activate Elevator Fire Hat	Activate Elevator primary or secondary control	Activate Elevator shunt trip	Silence of audible devices Including FACP & annunciator	Event acknowledgement	Reset of all system functions and all visual devices	Remote transmission to Central Station A=alarm; T=trouble; S=Supervisory; L = log only	Remote indicator
Manual Pull Stations	X	X	X		X							A	
Smoke detectors common area	X	X	X		X							A	
Water Flow Monitor	X	X	X		X							A	
FACP/annunciator silence button		X	X		X			X				L	
FACP/annunciator acknowledge button		X	X		X				X				
FACP/annunciator reset button		X	X		X					X		L	
Removal of any device		X	X		X							T	
Ground fault		X	X		X							T	
System wiring "open"		X	X		X							T	
AC Power loss		X	X		X							T	
Secondary power loss		X	X		X							T	
Telephone line loss		X	X		X							T	